



RESULTS

Below are the results from the first and second rounds of testing of drinking water for lead that was conducted at Stonewall Public Schools - McLish Middle School. The initial sampling event occurred on October 21, 2021. The resampling event occurred on November 18, 2022.

In the initial sampling, sixteen (16) outlets were tested resulting in a total of thirty-two (32) samples being sent to the lab.

- Seventeen (17) samples had no detectable level of lead.
- Fourteen (14) samples had a low detection of lead between 1.0 and 14.9 µg/L.
- One (1) sample had a high detection of lead equal to or above 15.0 µg/L.

In the resampling, one (1) outlet was tested resulting in a total of two (2) samples being sent to the lab.

- Zero (0) samples had no detectable level of lead.
- One (1) sample had a low detection of lead between 1.0 and 14.9 µg/L.
- One (1) sample had a high detection of lead equal to or above 15.0 µg/L.

The table below shows all sample results. Sample results are in micrograms per liter, shown as µg/L. For more information on how to read this report, please see our **Results Interpretation Fact Sheet**.

Sample ID	Comments	First Draw (µg/L)	Flush (µg/L)	Remedial Action	First Draw (µg/L)	Flush (µg/L)
		Initial Sampling			Resampling	
Non-Detect (<1.0 µg/L)						
1-1-CAFÉ-IM	Cafeteria building; Hoshizaki ice machine in cafeteria	<1.0	<1.0	N/A		
2-1-HALL-WC1	Main building; Elkay water cooler in far-left hallway	<1.0	<1.0	N/A		
2-1-MILLER-CF	Main building; Classroom faucet in Miller classroom	<1.0	<1.0	N/A		
3-1-GYM-WC1	Gym; Elkay water cooler in hallway on left side of gym	<1.0	<1.0	N/A		
3-1-GYM-WC2	Gym; Elkay water cooler in hallway on right side of gym	<1.0	<1.0	N/A		

Sample ID	Comments	First Draw (µg/L)	Flush (µg/L)	Remedial Action	First Draw (µg/L)	Flush (µg/L)
		Initial Sampling			Resampling	
6-1-PREK-WC1	PreK building; Elkay water cooler in hallway on North side	<1.0	<1.0	N/A		
Low Detection (1.0 - 14.9 µg/L)						
2-1-HALL-WC2	Main building; Elkay water cooler in right hallway	<1.0	1.0			
1-1-KIT-KF1	Cafeteria building; Kitchen faucet in concessions stand; right side near dish pit	1.1	<1.0			
6-1-PREK-WC2	PreK building; Elkay water cooler in hallway on South side	1.8	1.7			
1-1-KIT-KF2	Cafeteria building; Kitchen faucet on handwash station in kitchen	1.9	<1.0			
1-1-CONC-KF	Cafeteria building; Kitchen faucet in concessions stand; left side	2.0	<1.0			
4-1-LIB-WC	Library; Elkay water cooler in library	3.3	2.5			
6-1-CART-CF	PreK building; Classroom faucet in Carter classroom	4.9	<1.0			
6-1-BARB-CF	PreK building; Classroom faucet in Barbara classroom	8.7	1.3			
5-1-STEM-CF	STEM Lab; Classroom faucet in STEM lab	14.0	1.5			
High Detection (≥15.0 µg/L)						
3-1-CONC-KF	Gym; Kitchen faucet in gym concessions stand	15.2	1.5	Replaced	81.5	8.7

Building Index

1. Cafeteria
2. Main Building
3. Gym
4. Library
5. STEM Lab
6. PreK Building