

Alternative Name and Description		Sub-Option	Construction Cost (1)	Right-of-Way Cost (2)	Utility Relocation Cost (3)	Total Bridge Length (ft)	Total Retaining Wall Cast	Floor Storage Impacts (cy)	Wetlands (acres)	Streams (acres)	Johnson Creek PUA (acres)	Texoma State Park (acres)	USACE Property (acres)	Tribal Land (acres)	Hazardous Materials Site	Archeological Site 34BR11
6-2	North Offset Bridge - 57' Lake Causeway - 27.5' Land Causeway - 27.5'	A	\$144.55 M	\$1.73 M	\$ -	4,942	-	590,165	0.77	0.11	3.8	2.83	62.96	0	N	Y
	B	\$189.56 M	\$0.7 M	6,146		\$58.81 M	-811	0.67	0.06	2.2	2.83	20.65	0	N	Y	
6-3	North Offset Bridge - 57' Lake Causeway - 27.5' Land Causeway - On Existing Alignment	-	\$144.37 M	\$1.67 M	\$ -	4,942	-	595,520	0.81	0.09	3.74	2.65	64.3	0	N	Y
6-6	North Offset with Phased Bridge Construction Bridge - 27.5' Lake Causeway - 27.5' Land Causeway - 27.5'	A	\$149.84 M	\$1.69 M	\$ -	4,942	-	595,169	0.49	0.07	3.18	3.39	51.8	0	Y	Y
		B	\$156.35 M	\$1.08 M		4,942	\$35.31 M	279,876	0.49	0.07	3.18	3.39	32.61	0	Y	Y
6-14	South Offset Bridge - 57' Lake Causeway - 27.5' Land Causeway - 27.5'	-	\$150.2 M	\$2.7 M	\$ -	4,942	-	590,165	1.32	0.09	3.74	6.19	64.76	1.16	Y	Y
6-15	South Offset Bridge - 57' Lake Causeway - 27.5' Land Causeway - On Existing Alignment	-	\$149.9 M	\$2.68 M	\$ -	4,942	-	595,520	0.89	0.08	3.73	6.19	64.79	1.16	Y	Y
6-17	New Southern Alignment Land Causeway - On Existing Alignment	A	\$423.45 M	\$3.45 M	\$ -	5,422	-	1,101,425	1.09	0.09	3.73	6.56	105.16	1.43	Y	N
		B	\$148.89 M	\$1.99 M		10,625		226,348	1.09	0.09	3.73	6.56	58.97	1.43	Y	N
6-18	New Southern Alignment Land Causeway - 27.5' Offset	A	\$422.5 M	\$3.46 M	\$ -	5,422	-	1,120,416	1.49	0.08	3.74	6.34	106.15	1.43	Y	N
		B	\$147.02 M	\$2.01 M		10,625		226,348	1.49	0.08	3.74	6.34	60.06	1.43	Y	N

(1) 20% Contingency. Mitigation costs not included.

(2) 5% Contingency. ODOT provided values.

(3) Utility relocation costing information not provided at the time of the report submittal. Information is to be provided at a later date.