

MEMO



To

CHBP Grant Review

From

HNTB

Cc

ODOT

Subject

Kay County CHBP I-35 Plan Set and
Cost Estimate

Date

November 27, 2018

Attached are preliminary 90% design plans and cost estimates for consideration in the Kay County CHBP Grant Application for the I-35 Bridge Raises for JP2443215. Please note the following items as you review:

- These plans are preliminary and not for construction. These plans are 90% complete and have been submitted for the Final Plan Field Review Meeting scheduled for December 6, 2018. 100% Plans, Specs, and Estimates are due in December 2018.
- Plans and cost estimates have been provided for JP 22432(15) – I-35 Bridge Raisings, which includes eight bridge locations (Indian, Adobe, Ferguson, Chrysler, Coleman, Hartford, Highland, North) over I-35 in Kay County, Oklahoma. Also included are the plans and costs for one additional bridge location, the removal/demolition of Home Road over I-35.
- As part of the Field Assessment and corresponding memo dated 5-25-2017, it was recommended that Home Road be removed from service as it was not a good candidate for a raise considering the condition of the existing structure. This removal was subsequently approved by ODOT and later approved by the Kay County commission.
- The removal/demolition of Home Road bridge has been excluded from the Grant application.

STATE OF OKLAHOMA
DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED
STATE BRIDGE
FEDERAL AID PROJECT NO. J2-4432(015)SS
GRADE, DRAIN, SURFACE AND BRIDGE PLANS FOR
I-35 BRIDGE RAISINGS
KAY COUNTY
I-35 CONTROL SECTION NO 35-36-25
STATE JOB NO. 24432(15)

INDEX OF SHEETS

DESCRIPTION	REVISIONS	DATE
-------------	-----------	------


0001	COVER SHEET
0002	TYPICAL SECTIONS
AB01	GENERAL NOTES (BRIDGE)
AB02	SUMMARY OF PAY QUANTITIES (BRIDGE)
AR01	SUMMARY PAY QUANTITIES & NOTES (ROADWAY)
AR02	SUMMARY OF QUANTITIES (ROADWAY)
AT01	SUMMARY OF PAY QUANTITIES & NOTES (TRAFFIC)
AT02	SUMMARY OF QUANTITIES (TRAFFIC)
B001	CONSTRUCTION SEQUENCE NOTES (BRIDGE)
B002-B009	GENERAL PLAN AND ELEVATION (BRIDGE "A-G", BRIDGE "J")
B010-B014	FALSEWORK SHEETS
B015-B017	BOLSTER DETAILS
B018-B019	APPROACH SLAB DETAILS
B020	SLOPEWALL AND DRAIN DETAILS
B021-B022	HOME ROAD DEMOLITION-ROLLING ROAD BLOCK
B023	HOME ROAD DEMOLITION-CROSSOVER
B024-B027	HOME ROAD PLANS (INFORMATION ONLY)
R001-R009	STORM WATER MANAGEMENT PLAN
R010-R015	EROSION CONTROL SHEETS
R016-R025	PLAN AND PROFILE SHEETS
T001-T002	ADVANCE WARNING SIGNS (LANE CLOSURE AND SHOULDER WORK)
T003	WARNING SIGNS (TYP SECTION LINE)
T004-T011	TRAFFIC CONTROL DETAILS CROSSOVERS
T012-T013	TRAFFIC CONTROL DETAILS ROLLING ROADBLOCK
X001-X010	CROSS SECTIONS - NORTH AVE
X011-X020	CROSS SECTIONS - HIGHLAND AVE
X021-X031	CROSS SECTIONS - HARTFORD AVE
X032-X041	CROSS SECTIONS - COLEMAN RD
X042-X052	CROSS SECTIONS - CHRYSLER AVE
X053-X067	CROSS SECTIONS - FERGUSON AVE
X068-X077	CROSS SECTIONS - ADOBE ROAD
X078-X088	CROSS SECTIONS - HOME ROAD
X089-X096	CROSS SECTIONS - INDIAN ROAD

THE FOLLOWING ODOT STANDARD DRAWINGS ARE REQUIRED

ROADWAY	TRAFFIC			
SSS-1-1	TCS1-1-01	TCS9-1-01	TCS19-1-01	WSD2-1-00
TSC2-3-2	TCS2-1-00	TCS10-1-00	TCS20-1-00	WSD3-1-00
TSR-2-0	TCS3-1-01	TCS11-1-01	THRI-1-02	DU1-1-00
PCES-4-1	TCS4-1-01	TCS13-1-00	SKT-1-00	DU2-1-00
RWF2-2-1	TCS5-1-00	TCS14-1-00	GHW1-1-00	SBS2-1-00
TFL-1-1	TCS6-1-02	TCS15-1-00	GHW2-1-00	GMS1-1-00
LECS-4	TCS7-1-02	TCS17-1-00	RSD1-1-00	SSP1-1-02
	TCS8-1-00	TCS18-1-01	WSD1-1-00	SSA1-1-02

SURVEY CONTROL DATA
HORIZONTAL DATUM:
OKLAHOMA NORTH ZONE (3501) NAD 83.
BEARINGS ARE BASED ON STATE PLANE
GRID, AND ARE NOT ASTRONOMIC.
VERTICAL DATUM:
NAVD 1988

DESIGN DATA
COUNTY ROADS
AADT 2017 = 100
AADT 2037 = 181
V = VARIES



SCALES
PLAN 1" = 50'
PROFILE HOR. 1" = 50'
VER. 1" = 5'
LAYOUT MAP 1" = 2 MILE

CONVENTIONAL SYMBOLS

	PROPOSED ROAD
	RAILROADS
	RANGE & TOWNSHIP
	SECTION LINES
	QUARTER SECTION LINES
	FENCES
	GROUND LINE
	EXISTING ROADS
	BASE LINE
	GRADE LINES
	TELEPHONE & TELEGRAPH
	POWER LINES
	BUILDINGS
	OILWELL
	DRAINAGE STRUCTURES - IN PLACE
	DRAINAGE STRUCTURES - NEW
	RIGHT-OF-WAY LINES - EXISTING
	RIGHT-OF-WAY LINES - NEW
	CONTROLLED ACCESS
	MAILBOX
	EXISTING CENTERLINE
	EXISTING SANITARY SEWERS
	EXISTING GAS LINES
	EXISTING WATER LINES
	EXISTING TELEPHONE CABLES UNDERGROUND

INDIAN ROAD
BRIDGE "J" 78+08.91 TO 79+80.41 (171.50')
NBI NO. 14155, LOCATION NO. 3625 2605X
STA 73+50.00 TO STA 78+08.91
STA 79+80.41 TO STA 84+50.00

HOME ROAD
BRIDGE "H"
NBI NO. 14154, LOCATION NO. 3625 2505X
(DEMOLISH EXISTING BRIDGE/REGRADE DITCHES
I-35 STA 817+00.00 TO 823+00.00)

ADOBE ROAD
BRIDGE "G" 86+42.94 TO 88+19.44 (176.50')
NBI NO. 15149, LOCATION NO. 3625 1601X
STA 81+60.00 TO STA 86+42.94
STA 88+19.44 TO STA 93+20.00

FERGUSON AVE
BRIDGE "F" 81+32.28 TO 83+03.78 (171.50')
NBI NO. 15147, LOCATION NO. 3625 1399X
STA 74+05.00 TO STA 81+32.28
STA 83+03.78 TO STA 89+10.00


CHRYSLER AVE
BRIDGE "E" 77+16.78 TO 78+88.28 (171.50')
NBI NO. 15146, LOCATION NO. 3625 1299X
STA 72+25.00 TO STA 77+16.78
STA 78+88.28 TO STA 84+50.00

COLEMAN ROAD
BRIDGE "D" 77+21.86 TO 78+93.36 (171.50')
NBI NO. 15145, LOCATION NO. 3625 1199X
STA 71+60.00 TO STA 77+21.86
STA 78+93.36 TO STA 84+50.00

HARTFORD AVE.
BRIDGE "C" 24+56.51 TO 26+28.01 (171.50')
NBI NO. 14437, LOCATION NO. 3625 0900X
STA 19+00.00 TO STA 24+56.51
STA 26+28.01 TO STA 32+00.00

HIGHLAND AVE.
BRIDGE "B" 24+52.80 TO 26+24.30 (171.50')
NBI NO. 14435, LOCATION NO. 3625 0799X
STA 19+25.00 TO STA 24+52.80
STA 26+24.30 TO STA 32+00.00

NORTH AVE.
BRIDGE "A" 24+53.17 TO 26+24.67 (171.50')
NBI NO. 14429, LOCATION NO. 3625 0599X
STA 18+40.00 TO STA 24+53.17
STA 26+24.67 TO STA 32+00.00



ROADWAY LENGTH _____ 8,838.00 FT. 1.673 MI.
BRIDGE LENGTH _____ 1,377.00 FT. 0.260 MI.
PROJECT LENGTH _____ 1.933 MI.
EQUATION: SEE PLAN AND PROFILE SHEETS
EXCEPTIONS: NONE

SUBMITTED BY
GUY ENGINEERING
Certificate of Authorization No. 1427
Renewal Date: June 30, 2020

JOHN R. WORMAN, P.E. NO. 15497
(THIS SEAL COVERS ALL SHEETS EXCEPT AB01-AB02, B001-B027)

SUBMITTED BY
HNTB
Certificate of Authorization No. 1893
Renewal Date: JUNE 30, 2019



JESSE D. KUHLEN, P.E. NO. 28383
(THIS SEAL COVERS SHEETS AB01-AB02, B001-B027)

OKLAHOMA DEPARTMENT OF TRANSPORTATION	DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION
DATE APPROVED _____	DATE APPROVED _____
BY _____ CHIEF ENGINEER	BY _____ DIVISION ADMINISTRATOR
JOB 24432(15)	PROJECT NO. J2-4432(015)SS
COUNTY KAY	HIGHWAY/ROAD I-35 BRIDGES
	SHEET NO. 0001

Wednesday, October 24, 2018 2:22:40 PM V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\1070-COVER.dwg

2009 OKLAHOMA STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION - ENGLISH GOVERN, APPROVED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION, JANUARY 4, 2010.

DESCRIPTION	REVISIONS	DATE



TYPICAL SECTION ③
Not To Scale

NORTH AVE STA. 18+40.00 TO STA. 24+33.17 AND STA. 26+44.67 TO STA. 32+00.00
 HIGHLAND AVE STA. 19+25.00 TO STA. 24+36.51 AND STA. 26+44.30 TO STA. 32+00.00
 HARTFORD AVE STA. 19+00.00 TO STA. 24+36.51 AND STA. 26+48.01 TO STA. 32+00.00
 COLEMAN RD STA. 71+60.00 TO STA. 77+01.86 AND STA. 79+13.36 TO STA. 84+50.00
 CHRYSLER AVE STA. 72+25.00 TO STA. 76+96.78 AND STA. 79+08.28 TO STA. 84+50.00
 FERGUSON AVE STA. 74+05.00 TO STA. 81+12.28 AND STA. 83+23.78 TO STA. 89+10.00
 ADOBE RD STA. 81+60.00 TO STA. 86+22.94 AND STA. 88+39.44 TO STA. 93+20.00
 INDIAN RD STA. 73+50.00 TO STA. 77+88.91 AND STA. 80+00.41 TO STA. 84+50.00

I-35 CROSSOVER S. OF INDIAN ROAD

Not To Scale
 I-35 STA. 858+85.26 TO STA. 859+85.26

① TOPSOIL NOTE:
 THE CONTRACTOR SHALL STRIP ALL OF THE AVAILABLE TOPSOIL, STOCKPILE IT, AND PLACE IT BACK ON THE SECTION IN ACCORDANCE WITH SECTION 205 OF THE STANDARD SPECIFICATIONS. RESERVED TOPSOIL SHALL BE SPREAD FIRST ON THE COMPLETED SLOPES OF THE CUT SECTIONS AND THE REMAINDER ON COMPLETED FILL SLOPES OR OTHER PRIORITY AREAS LOCATED BY THE ENGINEER. ALL ADDITIONAL COSTS ASSOCIATED WITH OPERATION SHALL BE INCLUDED IN THE PAY ITEM FOR SALVAGED TOPSOIL, LUMP SUM.

THE GRADING LINE AS SHOWN ON THE TYPICAL IS TO THE TOP OF THE TOPSOIL. EARTHWORK QUANTITIES WERE NOT ADJUSTED FOR SALVAGE AND THE TOPSOIL QUANTITY IS INCLUDED IN THE EARTHWORK BALANCE.

② DISTANCE MEASURED VERTICALLY FROM EDGE OF FINISHED GRADE SHOULDER.

③ EXCEPTIONS:
 NORTH AVE STA. 18+40.00 TO STA. 19+40.00 TRANSITION FROM EX. PAV'T. TO TYP.
 NORTH AVE STA. 22+64.90 TO STA. 23+41.90 TRANSITION FROM TYP. TO GUARDRAIL WIDENING
 NORTH AVE STA. 27+35.94 TO STA. 28+12.94 TRANSITION FROM GUARDRAIL WIDENING TO TYP.
 NORTH AVE STA. 31+00.00 TO STA. 32+00.00 TRANSITION FROM TYP. TO EX. PAV'T.

HIGHLAND AVE STA. 19+25.00 TO STA. 20+25.00 TRANSITION FROM EX. PAV'T. TO TYP.
 HIGHLAND AVE STA. 22+64.53 TO STA. 23+41.53 TRANSITION FROM TYP. TO GUARDRAIL WIDENING
 HIGHLAND AVE STA. 27+35.57 TO STA. 28+12.57 TRANSITION FROM GUARDRAIL WIDENING TO TYP. RT
 HIGHLAND AVE STA. 28+48.07 TO STA. 29+25.07 TRANSITION FROM GUARDRAIL WIDENING TO TYP. LT
 HIGHLAND AVE STA. 31+00.00 TO STA. 32+00.00 TRANSITION FROM TYP. TO EX. PAV'T.

W HARTFORD AVE STA. 19+00.00 TO STA. 20+00.00 TRANSITION FROM EX. PAV'T. TO TYP.
 W HARTFORD AVE STA. 22+68.24 TO STA. 23+45.24 TRANSITION FROM TYP. TO GUARDRAIL WIDENING
 W HARTFORD AVE STA. 27+39.28 TO STA. 28+16.28 TRANSITION FROM GUARDRAIL WIDENING TO TYP.
 W HARTFORD AVE STA. 31+00.00 TO STA. 32+00.00 TRANSITION FROM TYP. TO EX. PAV'T.


COLEMAN RD STA. 71+60.00 TO STA. 72+60.00 TRANSITION FROM EX. PAV'T. TO TYP.
 COLEMAN RD STA. 75+33.59 TO STA. 76+10.59 TRANSITION FROM TYP. TO GUARDRAIL WIDENING
 COLEMAN RD STA. 80+04.63 TO STA. 80+81.63 TRANSITION FROM GUARDRAIL WIDENING TO TYP.
 COLEMAN RD STA. 83+50.00 TO STA. 84+50.00 TRANSITION FROM TYP. TO EX. PAV'T.

CHRYSLER AVE STA. 72+25.00 TO STA. 73+25.00 TRANSITION FROM EX. PAV'T. TO TYP.
 CHRYSLER AVE STA. 75+28.51 TO STA. 76+05.51 TRANSITION FROM TYP. TO GUARDRAIL WIDENING
 CHRYSLER AVE STA. 79+99.55 TO STA. 80+76.55 TRANSITION FROM GUARDRAIL WIDENING TO TYP. LT
 CHRYSLER AVE STA. 80+49.55 TO STA. 81+26.55 TRANSITION FROM GUARDRAIL WIDENING TO TYP. RT
 CHRYSLER AVE STA. 83+50.00 TO STA. 84+50.00 TRANSITION FROM TYP. TO EX. PAV'T.

FERGUSON AVE STA. 74+05.00 TO STA. 74+55.00 TRANSITION FROM EX. PAV'T. TO TYP. RT.
 FERGUSON AVE STA. 75+94.01 TO STA. 76+71.01 TRANSITION FROM TYP. TO GUARDRAIL WIDENING RT
 FERGUSON AVE STA. 76+19.01 TO STA. 76+96.01 TRANSITION FROM TYP. TO GUARDRAIL WIDENING LT
 FERGUSON AVE STA. 86+77.55 TO STA. 87+54.55 TRANSITION FROM GUARDRAIL WIDENING TO TYP.
 FERGUSON AVE STA. 88+10.00 TO STA. 89+10.00 TRANSITION FROM TYP. TO EX. PAV'T.


ADOBE RD STA. 81+60.00 TO STA. 82+60.00 TRANSITION FROM EX. PAV'T. TO TYP.
 ADOBE RD STA. 84+54.67 TO STA. 85+31.67 TRANSITION FROM TYP. TO GUARDRAIL WIDENING RT
 ADOBE RD STA. 83+92.17 TO STA. 84+69.17 TRANSITION FROM TYP. TO GUARDRAIL WIDENING LT
 ADOBE RD STA. 89+30.71 TO STA. 90+07.71 TRANSITION FROM GUARDRAIL WIDENING TO TYP. RT
 ADOBE RD STA. 89+93.21 TO STA. 90+70.21 TRANSITION FROM GUARDRAIL WIDENING TO TYP. LT
 ADOBE RD STA. 92+20.00 TO STA. 93+20.00 TRANSITION FROM TYP. TO EX. PAV'T.

INDIAN RD STA. 73+50.00 TO STA. 74+50.00 TRANSITION FROM EX. PAV'T. TO TYP.
 INDIAN RD STA. 76+01.89 TO STA. 76+78.89 TRANSITION FROM TYP. TO GUARDRAIL WIDENING RT
 INDIAN RD STA. 75+39.39 TO STA. 76+16.39 TRANSITION FROM TYP. TO GUARDRAIL WIDENING LT
 INDIAN RD STA. 81+97.93 TO STA. 82+74.93 TRANSITION FROM GUARDRAIL WIDENING TO TYP. RT
 INDIAN RD STA. 82+35.43 TO STA. 83+12.43 TRANSITION FROM GUARDRAIL WIDENING TO TYP. LT
 INDIAN RD STA. 83+50.00 TO STA. 84+50.00 TRANSITION FROM TYP. TO EX. PAV'T.



I-35 DITCH GRADING AT HOME ROAD


Not To Scale
 I-35 STA. 817+00.00 TO STA. 823+00.00 LT
 I-35 STA. 818+50.00 TO STA. 822+00.00 RT




GUARDRAIL WIDENING ③

Not To Scale

NORTH AVE STA. 23+41.90 TO STA. 24+33.17
 NORTH AVE STA. 26+44.67 TO STA. 27+35.94
 HIGHLAND AVE STA. 23+41.53 TO STA. 24+32.80
 HIGHLAND AVE STA. 26+44.30 TO STA. 27+35.57 RT
 HIGHLAND AVE STA. 26+44.30 TO STA. 28+48.07 LT
 HARTFORD AVE STA. 23+45.24 TO STA. 24+36.51
 HARTFORD AVE STA. 26+48.01 TO STA. 27+39.28
 COLEMAN RD STA. 76+10.59 TO STA. 77+01.86
 COLEMAN RD STA. 79+13.36 TO STA. 80+04.63
 CHRYSLER AVE STA. 76+05.51 TO STA. 76+96.78
 CHRYSLER AVE STA. 79+08.28 TO STA. 79+99.55 LT
 CHRYSLER AVE STA. 79+08.28 TO STA. 80+49.55 RT
 FERGUSON AVE STA. 76+71.01 TO STA. 81+12.28 RT
 FERGUSON AVE STA. 76+96.01 TO STA. 81+12.28 LT
 FERGUSON AVE STA. 83+23.78 TO STA. 86+77.55
 ADOBE RD STA. 85+31.67 TO STA. 86+22.94 RT
 ADOBE RD STA. 84+69.17 TO STA. 86+22.94 LT
 ADOBE RD STA. 88+39.44 TO STA. 89+30.71 RT
 ADOBE RD STA. 88+39.44 TO STA. 89+93.21 LT
 INDIAN RD STA. 76+78.89 TO STA. 77+88.91 RT
 INDIAN RD STA. 76+16.39 TO STA. 77+88.91 LT
 INDIAN RD STA. 80+00.41 TO STA. 81+97.93 RT
 INDIAN RD STA. 80+00.41 TO STA. 82+35.43 LT



TYPICAL SLAB SODDING



ROUNDING DETAIL

Not To Scale

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION GUY ENGINEERING SERVICES, INC.
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			
COUNTY <u>KAY</u>			STATE JOB NO. <u>24432(15)</u> SHEET NO. <u>0002</u>

TYPICAL SECTIONS

Friday, October 26, 2018 3:51:28 PM V:\16-1070E BR Raising Over I-35, Koy, 1840, HNTB\CW3D\PLANS\1070-TYPICAL_SECTION.dwg

REVISIONS		
REV. NO.	DESCRIPTION	DATE

24432 (15) 0200 BRIDGE		PAY QUANTITIES												
ITEM		DESCRIPTION	UNIT	BRIDGE "A" NORTH AVE.	BRIDGE "B" HIGHLAND AVE.	BRIDGE "C" HARTFORD AVE.	BRIDGE "D" COLEMAN RD.	BRIDGE "E" CHRYSLER AVE.	BRIDGE "F" FERGUSON AVE.	BRIDGE "G" ADOBE RD.	BRIDGE "H" HOME RD.	BRIDGE "J" INDIAN RD.	TOTALS	
501 (B)	1307	SUBSTRUCTURE EXCAVATION COMMON	BR-1, BR-2	CY	55.00	65.00	75.00	45.00	45.00	55.00	55.00	---	40.00	435.00
501 (G)	6309	CLSM BACKFILL	BR-1, BR-2	CY	45.00	45.00	45.00	46.00	46.00	45.00	45.00	---	39.00	356.00
502 (C)	6116	FALSEWORK AND JACKING	BR-6	LSUM	1.00	1.00	1.00	1.00	1.00	1.00	1.00	---	1.00	1.00
504 (A)	1304	APPROACH SLAB	BR-1	SY	129.00	129.00	129.00	129.00	129.00	129.00	129.00	---	111.20	1,014.20
504 (B)	1305	SAW CUT GROOVING	BR-1	SY	119.40	119.40	119.40	119.40	119.40	119.40	119.40	---	101.60	937.40
504 (D)	6245	CONCRETE RAIL (TR4)	BR-1	LF	80.00	80.00	80.00	80.00	80.00	80.00	80.00	---	80.00	640.00
506 (A)	1322	STRUCTURAL STEEL	BR-1, BR-3	LB	18,680.00	17,490.00	16,110.00	20,240.00	21,160.00	19,320.00	19,320.00	---	20,670.00	152,990.00
507 (C)	6282	ELASTOMERIC BEARING PADS	BR-1, BR-4	EA	10.00	10.00	10.00	10.00	10.00	10.00	10.00	---	---	70.00
509	6152	SPECIAL CONCRETE FINISH	BR-1	SY	796.00	799.00	801.00	788.00	792.00	796.00	818.00	---	694.00	6,284.00
509 (B)	1328	CLASS A CONCRETE	BR-1, BR-7	CY	9.20	7.10	5.00	11.40	12.00	9.90	9.90	---	11.10	75.60
510 (C)	6138	SLOPE WALL (5")	BR-1, BR-2	SY	918.00	856.00	941.00	857.00	854.00	958.00	794.00	---	982.00	7,160.00
513 (B)	6019	CLASS B BRIDGE DECK REPAIR	BR-8	SY	---	---	---	---	---	---	33.00	---	---	33.00
523 (C)	6570	DECK AREA SEAL (FLOODCOATS)	BR-1	SY	457.00	457.00	457.00	457.00	457.00	457.00	471.00	---	381.00	3,594.00
540	4501	(PL) REPAIR BRIDGE ITEMS	BR-5	SY	1.00	3.00	5.00	2.00	1.00	1.00	---	---	1.00	15.00
545	4800	(PL) REPLACE BRIDGE ITEMS	BR-11	LSUM	---	---	---	1.00	1.00	---	1.00	---	1.00	1.00
613 (H)	6204	6" PERFORATED PIPE UNDERDRAIN ROUND	BR-1, BR-2	LF	249.00	238.00	253.00	236.00	234.00	253.00	227.00	---	252.00	1942.00
613 (I)	6207	6" NON-PERFORATED PIPE UNDERDRAIN ROUND	BR-1, BR-2	LF	92.00	92.00	92.00	92.00	92.00	92.00	92.00	---	92.00	736.00
619 (B)	2500	REMOVAL OF BRIDGE ITEMS	BR-9	LSUM	1.00	1.00	1.00	1.00	1.00	1.00	1.00	---	1.00	1.00
619 (D)	1397	REMOVAL OF EXISTING BRIDGE	BR-10	LSUM	---	---	---	---	---	---	1.00	---	---	1.00

PAY QUANTITY NOTES

- (BR-1) PAYMENT FOR THIS ITEM WILL BE BASED UPON PLAN QUANTITIES ONLY. SEE SECTION 109.01.B OF THE STANDARD SPECIFICATIONS.
- (BR-2) PAYMENT AND LIMITS FOR THESE ITEMS ARE NOTED AND SHOWN ON THE SLOPEWALL AND DRAIN DETAILS SHEET.
- (BR-3) PAYMENT FOR ITEM "STRUCTURAL STEEL" INCLUDES THE STRUCTURAL STEEL, HEADED STUD ANCHORS, AND SQUARING DIAPHRAGMS REQUIRED FOR THE PERMANENT BOLSTERS. THIS ALSO INCLUDES COST FOR GALVANIZING. BASIS OF MEASUREMENT IS FOR THE STRUCTURAL STEEL ONLY. ALL STRUCTURAL STEEL FOR FALSEWORK AND JACKING IS INCLUDED WITH THE BID ITEM "FALSEWORK AND JACKING".
- (BR-4) BASIS OF MEASUREMENT ASSUMES A SINGLE, CONTINUOUS, 2'-0" WIDE BEARING PAD AT THE TOP OF EACH BOLSTER AT ABUTMENT AND PIER AND COTTON FIBER REINFORCED PADS ON THE BOTTOM OF THE BOLSTER AS SHOWN IN THE PLANS. MULTIPLE, SHORTER 2'-0" WIDE BEARING PADS MAY BE USED IN LIEU OF A SINGLE PAD AT EACH ABUTMENT AND PIER.
- (BR-5) PAYMENT FOR ITEM "(PL) REPAIR BRIDGE ITEMS" WILL BE BASED ON THE PLAN QUANTITIES. BASIS OF MEASUREMENT IN SQUARE YARDS IS TOTAL SURFACE AREA OF HOLES IN THE PIERS AND ABUTMENTS DUE TO JACKING ASSEMBLY ATTACHMENT AND OTHER MISCELLANEOUS REPAIRS TO THE PIERS OR ABUTMENTS AS NOTED IN THE PLANS. THE BID ITEM PRICE PER SQUARE YARD FOR "(PL) REPAIR BRIDGE ITEMS" SHALL INCLUDE ALL COSTS FOR MATERIALS AND INSTALLATION INCLUDING CONCRETE, GROUT, REINFORCING STEEL, LABOR, EQUIPMENT, TOOLS, AND INCIDENTALS NECESSARY TO COMPLETE THE WORK.
- (BR-6) PAYMENT FOR ITEM "FALSEWORK AND JACKING" SHALL INCLUDE ALL ITEMS NOTED IN THE GENERAL NOTES "FALSEWORK AND JACKING", "LIFTING OF EXISTING BRIDGE" AND "ANCHORAGE INTO EXISTING CONCRETE".
- (BR-7) PAYMENT FOR ITEM "CLASS A CONCRETE" WILL BE BASED ON THE PLAN QUANTITIES. THIS ITEM INCLUDES THE PERMANENT STEEL BOLSTER CONCRETE ONLY.
- (BR-8) PAYMENT FOR "CLASS B BRIDGE DECK REPAIR" INCLUDES REMOVAL OF EXISTING CONCRETE TO A MINIMUM OF THE LIMITS DEFINED IN THE PLANS AND IN ACCORDANCE WITH SECTION 513 OF THE STANDARD SPECIFICATIONS. THE BID ITEM PRICE PER SQUARE YARD FOR "CLASS B BRIDGE DECK REPAIR" SHALL INCLUDE ALL COSTS FOR REMOVAL OF EXISTING CONCRETE AS WELL AS MATERIALS AND INSTALLATION INCLUDING CONCRETE, REINFORCING STEEL, LABOR, EQUIPMENT, TOOLS, AND INCIDENTALS NECESSARY TO COMPLETE THE WORK.
- (BR-9) PAYMENT FOR ITEM "REMOVAL OF EXISTING BRIDGE ITEMS" INCLUDES EXISTING NEOPRENE PADS, EXISTING SLOPEDRAINS, AND EXISTING SLOPEWALLS AS DEFINED IN PLANS AND NOTES.
- (BR-10) PAYMENT FOR THIS ITEM INCLUDES THE DEMOLITION OF THE EXISTING BRIDGE AT HOME RD AS SHOWN IN THE PLANS. THIS INCLUDES THE REMOVAL OF THE EXISTING SLOPEWALLS AND SLOPEDRAINS AND ALL LABOR, EQUIPMENT, TOOLS AND INCIDENTALS NECESSARY TO REMOVE THE BRIDGE FOR EITHER ALTERNATIVE AS PROPOSED.
- (BR-11) PAYMENT FOR "(PL) REPLACE BRIDGE ITEMS" INCLUDES REMOVAL OF EXISTING CONCRETE PILASTER AND RAILS AS NOTED IN THE PLANS. ALL COSTS FOR MATERIALS AND INSTALLATION INCLUDING CONCRETE, REINFORCING STEEL, LABOR, EQUIPMENT, TOOLS, AND INCIDENTALS NECESSARY TO COMPLETE THE WORK ARE INCLUDED IN THIS PAY ITEM.

BRIDGE "A" - "J" COUNTY ROADS OVER I-35		KAY COUNTY		Design	WJS	9/18
SUMMARY OF PAY QUANTITIES AND NOTES (BRIDGE)				Detail	KNB	8/18
				Check	WJS	9/18
				Squad	THOMAS	
				Engr:	THOMAS	
STATE OF OKLAHOMA		DEPARTMENT OF TRANSPORTATION				
JOB/PIECE NO. 24432(15)		SHEET NO. AB02				

ROADWAY GENERAL CONSTRUCTION NOTES

EXISTING ROADWAY SHALL REMAIN CLOSED TO THROUGH TRAFFIC. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL DRIVES AND FIELD ENTRANCES DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER BARRICADES, LIGHTS, AND SIGNING WITHIN THE LIMITS OF CONSTRUCTION. ALL CONSTRUCTION SIGNING WILL BE DONE ACCORDING TO STANDARDS SET FORTH IN THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (CURRENT EDITION), AND AS SHOWN ON TCS STANDARD DRAWINGS.

THE CONTRACTOR SHALL SUBMIT A DETAILED CONSTRUCTION PHASING AND TRAFFIC MANAGEMENT PLAN TO THE ENGINEER FOR REVIEW AND APPROVAL BEFORE CONSTRUCTION OPERATIONS BEGIN. THE TRAFFIC MANAGEMENT SHALL CONFORM TO ALL APPLICABLE STATE STANDARDS AND MUTCD GUIDELINES (LATEST REVISIONS).

THE CONTRACTOR SHALL NOT WASTE ANY EXCESS EXCAVATION UNTIL ALL PLANNED EMBANKMENTS AND BACKFILLS ARE COMPLETED. EXCESS UNCLASSIFIED EXCAVATION MATERIAL DETERMINED BY THE ENGINEER TO BE SUITABLE FOR BACKFILL SHALL BE USED TO REDUCE ANY UNCLASSIFIED BORROW NEEDED. COST OF SECOND HANDLING SHALL BE INCLUDED IN OTHER ITEMS OF WORK. ANY REMAINING EXCESS EXCAVATION SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND BE DISPOSED OF IN A MANNER APPROVED BY THE ENGINEER.

THE CONTRACTOR SHALL GIVE NOTICE TO THE COUNTY AND THE OKLAHOMA DEPARTMENT OF TRANSPORTATION (DIVISION 4) IN WRITING, FOURTEEN (14) CALENDAR DAYS BEFORE WORK BEGINS ON THE PROJECT.

CONTRACTOR SHALL NOT DISTURB ANY RIGHT-OF-WAY STAKES. IF ANY OF THE RIGHT-OF-WAY STAKES ARE REMOVED OR DISTURBED DURING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING THEM, AT HIS OWN EXPENSE, TO THE SATISFACTION OF THE ENGINEER AND COUNTY, IN ORDER TO CONSTRUCT THE PERMANENT FENCE AT THE PROPER LOCATION.

SURFACING OF RETURNS, UNLESS OTHERWISE SHOWN ON THE PLANS, SHALL BE OF THE SAME MATERIAL (BASE AND SURFACE) AS THAT OF THE ABUTTING SHOULDER OF THE MAINLINE. BASE AND SURFACE THICKNESS SHALL BE THE THICKNESS SHOWN ON PLANS.

T.B.S.C. SURFACES SHALL BE SPRINKLED WITH WATER AND ROLLED WITH A PNEUMATIC ROLLER IN A MANNER APPROVED BY THE INSPECTOR.

IN ACCORDANCE WITH THE OKLAHOMA UNDERGROUND FACILITIES DAMAGE PREVENTION ACT THE CONTRACTOR SHALL NOTIFY THE OKLAHOMA ONE-CALL SYSTEM, 48 HOURS PRIOR TO BEGINNING EXCAVATION. OKLAHOMA ONE-CALL SYSTEM, INC. "CALL OKIE" 1-800-522-6543 OR 811.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE HE MAY INFLICT TO THE EXISTING UNDERGROUND UTILITIES WITHIN THE PROJECT AREA AS A RESULT OF HIS DIGGING, TRENCHING, BORING, ETC. . . . PRIOR TO DIGGING NEAR THE UTILITIES, THE CONTRACTOR SHALL CALL FOR A LIST OF ALL UNDERGROUND FACILITIES REGISTERED IN THE AREA OF CONSTRUCTION LISTED WITH THE FOLLOWING AGENCIES:
THE OKIE NOTIFICATION CENTER 811 OR 1-800-522-6543 OR WWW.CALLOKIE.COM OR THE LOCAL COUNTY CLERK'S OFFICE.

DEPTH OF EXISTING UTILITIES SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.

VEGETATIVE MULCHING: THE VEGETATIVE MULCH SHALL BE ANCHORED IN ACCORDANCE WITH THE "ADHESIVE SPRAY METHOD", AS SPECIFIED IN SECTION 233.04B(1) OF THE STANDARD SPECIFICATIONS.

AT THE BEGINNING OF THE TURFING OPERATIONS, ANY AREAS INCLUDED IN PLANNED QUANTITIES THAT HAVE GROWN A SATISFACTORY VOLUNTEER TURF OR PERENNIAL GRASS, AS DETERMINED BY THE ENGINEER, SHALL BE FERTILIZED AND WATERED AS CALLED FOR ON THE PLANS, BUT SHALL NOT BE SEEDED, SODDED, OR SPRIGGED.

DO NOT DISTURB SECTION CORNERS OR ¼ SECTION CORNERS. IF DISTURBED MONUMENTS SHALL BE RESET WITHIN 30 DAYS OF PROJECT COMPLETION BY A REGISTERED LAND SURVEYOR LICENSED IN THE STATE OF OKLAHOMA.

ROADWAY PAY QUANTITY NOTES

(R-1) PAYMENT FOR THIS ITEM WILL BE BASED ON PLAN QUANTITIES ONLY. SEE SECTION 109.01B OF THE STANDARD SPECIFICATIONS .

(R-4) INCLUDES 200 CU. YDS. FOR DRIVEWAYS, RETURNS, DIKES, AND MISCELLANEOUS EARTHWORK.

(R-5) AN ESTIMATED QUANTITY OF 8136 C.Y. TOPSOIL TO BE RESERVED FOR REPLACEMENT OF APPROXIMATELY 5" ON COMPLETED FORESLOPES, DITCHES, AND BACKSLOPES. THIS QUANTITY IS INCLUDED IN THE EARTHWORK BALANCE. ANY ADDITIONAL EXCAVATION REQUIRED IN CUT SECTIONS TO ALLOW FOR PLACEMENT OF TOPSOIL TO FINAL GRADE, SHALL BE INCLUDED IN THE PRICE BID.

(R-7) FOR TYPE A SALVAGED TOPSOIL PRICE BID TO INCLUDE COST OF 18-46-0 FERTILIZER, ESTIMATED AT 150 POUNDS PER ACRE.

FOR 230(A) SOLID SLAB SOD PRICE BID TO INCLUDE COST OF 10-20-10 FERTILIZER OR APPROVED EQUIVALENT, ESTIMATED AT 200 POUNDS PER S.Y.

(R-8) FOR SOLID SLAB SODDING PRICE BID TO INCLUDE THE COST OF WATERING, ESTIMATED AT 80 GALLONS PER S.Y.

(R-11) THE QUANTITY ESTIMATED FOR TEMPORARY EROSION AND SEDIMENT CONTROL IS 12.46 ACRES.

(R-25) ESTIMATED AT 140 LBS. PER CU. FT.

(R-30) PRICE BID TO INCLUDE COST OF 56 GALLONS OF TACK COAT, MEETING THE REQUIREMENTS OF SECTION 407 OF THE STANDARD SPECIFICATIONS.

(R-32) ESTIMATED AT 112 LBS. PER SQ. YD. PER 1" THICK.

(R-41) QUANTITY INCLUDES AN ESTIMATED 10 C.Y. TO BE USED AS DIRECTED BY THE ENGINEER.

(R-48) INCLUDES REMOVAL OF ALL EXISTING ROADWAY DRAINAGE STRUCTURES, HEADWALLS (UNLESS OTHERWISE SPECIFIED), INLETS, FENCES, AND OTHER STRUCTURES WITHIN THE RIGHT OF WAY.

(R-49) TO BECOME THE PROPERTY OF AND BE DISPOSED OF BY THE CONTRACTOR IN A MANNER APPROVED BY THE ENGINEER.

R-52) INCLUDES 2% FOR GROUND MEASUREMENT.

1) QUANTITY INCLUDES 19 TONS FOR TEMPORARY ACCESS TO DRIVEWAYS.

2) ESTIMATED QUANTITY ONLY. COST TO INCLUDE TEMPORARY SEDIMENT REMOVAL. REMOVE SEDIMENT WHEN 1/3 FULL.

3) STAKE SOD ON ALL SLOPES 1:2 OR STEEPER, AND ON ANY AREAS THAT ARE IN SUCH CONDITION THAT THERE IS DANGER OF SOD SLIPPING. PERFORM STAKING CONCURRENTLY WITH SOD PLACEMENT AND PRIOR TO TAMPING WITH SOUND WOODEN STAKES APPROXIMATELY 1 INCH SQUARE OR 1 INCH IN DIAMETER AND NOT LESS THAN 12 INCHES IN LENGTH, OR USE METAL STAPLES IN PLACE OF WOODEN STAKES. PLACE STAKES AND STAPLE THE SOD WHERE NECESSARY, AND AS DETERMINED BY THE ENGINEER. SEE STANDARD DRAWING SSS-1-1 FOR DETAILS.

4) CONSTRUCTION STAKING SHALL INCLUDE ESTABLISH AND RE-ESTABLISH STAKING OF CENTERLINE, BENCHMARKS, AND RIGHT-OF-WAY. INCLUDES SLOPE STAKING, STRUCTURE AND BRIDGE STAKING, ROADWAY STAKING (DRIVEWAYS INCLUDED), BLUETOPPING, AND CHECKING ALIGNMENTS AND ELEVATIONS AS REQUIRED.

5) INCLUDES REMOVING AND RESETTING GUARDRAIL AS NECESSARY NEAR BOTTOM OF BRIDGE SLOPEWALLS IN ORDER TO REMOVE AND REPLACE SLOPEWALLS AS SHOWN ON BRIDGE PLANS.

6) SAW CUTTING IS INCLUDED IN REMOVAL OF ASPHALT.

7) INCLUDES REMOVAL OF CONCRETE PAD AND SAND FILLED IMPACT ATTENUATORS. SAND FILLED IMPACT ATTENUATORS TO BECOME PROPERTY OF ODOT. CONTRACTOR TO DELIVER TO ODOT. COORDINATE WITH ENGINEER FOR DELIVERY LOCATION.

8) DOES NOT INCLUDE BRIDGE REMOVAL AT HOME ROAD.

DESCRIPTION	REVISIONS	DATE

31170(15)					
PAY QUANTITIES					
0100 ROADWAY ITEMS (BASE BID)					
ITEM	DESCRIPTION	PAY NOTES	UNIT	QUANTITY	
201(A)	0102	CLEARING AND GRUBBING	L. SUM	1	
202(A)	0183	UNCLASSIFIED EXCAVATION	R-1	C.Y.	7,285
202(D)	0184	UNCLASSIFIED BORROW	R-1,R-4	C.Y.	16,665
205(A)	4230	TYPE A - SALVAGED TOPSOIL	R-7	C.Y.	8,136
221(C)	2801	TEMPORARY SILT FENCE	2	L.F.	19,725
221(F)	0100	TEMPORARY SILT DIKE	2	L.F.	225
221(K)	0600	TEMPORARY FIBER LOG	2,3	L.F.	15
230(A)	2806	SOLID SLAB SODDING	R-7,R-8	S.Y.	60,165
233(A)	2817	VEGETATIVE MULCHING	R-11	AC.	12.46
402(E)	0225	TRAFFIC BOUND SURFACE COURSE TYPE E	1,R-25	TON	8,068
509(D)	0325	CLASS C CONCRETE	R-41	C.Y.	10
613(A)	0492	24" R.C. PIPE CLASS III		L.F.	10
613(L)	5730	24" PREFAB. CULVERT END SEC., ROUND		EA.	2
619(A)	0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	5,7-8,R-48,R-49	L. SUM	1
619(B)	4725	REMOVAL OF FENCE	R-49	L.F.	2,993
619(B)	4728	REMOVAL OF ASPHALT PAVEMENT	6,R-49	S.Y.	145
619(B)	4780	REMOVAL OF GUARDRAIL	R-49	L.F.	3,918
623(A)	0932	BEAM GUARDRAIL W-BEAM SINGLE		L.F.	2,038
623(G)	8590	GUARDRAIL END TREATMENT (31")		EA.	32
623(I)	8700	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")		EA.	32
624(C)	4459	FENCE-STYLE SWF (6 BARBED WIRE)	R-52	L.F.	3,168

31170(15)					
PAY QUANTITIES					
0100 ROADWAY ITEMS (BID ALTERNATE A-CROSSOVER PAVING QUANTITIES)					
ITEM	DESCRIPTION	PAY NOTES	UNIT	QUANTITY	
303(A)	2100	AGGREGATE BASE TYPE A		CY	82
310(B)	0149	SUBGRADE, METHOD B		SY	370
411(B)	5945	SUPERPAVE, TYPE S3 (PG 64-22 OK)	R-30,R-32	TON	124
411(C)	5960	SUPERPAVE, TYPE S4 (PG 64-22 OK)	R-30,R-32	TON	41

31170(15)					
PAY QUANTITIES					
0600 STAKING (BASE BID)					
ITEM	DESCRIPTION	PAY NOTES	UNIT	QUANTITY	
642(B)	0096	CONSTRUCTION STAKING LEVEL II	4	L. SUM	1

31170(15)					
PAY QUANTITIES					
0640 CONSTRUCTION (BASE BID)					
ITEM	DESCRIPTION	PAY NOTES	UNIT	QUANTITY	
220	2800	SWPPP DOCUMENTATION AND MANAGEMENT		L. SUM	1
641	1399	MOBILIZATION		L. SUM	1

BID NOTES

BID ALTERNATE A INCLUDES ROLLING BLOCKS IN BOTH DIRECTIONS ALONG I-35 FOR 8 OF THE BRIDGE LOCATIONS. HOWEVER, THE DEMOLITION OF THE BRIDGE AT HOME ROAD DOES NOT INCLUDE ROLLING ROAD BLOCKS. BUT CROSSOVERS ARE BEING UTILIZED IN THE BASE BID AT THIS LOCATION. SEE TRAFFIC CONTROL PAY QUANTITIES FOR ADDITIONAL DETAILS. BID ALTERNATE A ROADWAY PAY QUANTITIES ONLY INCLUDES QUANTITIES FOR THE CROSS OVER PAVING.

BID ALTERNATE B IS FOR A ROLLING ROAD BLOCK AT HOME ROAD DEMOLITION INSTEAD OF CROSSOVER AND FOR THE 8 BRIDGES TO BE RAISED UNDER LIVE TRAFFIC INSTEAD OF UTILIZING ROLLING ROAD BLOCKS. THIS WILL REQUIRE LANE CLOSURES INSTEAD OF ROAD BLOCKS. SEE TRAFFIC CONTROL PAY QUANTITIES FOR ADDITIONAL DETAILS. ALTERNATE B DOES NOT HAVE ANY ROADWAY QUANTITIES ASSOCIATED WITH THIS ALTERNATE.

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION				
DRAWN	ALM	09/18	GUY ENGINEERING SERVICES, INC.				
CHECKED	BDC	09/18	SUMMARY OF PAY QUANTITIES & NOTES (ROADWAY)				
APPROVED	JRW	09/18					
SQUAD							
COUNTY	KAY	HIGHWAY/ROAD	I-35	STATE JOB NO.	24432(15)	SHEET NO.	AR01

SIGN SUMMARY

SIGN NO.	APPROX CRL STATION AND OFFSET LOCATION		DESCRIPTION	SIGN	BARRICADE (TYPE III 880(C))	SHEET ALUMINUM SIGNS 850(A)	2-1/2" SQUARE TUBE POST 851(C)		REMARKS	
					SF		SF	A		B
								LF		LF
1	FERGUSON	74+05.00 15' RT.	LEFT REVERSE CURVE ADVISORY SPEED (20 MPH)	W1-4(L) W13-1P(20)	6.25 2.25		14		MOUNT BOTH SIGNS ON SINGLE POST	
2	FERGUSON	81+08.00 16' RT.	LEFT REVERSE CURVE ADVISORY SPEED (20 MPH)	W1-4(L) W13-1P(20)	6.25 2.25		14		MOUNT BOTH SIGNS ON SINGLE POST	
3	FERGUSON	83+28.00 16' LT.	LEFT REVERSE CURVE ADVISORY SPEED (20 MPH)	W1-4(L) W13-1P(20)	6.25 2.25		14		MOUNT BOTH SIGNS ON SINGLE POST	
4	FERGUSON	89+00.00 16' LT.	LEFT REVERSE CURVE ADVISORY SPEED (20 MPH)	W1-4(L) W13-1P(20)	6.25 2.25		14		MOUNT BOTH SIGNS ON SINGLE POST	
5	HOME ROAD	SECTION LINE EAST OF BRIDGE	2-TYPE III BARRICADES "BRIDGE OUT 0.5 MILES AHEAD LOCAL TRAFFIC ONLY" MOUNTED ON EACH TYPE III BARRICADE	2-R11-3B	2	25.00	12	12		
5	HOME ROAD	SECTION LINE WEST OF BRIDGE	2-TYPE III BARRICADES "BRIDGE OUT 0.5 MILES AHEAD LOCAL TRAFFIC ONLY" MOUNTED ON EACH TYPE III BARRICADE	2-R11-3B	2	25.00	12	12		
6	HOME ROAD	150 EAST OF I-35 C.L.	3-TYPE III BARRICADES "ROAD CLOSED" MOUNTED ON EACH TYPE III BARRICADE	3-R11-2	3	30.00	12	12		
6	HOME ROAD	150 WEST OF I-35 C.L.	3-TYPE III BARRICADES "ROAD CLOSED" MOUNTED ON EACH TYPE III BARRICADE	3-R11-2	3	30.00	12	12		
TOTALS =					10	144.00	104	48		

DESCRIPTION	REVISIONS	DATE

PORTABLE LONGITUDINAL BARRIER WALL SUMMARY TABLE

LOCATION NORTHBOUND	DELIVER PORTABLE LONGITUDINAL BARRIER	RELOCATION OF PORTABLE LONGITUDINAL BARRIER
	877(B)	877(C)
	LF	LF
NORTH AVE OUTSIDE SHOULDER-PRE RAISE	560	
NORTH AVE INSIDE SHOULDER-PRE RAISE	560	
NORTH AVE OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
NORTH AVE OUTSIDE SHOULDER-POST BRIDGE RAISE		560
HIGHLAND AVE OUTSIDE SHOULDER-PRE RAISE	560	
HIGHLAND AVE INSIDE SHOULDER -PRE RAISE	560	
HIGHLAND AVE OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
HIGHLAND AVE OUTSIDE SHOULDER-POST BRIDGE RAISE		560
HARTFORD AVE OUTSIDE SHOULDER-PRE RAISE	560	
HARTFORD AVE INSIDE SHOULDER -PRE RAISE	560	
HARTFORD AVE OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
HARTFORD AVE OUTSIDE SHOULDER-POST BRIDGE RAISE		560
COLEMAN ROAD OUTSIDE SHOULDER-PRE RAISE	560	
COLEMAN ROAD INSIDE SHOULDER -PRE RAISE	560	
COLEMAN ROAD OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
COLEMAN ROAD OUTSIDE SHOULDER-POST BRIDGE RAISE		560
CHRYSLER AVE NORTHBOUND OUTSIDE SHOULDER-PRE RAISE	560	
CHRYSLER AVE NORTHBOUND INSIDE SHOULDER -PRE RAISE	560	
CHRYSLER AVE NORTHBOUND OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
CHRYSLER AVE OUTSIDE SHOULDER-POST BRIDGE RAISE		560
FERGUSON AVE OUTSIDE SHOULDER-PRE RAISE	560	
FERGUSON AVE INSIDE SHOULDER -PRE RAISE	560	
FERGUSON AVE OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
FERGUSON AVE OUTSIDE SHOULDER-POST BRIDGE RAISE		560
ADOBE ROAD OUTSIDE SHOULDER-PRE RAISE	560	
ADOBE ROAD INSIDE SHOULDER -PRE RAISE	560	
ADOBE ROAD OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
ADOBE ROAD OUTSIDE SHOULDER-POST BRIDGE RAISE		560
HOME ROAD OUTSIDE SHOULDER-PRE DEMOLITION	560	
HOME ROAD INSIDE SHOULDER -PRE DEMOLITION	560	
INDIAN ROAD OUTSIDE SHOULDER-PRE RAISE	560	
INDIAN ROAD INSIDE SHOULDER -PRE RAISE	560	
INDIAN ROAD OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
INDIAN ROAD OUTSIDE SHOULDER-POST BRIDGE RAISE		560
SUBTOTAL NORTHBOUND	1,120	17,920

PORTABLE LONGITUDINAL BARRIER WALL SUMMARY TABLE

LOCATION SOUTHBOUND	DELIVER PORTABLE LONGITUDINAL BARRIER	RELOCATION OF PORTABLE LONGITUDINAL BARRIER
	877(B)	877(C)
	LF	LF
NORTH AVE OUTSIDE SHOULDER-PRE RAISE	560	
NORTH AVE INSIDE SHOULDER -PRE RAISE	560	
NORTH AVE OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
NORTH AVE OUTSIDE SHOULDER-POST BRIDGE RAISE		560
HIGHLAND AVE OUTSIDE SHOULDER-PRE RAISE	560	
HIGHLAND AVE INSIDE SHOULDER -PRE RAISE	560	
HIGHLAND AVE OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
HIGHLAND AVE OUTSIDE SHOULDER-POST BRIDGE RAISE		560
HARTFORD AVE OUTSIDE SHOULDER-PRE RAISE	560	
HARTFORD AVE INSIDE SHOULDER -PRE RAISE	560	
HARTFORD AVE OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
HARTFORD AVE OUTSIDE SHOULDER-POST BRIDGE RAISE		560
COLEMAN ROAD OUTSIDE SHOULDER-PRE RAISE	560	
COLEMAN ROAD INSIDE SHOULDER -PRE RAISE	560	
COLEMAN ROAD OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
COLEMAN ROAD OUTSIDE SHOULDER-POST BRIDGE RAISE		560
CHRYSLER AVE OUTSIDE SHOULDER-PRE RAISE	560	
CHRYSLER AVE INSIDE SHOULDER -PRE RAISE	560	
CHRYSLER AVE OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
CHRYSLER AVE OUTSIDE SHOULDER-POST BRIDGE RAISE		560
FERGUSON AVE OUTSIDE SHOULDER-PRE RAISE	560	
FERGUSON AVE INSIDE SHOULDER -PRE RAISE	560	
FERGUSON AVE OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
FERGUSON AVE OUTSIDE SHOULDER-POST BRIDGE RAISE		560
ADOBE ROAD OUTSIDE SHOULDER-PRE RAISE	560	
ADOBE ROAD INSIDE SHOULDER -PRE RAISE	560	
ADOBE ROAD OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
ADOBE ROAD OUTSIDE SHOULDER-POST BRIDGE RAISE		560
HOME ROAD OUTSIDE SHOULDER-PRE DEMOLITION	560	
HOME ROAD INSIDE SHOULDER -PRE DEMOLITION	560	
INDIAN ROAD OUTSIDE SHOULDER-PRE RAISE	560	
INDIAN ROAD INSIDE SHOULDER -PRE RAISE	560	
INDIAN ROAD OUTSIDE LANE CLOSURE-BRIDGE RAISE		560
INDIAN ROAD OUTSIDE SHOULDER-POST BRIDGE RAISE		560
SUBTOTAL SOUTHBOUND	1,120	17,920
SUBTOTALNORTHBOUND	1,120	17,920
GRAND TOTAL	2,240	35,840

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION GUY ENGINEERING SERVICES, INC.
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			
SUMMARY OF QUANTITIES (TRAFFIC)			
COUNTY	KAY	HIGHWAY/ROAD	I-35
STATE JOB NO.	24432(15)	SHEET NO.	AT02

Friday, October 26, 2018 3:53:07 PM V:\16-1070E BR Raising Over I-35, Koy, 1840, HNTB\C\3D\PLANS\1070-SUMMARY SHEET.dwg

REVISIONS		
REV. NO.	DESCRIPTION	DATE

LIFTING OF THE EXISTING BRIDGES:

- THE EXISTING BRIDGES SHALL BE LIFTED USING FALSEWORK AND JACKING INSTALLED AT THE ABUTMENTS AND PIERS. SEE THE GENERAL NOTE "FALSEWORK AND JACKING" FOR ADDITIONAL INFORMATION. CONTRACTOR SHALL SUBMIT THE PROPOSED BRIDGE RAISE SEQUENCE TO THE ENGINEER FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION OF FALSEWORK.
- CONTRACTOR SHALL PROVIDE A MINIMUM OF 2 BACKUP JACKS FOR EACH SIZE/TYPE OF JACK USED.
 - CONTRACTOR SHALL PROVIDE A MINIMUM OF 2 SETS OF BACKUP HYDRAULIC HOSES, PUMPS, AND MANIFOLDS.
 - HYDRAULIC JACKS SHALL HAVE A MINIMUM CAPACITY OF 1.5 TIMES THE ANTICIPATED MAXIMUM JACK REACTION. ALL HYDRAULIC JACKS SHALL HAVE LOCKING COLLARS.
 - DURING THE BRIDGE RAISE, THE CONTRACTOR SHALL HAVE AUDIBLE AND VISUAL COMMUNICATION WITH ALL JACK LOCATIONS AT ALL TIMES.
 - DOWEL BARS MAY BE PRESENT AT BEARING LOCATIONS. CONTRACTOR SHALL BE PREPARED TO CUT AND/OR REMOVE BARS IF PRESENT.
 - PHASED LIFTING OPERATIONS ARE NECESSARY TO RAISE THE BRIDGE. TEMPORARY BOLSTERS WILL BE REQUIRED AT EACH JACK LOCATION.

ALL COSTS TO INSTALL FALSEWORK AND JACKING ON THE BRIDGE INCLUDING THE COST OF ALL MATERIAL, LABOR, EQUIPMENT AND INCIDENTALS SHALL BE INCLUDED IN THE UNIT PRICE BID PER LUMP SUM OF "FALSEWORK AND JACKING."

INDEX OF BRIDGE SHEETS	
NO.	DESCRIPTION
AB01	GENERAL NOTES (BRIDGE)
AB02	SUMMARY OF PAY QUANTITIES AND NOTES (BRIDGE)
B001	BRIDGE RAISING SEQUENCE AND JACKING TABLES
B002	GENERAL PLAN & ELEVATION - NORTH - BRIDGE "A"
B003	GENERAL PLAN & ELEVATION - HIGHLAND - BRIDGE "B"
B004	GENERAL PLAN & ELEVATION - HARTFORD - BRIDGE "C"
B005	GENERAL PLAN & ELEVATION - COLEMAN - BRIDGE "D"
B006	GENERAL PLAN & ELEVATION - CHRYSLER - BRIDGE "E"
B007	GENERAL PLAN & ELEVATION - FERGUSON - BRIDGE "F"
B008	GENERAL PLAN & ELEVATION - ADOBE - BRIDGE "G"
B009	GENERAL PLAN & ELEVATION - INDIAN - BRIDGE "J"
B010	ABUTMENT FALSEWORK TYPE 1
B011	PIER FALSEWORK TYPE 1
B012	PERMANENT BOLSTERS TYPE 1
B013	ABUTMENT FALSEWORK TYPE 2
B014	PIER FALSEWORK TYPE 2
B015	PERMANENT BOLSTERS TYPE 2
B016	ABUTMENT BOLSTER INSTALLATION
B017	PIER BOLSTER INSTALLATION
B018	APPROACH SLAB DETAILS
B019	CONCRETE TRAFFIC RAIL (TR-4) ON APPROACH SLAB
B020	SLOPEWALL AND DRAIN DETAILS
B021-B022	HOME ROAD DEMOLITION - ROLLING ROAD BLOCK ALTERNATIVE
B023	HOME ROAD DEMOLITION - CROSSOVER ALTERNATIVE
B024-B027	HOME ROAD EXISTING DETAILS - BRIDGE "H"

SUGGESTED BRIDGE RAISE SEQUENCE NOTES:


- INSTALL TRAFFIC CONTROL DEVICES ALONG MAINLINE I-35. SEE TRAFFIC CONTROL PLANS FOR MORE INFORMATION REGARDING MAINTENANCE OF TRAFFIC.
- REMOVE ANY APPURTENANCES AS NECESSARY. THIS INCLUDES ANY ATTACHED UTILITIES AND SIGNS. THIS MAY ALSO INCLUDE LOOSE OR DAMAGED CONCRETE CURB AND RAIL. REMOVE ALL LOOSE DEBRIS.
- INSTALL JACKING BRACKETS. USE A PACHOMETER OR OTHER APPROVED METHOD TO LOCATE EXISTING REINFORCEMENT PRIOR TO CORING/DRILLING HOLES FOR BRACKETS.
- INSTALL JACKS, TRANSFER BEAMS, AND SHIMS. INSTALLATION OF JACKS SHALL BE COORDINATED WITH TIMELINE FOR JACKING OPERATIONS.
- PERFORM ON-SITE COORDINATION MEETING WITH ENGINEERS, INSPECTORS, AND WORKERS TO DISCUSS PROCESSES AND SPECIFICATIONS FOR JACKING OPERATIONS.
- CONFIRM ALL HYDRAULIC PUMPS ARE WORKING AND PROVIDE BACKUPS AS SPECIFIED.
- CLOSE LOCAL ROAD. SEE TRAFFIC CONTROL PLANS FOR MORE INFORMATION REGARDING MAINTENANCE OF TRAFFIC. EXCAVATE DOWN TO EXPOSE THE FULL THICKNESS OF SLAB TO TOP OF ABUTMENT SEAT.
- INSTALL 2 KIP COUNTERWEIGHT AT EACH ABUTMENT WINGWALL PILE (FOUR TOTAL) ON APPROACH PAVEMENT SIDE.
- INSTALL CONTAINMENT SYSTEM TO PREVENT DEBRIS FROM FALLING ON I-35. INSTALL ADDITIONAL TRAFFIC CONTROL ALONG MAINLINE I-35. TRAFFIC CONTROL SHALL BE COORDINATED WITH RAISING OPERATIONS.
- ENERGIZE JACKS. RAISE BRIDGE UNTIL VISIBLE GAP BETWEEN EXISTING SLAB AND SUBSTRUCTURE. CHECK ALL JACK REACTIONS, HYDRAULIC PUMPS, AND DEFLECTIONS. GAP AT ALL SUBSTRUCTURE ELEMENTS SHOULD BE EQUAL. ADJUST JACK PRESSURES UNTIL REACTIONS AT ABUTMENTS ARE EQUAL AND REACTIONS AT SHOULDER PIERS ARE EQUAL. RECORD JACK REACTIONS AS "TARGET REACTIONS." AFTER LIFT-OFF CHECK IS COMPLETE, CONTINUE RAISE.
- RAISE BRIDGE 8"±. MAINTAIN "TARGET REACTIONS" THROUGHOUT LIFT. SEE JACKING TABLE FOR MORE INFORMATION. LOCK ALL JACKS. INSTALL TEMPORARY STEEL BOLSTERS AT BRACKETS. SHIM TIGHT. RELEASE JACKS UNIFORMLY ACROSS ALL SUBSTRUCTURE LOCATIONS.
- INSTALL SHIM STACK BELOW JACKS. RESET JACKS. ENERGIZE JACKS. CONTINUE RAISING BRIDGE WHILE MONITORING PRESSURES, REACTIONS, AND DEFLECTIONS.
- REPEAT STEPS 11 AND 12 AS REQUIRED TO RAISE BRIDGE TO FINAL ELEVATION +3". LOCK ALL JACKS.
- PRIOR TO INSTALLATION OF PREFABRICATED BOLSTERS, CLEAN BEARING SEATS WITH WIRE BRUSH AND COMPRESSED AIR. PERFORM VISUAL INSPECTION OF SEATS. IF ANY DEFECTS ARE NOTED, NOTIFY THE ENGINEER.
- INSTALL BOLSTERS. SEE SUGGESTED BOLSTER INSTALLATION DETAILS.
- ONCE BOLSTERS ARE PERMANENTLY INSTALLED, LOWER BRIDGE TO FINAL ELEVATION. RELEASE JACKS AND REMOVE FALSEWORK. PATCH HOLES AT PIERS AND CUT ANCHORS FLUSH AT ABUTMENTS. REMOVE COUNTERWEIGHTS FROM STEP NO. 8.
- RE-OPEN I-35 TO 2 LANES IN EACH DIRECTION.
- REMAINING IMPROVEMENTS TO STRUCTURE SHALL BE DONE WITH MINIMAL DISRUPTIONS TO MAINLINE TRAFFIC.
- AFTER WORK IS COMPLETED FOR BRIDGE AND ROADWAY IMPROVEMENTS, LOCAL ROAD MAY BE RE-OPENED TO TRAFFIC.

JACKING TABLE BRIDGES A-F					
SUBSTRUCTURE LOCATION	NUMBER OF JACKS	TOTAL LOAD	ANTICIPATED REACTION	MAXIMUM REACTION	MAX. DIFF. DISPLACEMENT
		KIP	KIP/JACK	KIP/JACK	IN
ABUTMENT NO. 1	5	45	9	14	±½
PIER NO. 1	2	420	210	225	±⅝
PIER NO. 2	4	592	148	210	±⅝
PIER NO. 3	2	420	210	225	±⅝
ABUTMENT NO. 2	5	45	9	14	±½

JACKING TABLE BRIDGE G					
SUBSTRUCTURE LOCATION	NUMBER OF JACKS	TOTAL LOAD	ANTICIPATED REACTION	MAXIMUM REACTION	MAX. DIFF. DISPLACEMENT
		KIP	KIP/JACK	KIP/JACK	IN
ABUTMENT NO. 1	5	54	11	15	±½
PIER NO. 1	2	455	227	247	±⅝
PIER NO. 2	4	645	161	234	-⅝ TO +¼
PIER NO. 3	2	455	227	247	±⅝
ABUTMENT NO. 2	5	54	11	15.0	±½

JACKING TABLE BRIDGE J					
SUBSTRUCTURE LOCATION	NUMBER OF JACKS	TOTAL LOAD	ANTICIPATED REACTION	MAXIMUM REACTION	MAX. DIFF. DISPLACEMENT
		KIP	KIP/JACK	KIP/JACK	IN
ABUTMENT NO. 1	5	44	9	12	±½
PIER NO. 1	2	364	182	197	±⅝
PIER NO. 2	4	520	130	182	-⅝ TO +¼
PIER NO. 3	2	364	182	197	±⅝
ABUTMENT NO. 2	5	44	9	12.0	±½


NOTE: ALL ANTICIPATED JACK REACTIONS WERE DETERMINED USING 1.0 *DL. DIFFERENTIAL DISPLACEMENT IS MEASURED RELATIVE TO THE TOTAL DISPLACEMENT MEASURED AT THE ADJACENT SUBSTRUCTURE LOCATION(S). LIFTING OPERATIONS WILL BE STOPPED IF MAXIMUM JACK REACTIONS OR MAXIMUM DIFFERENTIAL DISPLACEMENTS ARE APPROACHED UNTIL MITIGATION PLAN HAS BEEN APPROVED BY ON-SITE ENGINEER.




PRE-RAISE TYPICAL SECTION
(SUGGESTED MAINTENANCE OF TRAFFIC)

BRIDGE A-G & J COUNTY ROADS OVER I-35		KAY COUNTY		Design	SJK	07/18
BRIDGE RAISING SEQUENCE AND JACKING TABLES				Detail	KNB	10/18
				Check	SJK	10/18
Squad: Engr.: THOMAS				STATE OF OKLAHOMA DEPARTMENT OF TRANSPORTATION		
JOB/PIECE NO. 24432(15)				SHEET NO. B001		


REVISIONS		
REV. NO.	DESCRIPTION	DATE



PLAN



ELEVATION




NORTH AVE. VERTICAL PROFILE DATA


- NOTES:
- ELEVATION SHOWS THE BRIDGE IN THE RAISED POSITION.
 - * APPLY CONCRETE SURFACE FINISH TO THE SLAB FASCIAS, THE UNDERSIDE OF THE SLAB, THE EXPOSED ABUTMENT AND WINGWALL SURFACES, AND THE PIERS.
 - SEE ABUTMENT AND PIER FALSEWORK DETAILS FOR TEMPORARY JACK LOCATIONS.
 - CLEARANCES SHOWN ARE TO THE FUTURE I-35 OVERLAY PROJECT.
 - STATIONS AND DIMENSIONS GIVEN ARE APPROXIMATE. EXISTING STATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED.

BRIDGE "A" NORTH AVE. OVER I-35		KAY COUNTY	
GENERAL PLAN AND ELEVATION		Design	JDK 10/17
EXISTING 30'-55'-55'-30' CONT. CONC. SLAB SPANS 24' CLEAR ROADWAY		Detail	KNB 10/17
STATE OF OKLAHOMA		Check	SJK 07/18
DEPARTMENT OF TRANSPORTATION		Squad	Engr: THOMAS
JOB/PIECE NO. 24432(15)		SHEET NO. B002	


REVISIONS		
REV. NO.	DESCRIPTION	DATE



PLAN



ELEVATION






HIGHLAND AVE. VERTICAL PROFILE DATA

- NOTES:
- ELEVATION SHOWS THE BRIDGE IN THE RAISED POSITION.
 - * APPLY CONCRETE SURFACE FINISH TO THE SLAB FASCIAS, THE UNDERSIDE OF THE SLAB, THE EXPOSED ABUTMENT AND WINGWALL SURFACES, AND THE PIERS.
 - SEE ABUTMENT AND PIER FALSEWORK DETAILS FOR TEMPORARY JACK LOCATIONS.
 - CLEARANCES SHOWN ARE TO THE FUTURE I-35 OVERLAY PROJECT.
 - STATIONS AND DIMENSIONS GIVEN ARE APPROXIMATE. EXISTING STATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED.

BRIDGE "B" HIGHLAND AVE. OVER I-35		KAY COUNTY	
GENERAL PLAN AND ELEVATION		Design	JDK 10/17
EXISTING 30'-55'-55'-30' CONT. CONC. SLAB SPANS 24' CLEAR ROADWAY		Detail	KNB 10/17
STATE OF OKLAHOMA		Check	SJK 07/18
DEPARTMENT OF TRANSPORTATION		Squad	Engr: THOMAS
JOB/PIECE NO. 24432(15)		SHEET NO. B003	



REV. NO.	DESCRIPTION	REVISIONS	DATE




- NOTES:**
- ELEVATION SHOWS THE BRIDGE IN THE RAISED POSITION.
 - * APPLY CONCRETE SURFACE FINISH TO THE SLAB FASCIAS, THE UNDERSIDE OF THE SLAB, THE EXPOSED ABUTMENT AND WINGWALL SURFACES, AND THE PIERS.
 - SEE ABUTMENT AND PIER FALSEWORK DETAILS FOR TEMPORARY JACK LOCATIONS.
 - CLEARANCES SHOWN ARE TO THE FUTURE I-35 OVERLAY PROJECT.
 - STATIONS AND DIMENSIONS GIVEN ARE APPROXIMATE. EXISTING STATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED.

BRIDGE "C" HARTFORD AVE. OVER I-35		KAY COUNTY	
GENERAL PLAN AND ELEVATION		Design	JDK 10/17
EXISTING 30'-55'-55'-30' CONT. CONC. SLAB SPANS 24' CLEAR ROADWAY		Detail	KNB 10/17
STATE OF OKLAHOMA		Check	SJK 07/18
DEPARTMENT OF TRANSPORTATION		Squad	Eng: THOMAS
JOBPIECE NO. 24432(15)		SHEET NO. B004	


REVISIONS		
REV. NO.	DESCRIPTION	DATE



PLAN



ELEVATION




COLEMAN ROAD VERTICAL PROFILE DATA


- NOTES:
- ELEVATION SHOWS THE BRIDGE IN THE RAISED POSITION.
 - * APPLY CONCRETE SURFACE FINISH TO THE SLAB FASCIAS, THE UNDERSIDE OF THE SLAB, THE EXPOSED ABUTMENT AND WINGWALL SURFACES, AND THE PIERS.
 - SEE ABUTMENT AND PIER FALSEWORK DETAILS FOR TEMPORARY JACK LOCATIONS.
 - CLEARANCES SHOWN ARE TO THE FUTURE I-35 OVERLAY PROJECT.
 - STATIONS AND DIMENSIONS GIVEN ARE APPROXIMATE. EXISTING STATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED.

BRIDGE "D" COLEMAN ROAD OVER I-35		KAY COUNTY	
GENERAL PLAN AND ELEVATION		Design	JDK 10/17
EXISTING 30'-55'-55'-30' CONT. CONC. SLAB SPANS 24' CLEAR ROADWAY		Detail	KNB 10/17
STATE OF OKLAHOMA		Check	SJK 07/18
DEPARTMENT OF TRANSPORTATION		Squad	Engr: THOMAS
JOBPIECE NO. 24432(15)		SHEET NO. B005	


REVISIONS		
REV. NO.	DESCRIPTION	DATE



PLAN






ELEVATION



- NOTES:
- ELEVATION SHOWS THE BRIDGE IN THE RAISED POSITION.
 - * APPLY CONCRETE SURFACE FINISH TO THE SLAB FASCIAS, THE UNDERSIDE OF THE SLAB, THE EXPOSED ABUTMENT AND WINGWALL SURFACES, AND THE PIERS.
 - SEE ABUTMENT AND PIER FALSEWORK DETAILS FOR TEMPORARY JACK LOCATIONS.
 - CLEARANCES SHOWN ARE TO THE FUTURE I-35 OVERLAY PROJECT.
 - STATIONS AND DIMENSIONS GIVEN ARE APPROXIMATE. EXISTING STATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED.

BRIDGE "E" CHRYSLER AVE. OVER I-35		KAY COUNTY	
GENERAL PLAN AND ELEVATION		Design	JDK 10/17
EXISTING 30'-55'-55'-30' CONT. CONC. SLAB SPANS 24' CLEAR ROADWAY		Detail	KNB 10/17
STATE OF OKLAHOMA		Check	SJK 07/18
DEPARTMENT OF TRANSPORTATION		Squad	Engr: THOMAS
JOB/PIECE NO. 24432(15)		SHEET NO. B006	




REVISIONS		
REV. NO.	DESCRIPTION	DATE



- NOTES:
- ELEVATION SHOWS THE BRIDGE IN THE RAISED POSITION.
 - * APPLY CONCRETE SURFACE FINISH TO THE SLAB FASCIAS, THE UNDERSIDE OF THE SLAB, THE EXPOSED ABUTMENT AND WINGWALL SURFACES, AND THE PIERS.
 - SEE ABUTMENT AND PIER FALSEWORK DETAILS FOR TEMPORARY JACK LOCATIONS.
 - CLEARANCES SHOWN ARE TO THE FUTURE I-35 OVERLAY PROJECT.
 - STATIONS AND DIMENSIONS GIVEN ARE APPROXIMATE. EXISTING STATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED.

BRIDGE "F" FERGUSON AVE. OVER I-35		KAY COUNTY	
GENERAL PLAN AND ELEVATION		Design	JDK 10/17
EXISTING 30'-55'-55'-30' CONT. CONC. SLAB SPANS 24' CLEAR ROADWAY		Detail	KNB 10/17
STATE OF OKLAHOMA		Check	SJK 07/18
DEPARTMENT OF TRANSPORTATION		Squad	Engr: THOMAS
JOB/PIECE NO. 24432(15)		SHEET NO. B007	


REV. NO.	DESCRIPTION	REVISIONS	DATE




- NOTES:
- ELEVATION SHOWS THE BRIDGE IN THE RAISED POSITION.
 - * APPLY CONCRETE SURFACE FINISH TO THE SLAB FASCIAS, THE UNDERSIDE OF THE SLAB, THE EXPOSED ABUTMENT AND WINGWALL SURFACES, AND THE PIERS.
 - SEE ABUTMENT AND PIER FALSEWORK DETAILS FOR TEMPORARY JACK LOCATIONS.
 - CLEARANCES SHOWN ARE TO THE FUTURE I-35 OVERLAY PROJECT.
 - STATIONS AND DIMENSIONS GIVEN ARE APPROXIMATE. EXISTING STATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED.

BRIDGE "G" ADOBE ROAD OVER I-35		KAY COUNTY	
GENERAL PLAN AND ELEVATION		Design	WJS 10/17
EXISTING 31'-56.5'-56.5'-31' CONT. CONC. SLAB SPANS 24' CLEAR ROADWAY		Detail	KNB 10/17
STATE OF OKLAHOMA		Check	SJK 07/18
DEPARTMENT OF TRANSPORTATION		Squad	Engr: THOMAS
JOB/PIECE NO. 24432(15)		SHEET NO. B008	


REVISIONS		
REV. NO.	DESCRIPTION	DATE



PLAN




ELEVATION




- NOTES:
- ELEVATION SHOWS THE BRIDGE IN THE RAISED POSITION.
 - * APPLY CONCRETE SURFACE FINISH TO THE SLAB FASCIAS, THE UNDERSIDE OF THE SLAB, THE EXPOSED ABUTMENT AND WINGWALL SURFACES, AND THE PIERS.
 - SEE ABUTMENT AND PIER FALSEWORK DETAILS FOR TEMPORARY JACK LOCATIONS.
 - CLEARANCES SHOWN ARE TO THE FUTURE I-35 OVERLAY PROJECT.
 - STATIONS AND DIMENSIONS GIVEN ARE APPROXIMATE. EXISTING STATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED.

BRIDGE "J" INDIAN ROAD OVER I-35		KAY COUNTY	
GENERAL PLAN AND ELEVATION		Design	JDK 10/17
EXISTING 30'-55'-55'-30' CONT. CONC. SLAB SPANS 20' CLEAR ROADWAY		Detail	KNB 10/17
STATE OF OKLAHOMA		Check	SJK 07/18
DEPARTMENT OF TRANSPORTATION		Squad	Eng: THOMAS
JOB/PIECE NO. 24432(15)		SHEET NO. B009	


REVISIONS		
REV. NO.	DESCRIPTION	DATE



ABUTMENT NO. 1 ELEVATION
(LOOKING WEST, ABUTMENT NO. 2 SIMILAR)
(SLAB NOT SHOWN FOR CLARITY)



SECTION A-A
(PILES NOT SHOWN FOR CLARITY)



ABUTMENT BRACKET DETAIL

ALL PLATE THICKNESSES ARE 1/2\"/>


TABLE OF RAISE DIMENSIONS	
LOCATION	H
BRIDGE "A"	1'-2"
BRIDGE "B"	11"
BRIDGE "C"	8"
BRIDGE "D"	1'-5"
BRIDGE "E"	1'-6"
BRIDGE "F"	1'-3"
BRIDGE "G"	1'-3"

NOTES:


- FALSEWORK AND JACKING SHOWN ARE FOR CONTRACTOR'S INFORMATION ONLY. ALTERNATIVE FALSEWORK AND JACKING MAY BE USED WITH THE APPROVAL OF THE ENGINEER.
- JACKS SHALL BE DESIGNED FOR NOT LESS THAN 1.5 TIMES THE ESTIMATED MAXIMUM JACKING LOAD. SEE JACKING TABLE ON BRIDGE RAISING SEQUENCE SHEET.
- ABUTMENT ADHESIVE ANCHORS SHALL BE STAINLESS STEEL. AFTER BRIDGE RAISE IS COMPLETE AND FALSEWORK HAS BEEN REMOVED, ADHESIVE ANCHORS SHALL BE CUT OFF FLUSH WITH THE FACE OF THE ABUTMENT.
- ABUTMENT ADHESIVE ANCHORS ARE ASSUMED TO HAVE A MAXIMUM EMBEDMENT LENGTH OF 7.875". FOR EMBEDMENT LENGTH GREATER THAN 7.875", CONTRACTOR SHALL CHECK FOR INTERFERENCE WITH PRECAST PILES. HAS-R STAINLESS STEEL HILTI ADHESIVE ANCHORS WITH HIT-RE 500 V3 EPOXY ADHESIVE OR APPROVED EQUIVALENT MAY BE USED.
- ALL WELDS THIS SHEET SHALL BE DOUBLE-SIDED 3/16" FILLET WELDS MINIMUM UNLESS NOTED OTHERWISE. CJP WELDS MAY BE SUBSTITUTED FOR FILLET WELDS. NO FIELD WELDING IS PERMITTED FOR FABRICATION OF BOLSTERS AND FALSEWORK.
- * DIMENSIONS SHOWN ARE TAKEN FROM EXISTING PLANS. FIELD VERIFY.
- RAISE DIMENSION OF "H" BASED ON ELEVATIONS NOTED ON GENERAL PLAN AND ELEVATION SHEET. ADJUSTMENTS WILL BE NEEDED IF ELEVATIONS ARE FOUND TO BE LOWER THAN THOSE NOTED.
- ALL STRUCTURAL STEEL SHALL CONFORM TO AASHTO M270 GR. 50.

BRIDGE "A" - "G" COUNTY ROAD OVER I-35		KAY COUNTY		Design	SJK	10/17
ABUTMENT FALSEWORK TYPE 1				Detail	KNB	10/17
				Check	SJK	07/18
24'-0" CLEAR ROADWAY				Squad	THOMAS	
				Engr:	THOMAS	
STATE OF OKLAHOMA		DEPARTMENT OF TRANSPORTATION		JOBPIECE NO. 24432(15)		
			SHEET NO. B010			

REVISIONS		
REV. NO.	DESCRIPTION	DATE



PIER ELEVATION
(SLAB NOT SHOWN FOR CLARITY)




PIER BRACKET DETAIL
ALL PLATE THICKNESSES ARE 1" UNLESS NOTED OTHERWISE

** D DENOTES THREADED ROD DIAMETER.
D = 2 1/2" (BRIDGES A-F)
D = 3" (BRIDGE G)

NOTES:


- SEE NOTES ON SHEET B010.
- * DIMENSIONS SHOWN ARE TAKEN FROM EXISTING PLANS. FIELD VERIFY AS NEEDED.
- ALL WELDS THIS SHEET SHALL BE DOUBLE SIDED 1/2" FILLET WELDS MINIMUM UNLESS NOTED OTHERWISE. CJP WELDS MAY BE SUBSTITUTED FOR FILLET WELDS. NO FIELD WELDING IS PERMITTED FOR FABRICATION OF BOLSTERS AND FALSEWORK.
- RAISE DIMENSION OF "H" BASED ON ELEVATIONS NOTED IN GENERAL PLAN AND ELEVATION SHEET. ADJUSTMENTS WILL BE NEEDED IF ELEVATIONS ARE FOUND TO BE LOWER THAN THOSE NOTED.
- FOR "H" DIMENSION, SEE TABLE ON SHEET B010.
- THREADED ROD SHALL CONFORM TO ASTM A722, GR. 150.




SECTION A-A
(PIER NO. 2 SHOWN)

(JACKS LOCATED AT PIERS NO. 1 AND NO. 3 AS SHOWN IN PLANS.)

BRIDGE "A" - "G"		KAY COUNTY	
COUNTY ROAD OVER I-35		Design	SJK 10/17
PIER FALSEWORK TYPE 1		Detail	KNB 10/17
		Check	SJK 07/18
24'-0" CLEAR ROADWAY		Squad	THOMAS
Engr: THOMAS			
STATE OF OKLAHOMA	DEPARTMENT OF TRANSPORTATION		
JOBPIECE NO. 24432(15)		SHEET NO.	B011




PERMANENT ABUTMENT BOLSTER



SQUARING DIAPHRAGM

(ABUTMENT SHOWN, PIER SIMILAR)
NOTE: ADJUST DIAPHRAGM AS NECESSARY TO MISS STUDS.



PERMANENT PIER BOLSTER


NOTES:

1. FIELD VERIFY SUBSTRUCTURE DIMENSIONS PRIOR TO FABRICATION OF BOLSTERS. BOLSTER LENGTH SHALL MATCH THE EXISTING SUBSTRUCTURE WIDTH OF 27'-0"±.
2. NO FIELD WELDING IS PERMITTED FOR FABRICATION OF BOLSTERS.
3. CONTRACTOR SHALL TAKE ANY NECESSARY STEPS TO ELIMINATE AIR POCKETS DURING BOLSTER CONCRETE PLACEMENT.
4. SHEAR STUDS SHALL BE SPACED AT 1'-0" MAX. O.C. SPACINGS. STUDS SHALL BE PLACED AT ALTERNATING LOCATIONS BOTH TRANSVERSELY ACROSS AND LONGITUDINALLY ALONG THE BOLSTER. TOTAL OF STUDS FOR EACH BOLSTER = 54.
5. SEALANT AND BACKER ROD ARE INCLUDED FOR PAYMENT WITH THE BID ITEM "STRUCTURAL STEEL".
6. A BOLSTER GAP OF 1 INCH ON EACH SIDE OF PIER HAS BEEN PROVIDED TO ALLOW FOR INSTALLATION OF BOLSTER BY ACCOMMODATING POTENTIAL FABRICATION AND CONSTRUCTION TOLERANCES OF THE STEEL BOLSTER AND EXISTING PIER CONCRETE. GAP SHALL BE CONFIRMED TO BE ADEQUATE FOR INSTALLATION WITH FIELD VERIFICATION.


TABLE OF VARIABLES				
LOCATION	H	H1	H2	H3
BRIDGE "A"	1'-2"	1'-1 1/2"	1'-0 3/4"	6"
BRIDGE "B"	11"	10 3/4"	9 3/4"	4"
BRIDGE "C"	8"	7 3/4"	6 3/4"	4"
BRIDGE "D"	1'-5"	1'-4 3/4"	1'-3 3/4"	9"
BRIDGE "E"	1'-6"	1'-5 3/4"	1'-4 3/4"	10"
BRIDGE "F"	1'-3"	1'-2 3/4"	1'-1 3/4"	7"
BRIDGE "G"	1'-3"	1'-1 3/4"	1'-1 1/4"	7"

BRIDGE "A" - "G" COUNTY ROAD OVER I-35		KAY COUNTY		Design	SJK	05/18
PERMANENT BOLSTER TYPE 1		24'-0" CLEAR ROADWAY		Detail	KNB	06/18
				Check	SJK	07/18
STATE OF OKLAHOMA		DEPARTMENT OF TRANSPORTATION		Squad	Engr: THOMAS	
JOB/PIECE NO. 24432(15)		SHEET NO. B012				

REVISIONS		
REV. NO.	DESCRIPTION	DATE




ABUTMENT NO. 1 ELEVATION
(LOOKING WEST, ABUTMENT NO. 2 SIMILAR)
(SLAB NOT SHOWN FOR CLARITY)



ABUTMENT BRACKET DETAIL
ALL PLATE THICKNESSES ARE 1/2\"/>

- NOTES:
- FALSEWORK AND JACKING SHOWN ARE FOR CONTRACTOR'S INFORMATION ONLY. ALTERNATIVE FALSEWORK AND JACKING MAY BE USED WITH THE APPROVAL OF THE ENGINEER.
 - JACKS SHALL BE DESIGNED FOR NOT LESS THAN 1.5 TIMES THE ESTIMATED MAXIMUM JACKING LOAD. SEE JACKING TABLE ON BRIDGE RAISING SEQUENCE SHEET.
 - ABUTMENT ADHESIVE ANCHORS SHALL BE STAINLESS STEEL. AFTER BRIDGE RAISE IS COMPLETE AND FALSEWORK HAS BEEN REMOVED, ADHESIVE ANCHORS SHALL BE CUT OFF FLUSH WITH THE FACE OF THE ABUTMENT.
 - ABUTMENT ADHESIVE ANCHORS ARE ASSUMED TO HAVE A MAXIMUM EMBEDMENT LENGTH OF 7.875". FOR EMBEDMENT LENGTH GREATER THAN 7.875", CONTRACTOR SHALL CHECK FOR INTERFERENCE WITH PRECAST PILES, HAS-R STAINLESS STEEL HILTI ADHESIVE ANCHORS WITH HIT-RE 500 V3 EPOXY ADHESIVE OR APPROVED EQUIVALENT MAY BE USED.
 - ALL WELDS THIS SHEET SHALL BE DOUBLE-SIDED 3/16" FILLET WELDS MINIMUM UNLESS NOTED OTHERWISE. CJP WELDS MAY BE SUBSTITUTED FOR FILLET WELDS. NO FIELD WELDING IS PERMITTED FOR FABRICATION OF BOLSTERS AND FALSEWORK.
 - * DIMENSIONS SHOWN ARE TAKEN FROM EXISTING PLANS. FIELD VERIFY.
 - RAISE DIMENSION OF 1'-6" BASED ON ELEVATIONS NOTED ON GENERAL PLAN AND ELEVATION SHEET. ADJUSTMENTS WILL BE NEEDED IF ELEVATIONS ARE FOUND TO BE LOWER THAN THOSE NOTED.
 - ALL STRUCTURAL STEEL SHALL CONFORM TO AASHTO M270 GR. 50.



REPLACE EXISTING COMPRESSIBLE FILL IF EXISTING MATERIAL IS DAMAGED FROM CONSTRUCTION ACTIVITIES




SECTION A-A
(PILES NOT SHOWN FOR CLARITY)

BRIDGE "J" INDIAN ROAD OVER I-35		KAY COUNTY	
ABUTMENT FALSEWORK TYPE 2		Design	SJK 10/17
20'-0" CLEAR ROADWAY		Detail	KNB 10/17
STATE OF OKLAHOMA		Check	SJK 07/18
DEPARTMENT OF TRANSPORTATION		Squad	THOMAS
JOB/PIECE NO. 24432(15)		Engr.	THOMAS
SHEET NO. B013			

REVISIONS		
REV. NO.	DESCRIPTION	DATE




- NOTES:
- SEE NOTES ON SHEET B013.
 - * DIMENSIONS SHOWN ARE TAKEN FROM EXISTING PLANS. FIELD VERIFY AS NEEDED.
 - ALL WELDS THIS SHEET SHALL BE DOUBLE SIDED 1/2" FILLET WELDS MINIMUM UNLESS NOTED OTHERWISE. CJP WELDS MAY BE SUBSTITUTED FOR FILLET WELDS. NO FIELD WELDING IS PERMITTED FOR FABRICATION OF BOLSTERS AND FALSEWORK.
 - RAISE DIMENSION OF 1'-6" BASED ON ELEVATIONS NOTED IN GENERAL PLAN AND ELEVATION SHEET. ADJUSTMENTS WILL BE NEEDED IF ELEVATIONS ARE FOUND TO BE LOWER THAN THOSE NOTED.
 - 2 1/2" Ø THREADED ROD SHALL CONFORM TO ASTM A722, GR. 150.




BRIDGE "J" INDIAN ROAD OVER I-35	KAY COUNTY	Design	SJK	10/17
PIER FALSEWORK TYPE 2		Detail	KNB	10/17
		Check	SJK	07/18
20'-0" CLEAR ROADWAY		Squad	THOMAS	
STATE OF OKLAHOMA		DEPARTMENT OF TRANSPORTATION	JOB/PIECE NO. 24432(15)	
				SHEET NO. B014

REVISIONS		
REV. NO.	DESCRIPTION	DATE




PERMANENT ABUTMENT BOLSTER



SQUARING DIAPHRAGM

(ABUTMENT SHOWN, PIER SIMILAR)
NOTE: ADJUST DIAPHRAGM AS NECESSARY TO MISS STUDS.




PERMANENT PIER BOLSTER

NOTES:

1. FIELD VERIFY SUBSTRUCTURE DIMENSIONS PRIOR TO FABRICATION OF BOLSTERS. BOLSTER LENGTH SHALL MATCH THE EXISTING SUBSTRUCTURE WIDTH OF 23'-0"±.
2. NO FIELD WELDING IS PERMITTED FOR FABRICATION OF BOLSTERS.
3. FIELD VERIFY EXISTING BEARING PL DIMENSIONS PRIOR TO FABRICATION.
4. CONTRACTOR SHALL TAKE ANY NECESSARY STEPS TO ELIMINATE AIR POCKETS DURING BOLSTER CONCRETE PLACEMENT.
5. SHEAR STUDS SHALL BE SPACED AT 1'-0" MAX. O.C. SPACINGS. STUDS SHALL BE PLACED AT ALTERNATING LOCATIONS BOTH TRANSVERSELY ACROSS AND LONGITUDINALLY ALONG THE BOLSTER. TOTAL OF STUDS FOR EACH BOLSTER = 46.
6. SEALANT AND BACKER ROD ARE INCLUDED FOR PAYMENT WITH THE BID ITEM "STRUCTURAL STEEL".
7. A BOLSTER GAP OF 1 INCH ON EACH SIDE OF PIER HAS BEEN PROVIDED TO ALLOW FOR INSTALLATION OF BOLSTER BY ACCOMMODATING POTENTIAL FABRICATION AND CONSTRUCTION TOLERANCES OF THE STEEL BOLSTER AND EXISTING PIER CONCRETE. GAP SHALL BE CONFIRMED TO BE ADEQUATE FOR INSTALLATION WITH FIELD VERIFICATION.

BRIDGE "J" INDIAN ROAD OVER I-35		KAY COUNTY		Design	SJK	05/18
PERMANENT BOLSTER TYPE 2 20'-0" CLEAR ROADWAY				Detail	KNB	06/18
				Check	SJK	07/18
STATE OF OKLAHOMA				DEPARTMENT OF TRANSPORTATION		Sheet No. B015
JOB PIECE NO. 24432(15)						


REVISIONS		
REV. NO.	DESCRIPTION	DATE



SUGGESTED ABUTMENT BOLSTER INSTALLATION

NOTE: WINGWALL AND PILES NOT SHOWN FOR CLARITY.

NOTE: TYPE 1 ABUTMENT BOLSTER SHOWN. TYPE 2 SIMILAR. STEEL PLATE ON TOP AND BOTTOM OF TYPE 2 BOLSTER IS CONTINUOUS.




SECTION A-A

SUGGESTED ABUTMENT BOLSTER INSTALLATION NOTES:


1. PLACE STEEL INSTALLATION WEDGES ON ABUTMENT CAP.
2. LOWER ABUTMENT BOLSTER ONTO WEDGES.
3. SLIDE BOLSTER UNTIL BEARING PAD IS CENTERED UNDER CL BEARING.
4. LIFT BACK EDGE OF BOLSTER USING LIFTING EYE. REMOVE STEEL WEDGES.
5. LOWER BOLSTER TO FINAL POSITION.

BRIDGE A - G & J COUNTY ROADS OVER I-35	KAY COUNTY	Design	SJK	05/18
ABUTMENT BOLSTER INSTALLATION		Detail	KNB	06/18
		Check	SJK	07/18
STATE OF OKLAHOMA		DEPARTMENT OF TRANSPORTATION	JOB PIECE NO. 24432(15)	
JOB PIECE NO. 24432(15)		SHEET NO. B016		Engr: THOMAS

REVISIONS		
REV. NO.	DESCRIPTION	DATE




SUGGESTED BOLSTER INSTALLATION DURING ROLL-IN



SECTION A-A

ROLLERS SUPPORTED BY CONSTRUCTION EQUIPMENT

NOTE: TYPE 1 PIER BOLSTER SHOWN. TYPE 2 SIMILAR.



SUGGESTED BOLSTER INSTALLATION AT SET DOWN

SUGGESTED PIER BOLSTER INSTALLATION NOTES:

1. INSTALL TEMPORARY BOLTED-ON INSTALLATION SUPPORTS. NOTE: TEMPORARY SUPPORTS BOLTED TO THE SUPERSTRUCTURE SHALL BE INSTALLED PRIOR TO BRIDGE RAISE.
2. LIFT BOLSTER AND SET ROLLER NOSE ON PIER WHILE SUPPORTING TRAILING END OF BOLSTER ON ROLLERS.
3. ROLL BOLSTER INTO FINAL POSITION USING WIRE ROPES.
4. TEMPORARY SUPPORT GEOMETRY SHALL BE SET SO AS THE ROLLER NOSE TRANSITIONS OFF THE PIER AND ONTO THE SUPPORT, THE LEADING END OF THE BOLSTER IS LOWERED INTO THE FINAL POSITION.
5. LOWER THE SUPPORT FOR THE TRAILING END OF THE BOLSTER TO SET BOLSTER ONTO PIER.

BRIDGE A - G & J COUNTY ROADS OVER I-35	KAY COUNTY	Design	SJK	05/18
		Detail	KNB	06/18
PIER BOLSTER INSTALLATION		Check	SJK	07/18
		Squad	THOMAS	
STATE OF OKLAHOMA	DEPARTMENT OF TRANSPORTATION	JOB/PIECE NO. 24432(15)	SHEET NO. B017	

REVISIONS		
REV. NO.	DESCRIPTION	DATE




APPROACH SLAB QUANTITIES			
ITEM	UNIT	APPROACH SLAB NO. 1	APPROACH SLAB NO. 2
25'-0" x 20'-0" APPROACH SLAB			
APPROACH SLAB	S.Y.	55.6	55.6
SAW-CUT GROOVING	S.Y.	50.8	50.8
CONCRETE RAIL (TR4)	L.F.	40.0	40.0
29'-0" x 20'-0" APPROACH SLAB			
APPROACH SLAB	S.Y.	64.5	64.5
SAW-CUT GROOVING	S.Y.	59.7	59.7
CONCRETE RAIL (TR4)	L.F.	40.0	40.0

- THE DEPARTMENT CONSIDERS THE COST OF CONCRETE, REINFORCING STEEL (INCLUDING SR1 AND SR2 BARS), BACKER ROD, RAPID CURE JOINT SEALANT, POLYSTYRENE AND POLYETHYLENE SHEETING TO BE INCLUDED IN THE CONTRACT UNIT PRICE OF "APPROACH SLAB".
- THERE IS AN ESTIMATED 23.4 CY OF CLASS AA CONCRETE AND AN ESTIMATED 4,340 LB. OF EPOXY COATED REINFORCING STEEL IN EACH APPROACH SLAB.
- THERE IS AN ESTIMATED 27.2 CY OF CLASS AA CONCRETE AND AN ESTIMATED 4,920 LB. OF EPOXY COATED REINFORCING STEEL IN EACH APPROACH SLAB.

TABLE OF VARIABLES						
LOCATION	A	B	C	D	E	F
BRIDGE "A"	29'-0"	14'-6"	13'-5"	15	44	2'-5½"
BRIDGE "B"	29'-0"	14'-6"	13'-5"	15	44	2'-2½"
BRIDGE "C"	29'-0"	14'-6"	13'-5"	15	44	1'-11½"
BRIDGE "D"	29'-0"	14'-6"	13'-5"	15	44	2'-8½"
BRIDGE "E"	29'-0"	14'-6"	13'-5"	15	44	2'-9½"
BRIDGE "F"	29'-0"	14'-6"	13'-5"	15	44	2'-6½"
BRIDGE "G"	29'-0"	14'-6"	13'-5"	15	44	2'-7½"
BRIDGE "J"	25'-0"	12'-6"	11'-5"	13	38	2'-10"

APPROACH SLAB BAR LIST (ONE SHOWN, TWO REQUIRED PER BRIDGE) (EPOXY COATED REINFORCING)				
MARK	SIZE	NO.	FORM	LENGTH
25'-0"x20'-0" APPROACH SLAB				
AT1	#4	42	STR.	12'-2"
AT2	#4	25	STR.	24'-8"
AL1	#4	26	STR.	19'-8"
AL2	#9	38	STR.	19'-8"
AL3	#4	38	BNT.	6'-10"
SR1	#5	106	BNT.	4'-1"
SR2	#5	16	BNT.	VARIES
SD1	#4	10	STR.	2'-0"
29'-0"x20'-0" APPROACH SLAB				
AT1	#4	42	STR.	14'-2"
AT2	#4	25	STR.	28'-8"
AL1	#4	30	STR.	19'-8"
AL2	#9	44	STR.	19'-8"
AL3	#4	38	BNT.	6'-10"
SR1	#5	106	BNT.	4'-1"
SR2	#5	16	BNT.	VARIES
SD1	#4	10	STR.	2'-0"


NOTE:
AL3 BARS SHALL BE FIELD CUT TO FIT WITHIN LIMITS OF APPROACH SLAB TO PROVIDE PROPER CLEARANCE.



TOP REINFORCING MAT DETAIL
APPROACH SLAB NO. 1

BOTTOM REINFORCING MAT DETAIL
APPROACH SLAB NO. 2

NOTE:
PLACE REINFORCING IN THE TOP OF THE APPROACH SLAB 2" FROM EITHER SIDE OF THE SAWED AND SEALED LONGITUDINAL JOINT. FOR ADDITIONAL DETAILS OF LONGITUDINAL JOINT, SEE STD. LECS-4



SECTION A









SECTION B

④ BOND BREAKER SHALL BE ONE 6 MIL OR TWO 4 MIL POLYETHYLENE SHEETS. BOND BREAKER SHALL EXTEND FULL WIDTH OF APPROACH SLAB AND FULL LENGTH UP TO THE BACK FACE OF THE ABUTMENT DIAPHRAGM.


NOTE:
SEE CONCRETE RAIL (TR4) SHEET FOR SR1 AND SR2 BAR BENDS AND ADDITIONAL DETAILS OF CONCRETE RAIL. FIELD VERIFY EXISTING DIMENSIONS.

BRIDGE A-G & J COUNTY ROADS OVER I-35		KAY COUNTY		Design	JDK	09/18
APPROACH SLAB DETAILS				Detail	KNB	09/18
				Check	WJS	10/18
STATE OF OKLAHOMA				DEPARTMENT OF TRANSPORTATION		Sheet No. B018
JOB/PIECE NO. 24432(15)				DATE		


REVISIONS		
REV. NO.	DESCRIPTION	DATE



NORMAL CROWN OR CROSS SLOPE



CONSTRUCTION JOINT R4 BARS #4 X 3'-4"



S BAR




SR1 BARS #5 X 4'-1"



T BARS #4 X 7'-0"



L BAR #4 X 1'-8"



SR2 BARS #5 X 4'-5 1/2" (MAX.)

CONCRETE TRAFFIC RAIL NOTES

CONSTRUCT THE CONCRETE TRAFFIC RAIL TO MEET THE REQUIREMENTS OF THE STANDARD SPECIFICATION FOR HIGHWAY CONSTRUCTION (ENGLISH) AS WELL AS THE FOLLOWING REQUIREMENTS.

CONTRACTOR SHALL FIELD VERIFY EXISTING RAIL DIMENSIONS PRIOR TO CONSTRUCTION OF RAIL TRANSITIONS. ALL RAIL TRANSITION LABOR AND MATERIALS SHALL BE INCLUDED IN THE PRICE BID PER LINEAR FOOT OF "CONCRETE RAIL (TR4)".

CLASS AA CONCRETE:
USE CLASS AA CONCRETE IN THE CONCRETE TRAFFIC RAIL. ALL COSTS OF CONCRETE TO BE INCLUDED IN THE PRICE BID PER LINEAR FOOT OF "CONCRETE RAIL (TR4)".

REINFORCING STEEL:
ALL REINFORCING STEEL, EXCEPT FOR THE S-BAR, USED IN THE CONCRETE TRAFFIC RAIL IS TO BE EPOXY COATED. WHEN TWO OR MORE S-BARS ARE USED IN A CONTINUOUS RAIL SECTION, BUTT THEIR ENDS TOGETHER WITHIN THE CENTER 3'-0" OF A RAIL POST. PLACE AND TIE ALL SR1 AND SR2 BARS BEFORE THE CONCRETE IS PLACED IN THE APPROACH SLABS. ALL REINFORCING STEEL PLACED WITHIN THE RAIL IS INCLUDED IN THE PRICE BID PER LINEAR FOOT OF "CONCRETE RAIL (TR4)". SR1 AND SR2 BARS ARE INCLUDED WITH THE BID ITEM "APPROACH SLAB".

GUARDRAIL CONNECTION:
FORM ALL DRILL HOLES, AS SHOWN, FOR THE CONNECTION OF THE THRIE-BEAM TERMINAL CONNECTION (END SHOE) AT THE LOCATIONS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. IT IS THE RESPONSIBILITY OF THE BRIDGE CONTRACTOR TO PROVIDE THE HOLES. THE CONTRACTOR THAT INSTALLS THE GUARDRAIL WILL BE RESPONSIBLE FOR INSTALLING THE THRIE-BEAM TERMINAL CONNECTION.


CONSTRUCTION JOINTS:
PLACE A CONSTRUCTION JOINT AT THE LOCATIONS SHOWN IN THE PLANS. PLACE 1/4" THICK PREFORMED EXPANSION MATERIAL IN THE CONSTRUCTION JOINT SUCH THAT IT COVERS THE ENTIRE AREA OF THE RAIL AND POST IN ACCORDANCE WITH THE DETAILS SHOWN.

CONCRETE RAIL CONSTRUCTION:
LOCATE POSTS AS SHOWN ON THIS SHEET CONSTRUCT OPENINGS SUCH THAT THE FACE OF THE POSTS ARE PERPENDICULAR TO THE ROADWAY PROFILE GRADE.

WATER BARRIER:
PROVIDE WATER BARRIER AT RAIL OPENINGS. PLACE THE CONCRETE FOR THE WATER BARRIER CONCURRENTLY WITH THE PLACEMENT OF THE CONCRETE IN THE POSTS. INCLUDE ALL COSTS OF WATER BARRIERS IN THE PRICE BID PER LINEAR FOOT OF "CONCRETE RAIL (TR4)".

BASIS OF PAYMENT

ITEM NO.	DESCRIPTION	UNIT
504(E)	CONCRETE RAIL (TR4)	L.F.



TYPICAL SECTION THRU RAIL

BRIDGE A-G & J COUNTY ROADS OVER I-35		KAY COUNTY	
Design	JDK	09/18	
Detail	RAW	09/18	
Check	WJS	10/18	
Squad	THOMAS		
Engr:	THOMAS		
STATE OF OKLAHOMA		DEPARTMENT OF TRANSPORTATION	
JOB/PIECENO. 24432(15)		SHEET NO. B019	

**CONCRETE TRAFFIC RAIL (TR4)
ON APPROACH SLAB**

REVISIONS		
REV. NO.	DESCRIPTION	DATE










TABLE OF VARIABLES					
LOCATION		DIM. A	DIM. B	DIM. C	SLOPE D
BRIDGE "A"	APPR. 1	38'-6"	38'-6"	26'-6"	**1.8
	APPR. 2	38'-6"	38'-6"	26'-6"	**1.8
BRIDGE "B"	APPR. 1	35'-0"	35'-0"	27'-2"	**1.8
	APPR. 2	35'-0"	35'-0"	27'-2"	**1.8
BRIDGE "C"	APPR. 1	37'-6"	37'-6"	27'-0"	**1.8
	APPR. 2	41'-6"	41'-6"	27'-2"	**1.8
BRIDGE "D"	APPR. 1	37'-0"	37'-0"	27'-0"	**1.9
	APPR. 2	37'-0"	37'-0"	27'-2"	**1.9
BRIDGE "E"	APPR. 1	37'-0"	37'-0"	27'-2"	**1.9
	APPR. 2	37'-0"	37'-0"	27'-2"	**1.9
BRIDGE "F"	APPR. 1	45'-0"	41'-0"	27'-5"	**1.8
	APPR. 2	42'-0"	42'-0"	27'-4"	**1.8
BRIDGE "G"	APPR. 1	30'-6"	30'-6"	28'-1"	2.0
	APPR. 2	30'-6"	30'-6"	28'-3"	2.0
BRIDGE "J"	APPR. 1	39'-6"	41'-6"	27'-0"	**1.9
	APPR. 2	41'-6"	41'-6"	27'-0"	**1.9

DIMENSIONS PROVIDED FOR SLOPE PAVING ARE APPROXIMATE. ** MATCH EXISTING SLOPE UNDER BRIDGE AND TRANSITION TO 2:1 MAX.

- NOTES:**
1. ALL EXISTING SLOPEWALLS SHALL BE REMOVED AND REPLACED. ALL REMOVAL WORK SHALL BE INCLUDED IN THE PRICE BID PER LUMP SUM "REMOVAL OF BRIDGE ITEMS".
 2. SHOULD THE 3'-0" DIMENSION CONFLICT WITH AN UNDERGROUND STRUCTURE (FOOTING, DRAINAGE STRUCTURE, ETC.), ADJUSTMENTS SHALL BE MADE TO THE DEPTH OF THE SLOPEWALL TO AVOID CONFLICT AS APPROVED BY FIELD ENGINEER.
 3. THE SLOPEWALL AND SLOPEDRAIN WILL BE PAID FOR AT THE UNIT PRICE BID PER SQUARE YARD OF SLOPE WALL (5') COMPLETED IN PLACE AS SHOWN ON THE PLANS. THE PRICE SHALL INCLUDE ALL COSTS OF JOINT FILLER, REINFORCING STEEL, LABOR, AND ALL OTHER INCIDENTALS NECESSARY TO COMPLETE THE WORK. ALL MATERIALS AND WORK SHALL BE IN ACCORDANCE WITH THAT PART OF SECTION 610 COVERING CONCRETE SIDEWALKS. SLOPEWALLS SHALL BE CONSTRUCTED WITH CLASS A CONCRETE. IN ACCORDANCE WITH SECTION 509, COARSE AGGREGATE FOR THIN SECTION CONCRETE (SEC. 701.06) MAY BE USED.
 4. ALL COST OF THE PIPE UNDERDRAIN (PERFORATED AND NON-PERFORATED), COVER MATERIAL (BOTH FINE AND COARSE), FILTER FABRIC, TRENCH EXCAVATION, STANDARD BEDDING MATERIAL, GRADING, CLSM BACKFILLING, AND EQUIPMENT AND LABOR FOR THEIR INSTALLATION SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE OF 6" PERFORATED PIPE UNDERDRAIN ROUND AND 6" NON-PERFORATED PIPE UNDERDRAIN ROUND.
 5. REINFORCING STEEL IS NON-EPOXY COATED.
 6. JOINT FILLER SHALL MEET THE REQUIREMENTS OF SECTION 701.08B.
 7. CLSM BACKFILL BENEATH APPROACHES IS INCLUDED IN THE PRICE BID PER CY OF CLSM BACKFILL.
 8. SLOPEWALL PAVING SECTIONS SHALL BE LIMITED TO A MAXIMUM OF 250 SQ. FT. OF SURFACE AREA. HORIZONTAL AND VERTICAL JOINTS SHALL BE PLACED TO MEET THESE REQUIREMENTS, WITH 90° ANGLES BETWEEN JOINTS MAINTAINED WHERE POSSIBLE.


BRIDGE A-G & J COUNTY ROADS OVER I-35		KAY COUNTY	
SLOPEWALL AND DRAIN DETAILS		Design	JDK 09/18
		Detail	KNB 09/18
		Check	WJS 10/18
		Squad	
		Engr:	THOMAS
STATE OF OKLAHOMA		DEPARTMENT OF TRANSPORTATION	
JOB/PIECE NO. 24432(15)		SHEET NO. B020	

REVISIONS		
REV. NO.	DESCRIPTION	DATE



PLAN

NOTE: HATCHED AREA DENOTES BRIDGE SECTION BEING REMOVED.



STAGE ONE ELEVATION

NOTE: HATCHED AREA DENOTES BRIDGE SECTION BEING REMOVED.

NOTE:
SEE TRAFFIC CONTROL PLANS FOR
LOCATION OF TEMPORARY PORTABLE
LONGITUDINAL BARRIER AND LANE
CONFIGURATIONS.

NOTE:
FALSEWORK TOWER LOCATIONS WERE ASSUMED AS SHOWN.
FALSEWORK REACTIONS PROVIDED ARE BASED ON PLAN
LOCATIONS. CONTRACTOR IS RESPONSIBLE FOR ACTUAL
FALSEWORK LOCATIONS AND DESIGN. IF ALTERNATE
FALSEWORK LOCATIONS ARE USED, CONTRACTOR IS
RESPONSIBLE FOR FALSEWORK LOADS AND BRIDGE STABILITY.

FALSEWORK TOWER REACTIONS	
LOCATION	k/TOWER
BACK SPAN	40
MAIN SPAN	120

NOTE: ALL ANTICIPATED REACTIONS WERE DETERMINED USING 1.25 *DL.
REACTION LOCATIONS FOR TOWERS WERE ASSUMED AT 5 FT FROM ϕ OF BRIDGE.


STAGE 1 SUGGESTED SEQUENCE

1. INSTALL TRAFFIC CONTROL PER TRAFFIC CONTROL PLANS.
2. INSTALL CONTAINMENT SYSTEM OVER ROADWAY.
REMOVE CONCRETE BARRIER PILASTERS AND RAIL.
3. INSTALL TEMPORARY FALSEWORK AT BOTH BACK SPANS AND MAIN SPANS.
4. SAW CUT MAIN SPANS IN LONGITUDINAL DIRECTION. OPTIONAL BACK SPAN
SAW CUT IN LONGITUDINAL DIRECTION.

NOTE: ESTIMATED WEIGHT OF PICKED SECTION
OVER ROADWAY = 132 KIPS (UNFACTORED).
CONTRACTOR IS RESPONSIBLE FOR FINAL
PICK WEIGHTS.

BRIDGE "H" HOME ROAD OVER I-35		KAY COUNTY		Design	SJK	09-18
HOME ROAD DEMOLITION-ROLLING ROAD BLOCK ALTERNATIVE (1 OF 2)		EXISTING 30'-55'-55'-30' CONC. SLAB SPANS 20' CLEAR ROADWAY		Detail	RAW	09-18
STATE OF OKLAHOMA		DEPARTMENT OF TRANSPORTATION		Check	SJK	10-18
JOB/PIECE NO. 24432(15)		SHEET NO. B021		Squad	Engr: THOMAS	

REVISIONS		
REV. NO.	DESCRIPTION	DATE




STAGE TWO ELEVATION

NOTE: HATCHED AREA DENOTES BRIDGE SECTION BEING REMOVED.

NOTE:
SEE TRAFFIC CONTROL PLANS FOR
LOCATION OF TEMPORARY PORTABLE
LONGITUDINAL BARRIER AND LANE
CONFIGURATIONS.

STAGE 2 SUGGESTED SEQUENCE:

1. SAW CUT FIRST MAIN SPAN IN TRANSVERSE DIRECTION AT LOCATIONS NOTED ON PLANS.
2. RIG PICK 1 TO THE CRANE.
3. BEGIN ROLLING ROAD BLOCK.
4. PICK AND REMOVE PICK 1. RELEASE ROLLING ROAD BLOCK.
5. RIG PICK 2 TO THE CRANE.
6. BEGIN ROLLING ROAD BLOCK.
7. PICK AND REMOVE PICK 2. RELEASE ROLLING ROAD BLOCK.
8. CONTRACTOR HAS THE OPTION TO REMOVE TEMPORARY SUPPORT IN SPAN 2 ADJACENT TO PIER NO. 1. ALL OTHER TEMPORARY SUPPORTS TO REMAIN FOR STABILITY.



STAGE THREE ELEVATION

NOTE: HATCHED AREA DENOTES BRIDGE SECTION BEING REMOVED.


STAGE 3 SUGGESTED SEQUENCE:

1. SAW CUT SECOND MAIN SPAN IN TRANSVERSE DIRECTION AT LOCATIONS NOTED ON PLANS.
2. RIG PICK 3 TO THE CRANE.
3. BEGIN ROLLING ROAD BLOCK.
4. PICK AND REMOVE PICK 3. RELEASE ROLLING ROAD BLOCK.
5. RIG PICK 4 TO THE CRANE.
6. BEGIN ROLLING ROAD BLOCK.
7. PICK AND REMOVE PICK 4. RELEASE ROLLING ROAD BLOCK.
8. REMOVE TEMPORARY SUPPORT ADJACENT TO PIER NO. 3. PROVIDE TEMPORARY SUPPORT AT CENTER PIER CANTILEVER UNTIL CENTER PIER SECTION IS REMOVED.
9. REMOVE REMAINING BRIDGE SUBSTRUCTURE SECTIONS AND SUBSTRUCTURE. SUBSTRUCTURE SHALL BE REMOVED TO AT LEAST 2 FT BELOW PROPOSED GROUND LINE.


PROPOSED GROUND LINE NOT SHOWN.
SEE ROADWAY PLANS FOR PROPOSED
GRADING LIMITS (TYPICAL)

BRIDGE "H" HOME ROAD OVER I-35		KAY COUNTY		Design	SJK	09-18
HOME ROAD DEMOLITION-ROLLING ROAD BLOCK ALTERNATIVE (2 OF 2) EXISTING 30'-55'-55'-30' CONT. CONC. SLAB SPANS 20' CLEAR ROADWAY				Detail	RAW	09-18
				Check	SJK	10-18
				Squad	THOMAS	
STATE OF OKLAHOMA				DEPARTMENT OF TRANSPORTATION		
JOB/PIECE NO. 24432(15)				SHEET NO. B022		

REVISIONS		
REV. NO.	DESCRIPTION	DATE



PLAN



ELEVATION

NOTE: FALSEWORK TOWER LOCATIONS WERE ASSUMED AS SHOWN. FALSEWORK REACTIONS PROVIDED ARE BASED ON PLAN LOCATIONS. CONTRACTOR IS RESPONSIBLE FOR ACTUAL FALSEWORK LOCATIONS AND DESIGN. IF ALTERNATE FALSEWORK LOCATIONS ARE USED, CONTRACTOR IS RESPONSIBLE FOR FALSEWORK LOADS AND BRIDGE STABILITY.

SUGGESTED DEMOLITION SEQUENCE:

1. CONSTRUCT CROSSOVERS AND INSTALL TRAFFIC CONTROL. BEGIN HEAD-TO-HEAD TRAFFIC USING CROSSOVER.
2. CLOSE HOME ROAD. INSTALL TEMPORARY FALSEWORK.
3. TRANSVERSE SAW CUT THE BRIDGE DECK AT LOCATION SHOWN IN PLANS. CONTRACTOR HAS THE OPTION TO REMOVE BARRIER RAIL & PILASTERS PRIOR TO SAW CUT.
4. PROTECT ROADWAY BELOW. ANY DAMAGE TO I-35 AS A RESULT OF BRIDGE DEMO WILL BE REPAIRED AT NO COST TO OWNER. REMOVE THE FIRST SECTION OF THE BRIDGE. ALL SUBSTRUCTURE SHALL BE REMOVED TO AT LEAST 2 FT BELOW PROPOSED GROUND LINE.
5. AFTER FIRST SECTION OF BRIDGE HAS BEEN REMOVED AND ROADWAY HAS BEEN CLEARED OF DEBRIS, USE CROSSOVERS TO SWITCH HEAD-TO-HEAD TRAFFIC TO OPPOSITE BOUND.
6. REMOVE THE REMAINING SECTIONS OF THE BRIDGE.

MAXIMUM FACTORED FALSEWORK TOWER REACTION = 150 KIP/TOWER
INCLUDES BARRIER PILASTERS AND RAIL

NOTE: ALL ANTICIPATED REACTIONS WERE DETERMINED USING 1.25 *DL.
REACTION LOCATIONS FOR TOWERS WERE ASSUMED AT 5 FT FROM Q. BRIDGE.

BRIDGE "H" HOME ROAD OVER I-35	KAY COUNTY	Design	SJK	09-18
HOME ROAD DEMOLITION CROSSOVER ALTERNATIVE EXISTING 30'-55'-55'-30' CONC. SLAB SPANS 20' CLEAR ROADWAY	STATE OF OKLAHOMA	Detail	RAW	09-18
		Check	SJK	10-18
		Squad Engr: THOMAS		
DEPARTMENT OF TRANSPORTATION	JOB/PIECE NO. 24432(15)	SHEET NO. B023		


FOR INFORMATION ONLY

DESIGN DATA

Concrete 1,000 psi
Reinforcing Steel 18,000 psi
Design Live Load H15-53

Maximum Foundation Loads:
Abutments 18.2 Ton/Pile
Piers: Direct Load 1.92 T/p'
Max. Load 2.51 T/p'

**BRIDGE "H"
HOME ROAD OVER I-35**



PLAN
Scale: 1" = 10'


† SUMMARY OF QUANTITIES

ITEM No.	ITEM	UNIT	Abut.	Piers	Super Structure	Total
202.06a	Class D Excav.	C.Y.			200	200
501.06b	Substr. Excav. Common	C.Y.	120	355		475
505.06	Concrete Rails	L.F.			343.0	343.0
509.06a	Class A Conc.	C.Y.	37.0	50.1		87.1
509.06a	Class A Conc. Pier Base	C.Y.		60.5		60.5
509.06b	Class A Conc.	C.Y.			311.9	311.9
511.06	Reinf. Steel	Lbs.	4960	11,025		55,025
514.06d	R.C. Piling	L.F.	390			390
514.06a	Concrete Test Pile	EA	1			1
Special	4" Conc. Slope Pavement	S.Y.	155.3			155.3

VERTICAL CURVE DATA

3M. "X" on NW Corner N. Home Rd. Lt.
Sta. 78+80.38 Elev. 1071.03
RM 409 Spike in 18" Oak 60' Rt.
Sta. 61+66 Elev. 1061.51

Sta. 78+02.76
End of Slab &
Sk. of Sk. Wall



GENERAL ELEVATION
Scale: 1" = 10'

* Non-Participating Item

All construction and materials shall be in accordance with the Oklahoma Standard Specifications of 1954 and Special Provisions.

All exposed concrete surfaces shall have a carborundum finish.

All reinforcing steel bars shall conform to A.S.T.M. Specifications A-305-49.

All abutment piling shall be driven using leads of sufficient strength to control piles.

Abutment piling shall be driven to practical refusal if above grade or to a minimum bearing of 50 tons if at or below grade.

All Abutment Piling shall be driven through the compacted fill 12" Pilot holes shall be drilled to natural ground line. All cost of pilot holes shall be included in the unit price bid for R.C. Piling.

Time will not be charged against the Bridge Contractor until the Piles at Abutments are complete in place and the grading throughout the structure has been completed.




The Bridge Contractor shall at all times maintain a minimum vertical clearance of 12' and a minimum horizontal clearance of 25' over each lane of interstate highway if the surfacing is completed and the highway opened to traffic prior to the completion of the grade separation structures. The Bridge Contractor will be held responsible for maintenance of traffic through the structure locations.

- REFERENCE LIST OF DIMS:**
- FOR DETAILS OF SUPERSTR. SEE SHEET # 51
 - DETAILS OF ABUTMENTS & CONC. PILING SEE SHEET # 50
 - DETAILS OF BEARING PLATES HAND RAIL & 4" CONC. SLOPE PAVEMENT SEE SH # 52
 - DETAILS OF PIERS SEE SHEET # 43
 - DETAILS OF SOFFIT ELEV. SEE SHEET # 45


RECORD		OKLAHOMA STATE HIGHWAY COMMISSION OKLAHOMA CITY, OKLA.	
ITEM	BY DATE	STR. No. 1	
DESIGN		GENERAL ELEV., PLAN & SUMMARY OF QUANTITIES	
DETAIL		30'-55'-55'-30' CONC. SLAB SPAN 20' RDY & 2-18" S.C.'s	
TRACED	D.F.S. 3/57	& STA. ON & SURVEY 820 + 98.40	
CHECKED	R.A.R. 3/57	F.A. PROJ. I-456(3)	
APPR'D			
SQUAD			

CHECKED BY: []
 DATE: []
 NO. []

FOR INFORMATION ONLY



Note: For detail of Handrail see Standard Detail Sheet For Handrail Post spacing See Gen. Elev. and Plan Sheet.



QUANTITIES		
ITEM	UNIT	QTY
Class AA	CY.	31.2
Reinforcing steel	Lbs	55,025

BAR LIST									
Mark	No.	Size	Form	Length	Mark	No.	Size	Form	Length
L1	42	7/8"	Str.	48'-4"	L1	8	1"	Str.	48'-4"
L2	40	1 1/8"	Str.	32'-3"	L1	115	1 1/2"	Str.	22'-8"
L3	50	3/4"	Str.	14'-6"	L2	40	1 1/2"	Str.	22'-8"
L4	25	1"	Str.	53'-6"	L3	30	1 1/2"	Str.	22'-8"
L5	20	1 1/8"	Str.	38'-0"	L4	74	5/8"	Str.	22'-8"
L6	20	1 1/8"	Str.	25'-6"	L5	20	1 1/2"	Str.	22'-8"
L7	6	1 1/4"	Str.	38'-0"	F	230	1 1/2"	Ant.	5'-2"
L8	4	1 1/4"	Str.	24'-3"	S	195	1 1/2"	Ant.	3'-8"
L9	44	1"	Str.	17'-7"					
L10	46	7/8"	Str.	31'-5"					
L11	48	1"	Str.	38'-8"					
L12	44	1 1/4"	Str.	32'-8"					
L13	12	7/8"	Str.	16'-9"					
L14	12	7/8"	Str.	43'-0"					
L15	13	7/8"	Str.	57'-0"					

NOTES

Detailed plans of falsework & forms shall be submitted to the Highway Commission & be approved by the Chief Engineer before any concrete is poured. Falsework & forms must be in place for the entire deck of one unit before any concrete in that unit is poured.

All forms shall be lined with an approved form lining (plywood, Masonite, or similar material). The form lining material shall be full sized commercial panels & joints shall line up, in so far as practical. No scrap or odd sized pieces will be used.

Provision shall be made for adjustment of forms to correct any deformation which may occur during concrete operations. Adequate provisions shall be made for making adjustments to forms during pouring operations.

The concrete mixer shall be sufficient capacity to pour all concrete as indicated by the construction joints in a continuous pour. A standby mixer shall be provided at the bridge site for emergency use, unless transit mixed concrete is used.

No construction joints other than those shown on plans, will be allowed.


All exposed edges on concrete shall have a 3/4" chamfer unless otherwise shown or noted. Bricking of the underside of the deck will not be required if a smooth & uniform finish, acceptable to the engineer, is otherwise obtained.

A standby vibrator shall be provided at the site to take the place of any working vibrator breaking down.

All reinforcing steel bars shall conform to A.S.T.M. Spec. A-305-48.

The contractor may at his option & with no expense to the State, cut all transverse bars to allow 1'-6" lap outside construction joint of the panel being poured.

Reinf. in bottom of slab shall be supported on approved metal slab spacers. Steel in top of slab shall be supported on approved metal high chairs at approx. 4' centers.



Note: A 20oz. Copper Water Stop shall be installed full length of Constr. Jt. All cost of Water Stop, shall be included in the unit price bid per Cu. Yds. for Class "AA" Conc.

BRIDGE "H"
HOME ROAD OVER I-35
Design Load H-15-59.

REVISIONS				RECORD			
NO.	DESCRIPTION	BY	DATE	ITEM	BY	DATE	
1	Rev. 1-30-57		1/30/57	DESIGN			
				DETAIL			
				TRACED			
				CHECKED			
				APPROVED			
				SQUAD:			


OKLAHOMA STATE HIGHWAY COMMISSION
OKLAHOMA CITY, OKLAHOMA

**STANDARD
DETAIL OF CONC. SLAB
FOR 30'-55'-55'-30' CONC. SLAB SPAN
20' RDWY & 2-18" S.C.'s
F.A. PROJ. 1-456**

FOR INFORMATION ONLY

BAR LIST-ONE ABUT.

Mark	No.	Size	Form	Length
H ₁	15	3/4"	Str.	27'-6"
H ₂	74	3/4"	Str.	3'-8"
H ₃	48	3/4"	Str.	3'-0"
H ₄	14	3/4"	Str.	8'-2"
V ₁	40	1/2"	Str.	3'-4"
V ₂	77	1/2"	Str.	4'-2"
WH ₁	2	1/2"	Bnt.	4'-4"
WH ₂	2	1/2"	Bnt.	8'-0"
WH ₃	3	1/2"	Bnt.	31'-9"
WH ₄	10	1/2"	Bnt.	9'-2"
BH ₁	5	1/2"	Bnt.	32'-0"
WV ₁	8	1/2"	Str.	3'-0"
WV ₂	8	1/2"	Str.	2'-6" Ave.
WV ₃	45	1/2"	Str.	2'-2"
WV ₄	2	1/2"	Str.	2'-6"
H	28	3/4"	Bnt.	8'-3"
P	14	1/2"	Bnt.	3'-8"



MAXIMUM LIMITS OF EXCAV. IN COMPACTED FILL

Abutment shall be back filled & tamped with a mechanical tamper (type & weight to be approved by the Engineer) by the Bridge Contractor after abutment is completed. All cost of backfill shall be included in the unit price bid per Cu. Yd. for Substr. Excav. Common.

Contractor may excavate to the neat lines of the abutment & if in satisfactory condition to the Resident Engineer, he may pour the concrete against the compacted fill. If necessary, Contractor shall use forms on the back vertical face of the Abut. & remove the same after concrete is set.

EXCAVATION DETAILS FOR ABUTMENTS

QUANTITIES


ITEM	UNIT	Abut. #1	Abut. #2
Class "A" Concrete	Cu. Yds.	18.5	18.5
Reinf. Steel	Lbs.	2480	2480
Reinf. Conc. Piling	Lin. Ft.	*	*
Substr. Excav. Com.	Cu. Yds.	60	60

* Included in Summary of Quantities - General Elevation & Plan - Sheet


**BRIDGE "H"
HOME ROAD OVER I-35**

NOTES


- 1- Unless Otherwise Noted, All Exposed Edges Shall Have A 3/4" Chamfer.
- 2- All construction and materials shall be in accordance with the Oklahoma Standard Specifications of 1954 and Special Provisions.




HALF REINF. PLAN HALF PLAN




ELEVATION




SECTION ON line



PILE SPACING DIAGRAM



BAR BENDING DETAILS



DETAIL OF REINF. CONC. PILE

Piling Note: Vertical Bars in piling - For lengths less than 35' use 4-1" φ bars. For lengths 35' to 39' use 6-1/8" φ bars. For lengths 40' or over use 8-1" φ bars. In piles requiring 8 vertical bars, the 4 side bars shall be 5'-0" shorter than the 4 corner bars.
Materials, driving equipment, construction methods, method of measurement, and basis of payment shall conform to the plans and Section 314 of the Specifications.

REVISIONS				RECORD		
NO.	DESCRIPTION	BY	DATE	ITEM	BY	DATE
1	Rev. H4 Bars & Reinf. Quant	DPS	5/9/57	DESIGN		
				DETAIL		
				TRACED	DPS	3/57
				CHECKED	RAR	3/57
				APPROVED		
				SQUAD:		

OKLAHOMA STATE HIGHWAY COMMISSION
OKLAHOMA CITY, OKLAHOMA

**STANDARD
DETAILS OF ABUTMENTS
FOR 30-55-55-30 CONC. SLAB SPAN
20' RDWY & 2-18" S.C.'s
F.A. PROJ. I-456**




FOR INFORMATION ONLY

BAR LIST - PIER No.1




Mark	No.	Size	Form	Length
H1	6	1"φ	Str.	22'-4"
H2	2	1/2"φ	Str.	22'-4"
H3	2	1/2"φ	Str.	14'-10"
H4	2	1 1/8"φ	Bnt.	20'-0"
H5	2	1 1/8"φ	Bnt.	17'-2"
H6	2	1 1/8"φ	Bnt.	14'-0"
H7	6	3/4"φ	Bnt.	9'-6"
H8	39	1/2"φ	Str.	9'-8"
S1	18	5/8"φ	Bnt.	7'-4" (Ave.)
S2	20	3/8"φ	Bnt.	11'-6" (Ave.)
S3	4	5/8"φ	Bnt.	13'-0"
S4	6	5/8"φ	Bnt.	3'-8"
D	20	3/4"φ	Str.	4'-0"
V	20	3/4"φ	Str.	22'-4"
F1	21	3/4"φ	Str.	15'-6"
F2	32	3/4"φ	Str.	10'-0"

BAR LIST - PIER No.2


Mark	No.	Size	Form	Length
H1	6	1"φ	Str.	22'-4"
H2	2	1/2"φ	Str.	22'-4"
H3	2	1/2"φ	Str.	14'-10"
H4	2	1 1/8"φ	Bnt.	20'-0"
H5	2	1 1/8"φ	Bnt.	17'-2"
H6	2	1 1/8"φ	Bnt.	14'-0"
H7	6	3/4"φ	Bnt.	9'-6"
H8	39	1/2"φ	Str.	9'-8"
S1	18	5/8"φ	Bnt.	7'-4" (Ave.)
S2	20	3/8"φ	Bnt.	11'-6" (Ave.)
S3	4	5/8"φ	Bnt.	13'-0"
S4	6	5/8"φ	Bnt.	3'-8"
D	20	3/4"φ	Str.	4'-0"
V	20	3/4"φ	Str.	22'-4"
F3	29	5/8"φ	Str.	15'-6"
F4	32	1"φ	Str.	12'-6"




REINFORCING DETAILS



S3 - 5/8"φ BARS




H8 - 1/2"φ BARS




H7 - 3/4"φ BARS


S1, S2 - 5/8"φ BARS




ELEVATION



SECTION - B



PIER BASE REINFORCING PIER No.1 & No.3



PIER BASE REINFORCING PIER No.2

QUANTITIES

ITEM	UNIT	PIER No.1	PIER No.2	PIER No.3
Reinforcing Steel	Lbs.	3,450	4,125	3,450
Class "A" Concrete	Cu. Yds.	16.7	16.7	16.7
Class "A" Conc. in Pier Bases	Cu. Yds.	18.7	23.1	18.7
Substr. Excav. - Common	Cu. Yds.	125	105	125

**BRIDGE "H"
HOME ROAD OVER I-35**

NOTES:
All reinforcing steel bars shall conform to A.S.T.M. specifications A-305-49.
All exposed edges shall have a 1/2" chamfer unless otherwise noted.
All concrete shall be poured dry.

NOTE: METAL STRIP
A 16 gage galvanized iron strip 12" wide shall be placed in the construction joint in each Pier Shaft as shown. Each joint in the metal strip shall be lapped 2", riveted and soldered to make it water tight. The materials shall comply with the requirements of the Oklahoma Standard Specifications of 1954 and A.A.S.H.O. specification. Concrete shall be carefully placed so as not to crush or deform this strip. All cost of the material and the placing of metal strip shall be included in the unit price bid per cubic yard for class "A" concrete in pier bases. Any variation in the elevation of pier bases shall be taken care of in the shaft and any additional concrete shall be paid for as class "A" concrete in pier bases. All cost of such variation shall be included in the unit price bid per cubic yard for class "A" concrete in pier bases.

REVISIONS				RECORD	
NO.	DESCRIPTION	BY	DATE	ITEM	BY DATE
1	Rev. H8 Bars & Reinf. Quan.	DFB	3/9/57	DESIGN	
				DETAIL	
				TRACED	I.S. 3/57
				CHECKED	R.A.R. 3/57
				APPROVED	
				SQUAD:	

OKLAHOMA STATE HIGHWAY COMMISSION
OKLAHOMA CITY, OKLAHOMA

**STRUCTURE No.1
DETAILS OF PIERS**

☐ STA. ☐ SURVEY 820+98.40
FA PROJ. I-456(3)

STORM WATER MANAGEMENT PLAN

DESCRIPTION	REVISIONS	DATE

SITE DESCRIPTION

EROSION AND SEDIMENT CONTROLS

PROJECT LIMITS: APPROX. 1/8 MILE EAST & WEST OF I-35 ALONG NORTH AVE
NORTH AVE IS LOCATED 1 MILE SOUTH OF THE SH-60 & I-35 JUNCTION ALONG
THE I-35 CORRIDOR.

PROJECT DESCRIPTION: RAISE BRIDGE PROFILE AND ADJUST ROADWAY PROFILE TO
MATCH. PROJECT INCLUDES REPLACING GUARDRAIL AND RESHAPING SLOPES TO
MATCH RAISE PROFILE GRADE OF THE ROAD.

SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES: _____
PRIOR TO INITIATING SOIL DISTURBING ACTIVITIES, THE CONTRACTOR WILL INSTALL
ALL PERIMETER TEMPORARY SEDIMENT CONTROLS SPECIFIED. STRIP, STOCKPILE AND
STABILIZE TOPSOIL. CLEAR AND GRUB ONLY IN NECESSARY AREAS, PRESERVING AS
MUCH NATIVE VEGETATION AS POSSIBLE. INSTALL, MAINTAIN AND/OR MOVE
TEMPORARY SEDIMENT ITEMS WITH CONSTRUCTION OPERATIONS AS PRACTICAL. IF
DIRECTED BY THE ENGINEER, PLANT TEMPORARY SEEDING. REPLACE SALVAGED
TOPSOIL AND DEVICES WHEN AN ACCEPTABLE VEGETATIVE COVER (AT LEAST 70%)
HAS BEEN ATTAINED. AS SITE CONDITIONS WARRANT, THE CONTRACTOR MAY
CHOOSE TO MODIFY THE TYPE OR ARRANGEMENT OF SPECIFIED PRACTICES TO
IMPROVE THEIR EFFECTIVENESS AS APPROVED BY THE ENGINEER. THE CONTRACTOR
WILL MAINTAIN A LOG OF MAJOR SOIL DISTURBANCE ACTIVITIES, AND ALSO THE
DATES OF INSTALLATION OF EROSION CONTROL MEASURES.

SOIL TYPE: REINACH LOAM/EDA LOAMY FINE SAND

TOTAL AREA OF THE CONSTRUCTION SITE: 2.86 ACRES (124,582 SF)

ESTIMATED AREA TO BE DISTURBED: 2.86 ACRES (124,582 SF)

OFFSITE AREA TO BE DISTURBED: _____
 (FOR CONTRACTOR USE)

TOTAL IMPERVIOUS AREA PRE-CONSTRUCTION: 0.16 ACRES (7,100 SF)

TOTAL IMPERVIOUS AREA POST-CONSTRUCTION: 0.19 ACRES (8,440 SF)

POST-CONSTRUCTION RUNOFF COEFFICIENT OF THE SITE: 0.45

LATITUDE & LONGITUDE OF CENTER OF PROJECT: N36°40'51" W97°20'45"

PROJECT WILL DISCHARGE TO:

NAME OF RECEIVING WATERS: ARKANSAS RIVER, SALT FORK

SENSITIVE WATERS OR WATERSHEDS: YES NO

303(D) IMPAIRED WATERS: YES NO

IF YES, LIST IMPAIRMENT: Enterococc, Turbidity

LOCATED IN A TMDL: YES NO

LAKE THUNDERBIRD TMDL: YES NO

MS4 ENTITY YES NO

NOTE: IF YES, LOCATION: OK621000010010_30

THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION CONTROL SUMMARIES, PAY ITEMS, & NOTES.

SOIL STABILIZATION PRACTICES:

- _____ TEMPORARY SEEDING
- PERMANENT SODDING, SPRIGGING OR SEEDING
- VEGETATIVE MULCHING
- _____ SOIL RETENTION BLANKET
- PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.

STRUCTURAL PRACTICES:

- _____ STABILIZED CONSTRUCTION EXIT
- TEMPORARY SILT FENCE
- _____ TEMPORARY SILT DIKES
- _____ TEMPORARY FIBER LOG
- _____ DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- _____ DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- _____ ROCK FILTER DAMS
- _____ TEMPORARY SLOPE DRAIN
- _____ PAVED DITCH W/ DITCH LINER PROTECTION
- _____ TEMPORARY DIVERSION CHANNELS
- _____ TEMPORARY SEDIMENT BASINS
- _____ TEMPORARY SEDIMENT TRAPS
- _____ TEMPORARY SEDIMENT FILTERS
- TEMPORARY SEDIMENT REMOVAL
- _____ RIP RAP
- _____ INLET SEDIMENT FILTER
- _____ TEMPORARY BRUSH SEDIMENT BARRIERS
- _____ SANDBAG BERMS
- _____ TEMPORARY STREAM CROSSINGS

OFFSITE VEHICLE TRACKING:

- _____ HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- _____ EXCESS DIRT ON ROAD REMOVED DAILY

NOTES:

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

GENERAL NOTES:

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2009 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:

- 103.05 BONDING REQUIREMENTS
- 104.10 FINAL CLEANING UP
- 104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13 ENVIRONMENTAL PROTECTION
- 106.08 STORAGE AND HANDLING OF MATERIAL
- 107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20 STORM WATER MANAGEMENT
- 220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221 TEMPORARY SEDIMENT CONTROL

IN ADDITION:

"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE STATE OF OKLAHOMA." ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2017.

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION				
DRAWN	ALM	09/18					
CHECKED	BDC	09/18					
APPROVED	JRW	09/18					
SQUAD							
COUNTY	KAY	HIGHWAY	NORTH AVE	STATE JOB NO.	24432(15)	SHEET NO.	R001

STORMWATER MANAGEMENT PLAN

Wednesday, October 24, 2018 1:04 PM V:\16-1070E_BR Raising Over I-35, Key, 1840, HNTB\CTV3\PLANS\1070-SWMP SHEETS.dwg

STORM WATER MANAGEMENT PLAN

DESCRIPTION	REVISIONS	DATE

SITE DESCRIPTION

EROSION AND SEDIMENT CONTROLS

PROJECT LIMITS: APPROX. 1/8 MILE EAST & WEST OF I-35 ALONG HIGHLAND AVE. HIGHLAND AVE IS LOCATED 1 MILE NORTH OF THE SH-60 & I-35 JUNCTION ALONG THE I-35 CORRIDOR.

PROJECT DESCRIPTION: RAISE BRIDGE PROFILE AND ADJUST ROADWAY PROFILE TO MATCH. PROJECT INCLUDES REPLACING GUARDRAIL AND RESHAPING SLOPES TO MATCH RAISE PROFILE GRADE OF THE ROAD.

SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES: _____
 PRIOR TO INITIATING SOIL DISTURBING ACTIVITIES, THE CONTRACTOR WILL INSTALL ALL PERIMETER TEMPORARY SEDIMENT CONTROLS SPECIFIED. STRIP, STOCKPILE AND STABILIZE TOPSOIL. CLEAR AND GRUB ONLY IN NECESSARY AREAS, PRESERVING AS MUCH NATIVE VEGETATION AS POSSIBLE. INSTALL, MAINTAIN AND/OR MOVE TEMPORARY SEDIMENT ITEMS WITH CONSTRUCTION OPERATIONS AS PRACTICAL. IF DIRECTED BY THE ENGINEER, PLANT TEMPORARY SEEDING. REPLACE SALVAGED TOPSOIL AND DEVICES WHEN AN ACCEPTABLE VEGETATIVE COVER (AT LEAST 70%) HAS BEEN ATTAINED. AS SITE CONDITIONS WARRANT, THE CONTRACTOR MAY CHOOSE TO MODIFY THE TYPE OR ARRANGEMENT OF SPECIFIED PRACTICES TO IMPROVE THEIR EFFECTIVENESS AS APPROVED BY THE ENGINEER. THE CONTRACTOR WILL MAINTAIN A LOG OF MAJOR SOIL DISTURBANCE ACTIVITIES, AND ALSO THE DATES OF INSTALLATION OF EROSION CONTROL MEASURES.

SOIL TYPE: BETHANY SILT LOAM/KIRKLAND SILT LOAM

TOTAL AREA OF THE CONSTRUCTION SITE: 2.18 ACRES (94,961 SF)

ESTIMATED AREA TO BE DISTURBED: 2.18 ACRES (94,961 SF)

OFFSITE AREA TO BE DISTURBED: _____
 (FOR CONTRACTOR USE)

TOTAL IMPERVIOUS AREA PRE-CONSTRUCTION: 0.16 ACRES (7,100 SF)

TOTAL IMPERVIOUS AREA POST-CONSTRUCTION: 0.17 ACRES (7,500 SF)

POST-CONSTRUCTION RUNOFF COEFFICIENT OF THE SITE: 0.45

LATITUDE & LONGITUDE OF CENTER OF PROJECT: N36°42'35" W97°20'45"

PROJECT WILL DISCHARGE TO:

NAME OF RECEIVING WATERS: TONKAWA CREEK

SENSITIVE WATERS OR WATERSHEDS: YES NO

303(D) IMPAIRED WATERS: YES NO

IF YES, LIST IMPAIRMENT: Enterococc, Turbidity

LOCATED IN A TMDL: YES NO

LAKE THUNDERBIRD TMDL: YES NO

MS4 ENTITY YES NO

NOTE: IF YES, LOCATION: _____
 THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION CONTROL SUMMARIES, PAY ITEMS, & NOTES.

SOIL STABILIZATION PRACTICES:

- _____ TEMPORARY SEEDING
- PERMANENT SODDING, SPRIGGING OR SEEDING
- VEGETATIVE MULCHING
- _____ SOIL RETENTION BLANKET
- PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.

STRUCTURAL PRACTICES:

- _____ STABILIZED CONSTRUCTION EXIT
- TEMPORARY SILT FENCE
- _____ TEMPORARY SILT DIKES
- _____ TEMPORARY FIBER LOG
- _____ DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- _____ DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- _____ ROCK FILTER DAMS
- _____ TEMPORARY SLOPE DRAIN
- _____ PAVED DITCH W/ DITCH LINER PROTECTION
- _____ TEMPORARY DIVERSION CHANNELS
- _____ TEMPORARY SEDIMENT BASINS
- _____ TEMPORARY SEDIMENT TRAPS
- _____ TEMPORARY SEDIMENT FILTERS
- TEMPORARY SEDIMENT REMOVAL
- _____ RIP RAP
- _____ INLET SEDIMENT FILTER
- _____ TEMPORARY BRUSH SEDIMENT BARRIERS
- _____ SANDBAG BERMS
- _____ TEMPORARY STREAM CROSSINGS

OFFSITE VEHICLE TRACKING:

- _____ HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- _____ EXCESS DIRT ON ROAD REMOVED DAILY

NOTES:

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

GENERAL NOTES:

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2009 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:

- 103.05 BONDING REQUIREMENTS
- 104.10 FINAL CLEANING UP
- 104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13 ENVIRONMENTAL PROTECTION
- 106.08 STORAGE AND HANDLING OF MATERIAL
- 107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20 STORM WATER MANAGEMENT
- 220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221 TEMPORARY SEDIMENT CONTROL

IN ADDITION:

"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE STATE OF OKLAHOMA." ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2017.

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			
COUNTY	KAY	HIGHWAY HIGHLAND AVE STATE JOB NO. 24432(15)	SHEET NO. R002

STORMWATER MANAGEMENT PLAN

Wednesday, October 24, 2018 1:20:22 PM V:\16-1070E_BR Raising Over I-35, Kay, 1840, HNTB\CTV3\PLANS\1070-SWMP SHEETS.dwg

STORM WATER MANAGEMENT PLAN

DESCRIPTION	REVISIONS	DATE

SITE DESCRIPTION

EROSION AND SEDIMENT CONTROLS

PROJECT LIMITS: APPROX. 1/8 MILE EAST & WEST OF I-35 ALONG HARTFORD AVE. HARTFORD AVE IS LOCATED 2 MILES NORTH OF THE SH-60 & I-35 JUNCTION ALONG THE I-35 CORRIDOR.

PROJECT DESCRIPTION: RAISE BRIDGE PROFILE AND ADJUST ROADWAY PROFILE TO MATCH. PROJECT INCLUDES REPLACING GUARDRAIL AND RESHAPING SLOPES TO MATCH RAISE PROFILE GRADE OF THE ROAD.

SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES: _____
 PRIOR TO INITIATING SOIL DISTURBING ACTIVITIES, THE CONTRACTOR WILL INSTALL ALL PERIMETER TEMPORARY SEDIMENT CONTROLS SPECIFIED. STRIP, STOCKPILE AND STABILIZE TOPSOIL. CLEAR AND GRUB ONLY IN NECESSARY AREAS, PRESERVING AS MUCH NATIVE VEGETATION AS POSSIBLE. INSTALL, MAINTAIN AND/OR MOVE TEMPORARY SEDIMENT ITEMS WITH CONSTRUCTION OPERATIONS AS PRACTICAL. IF DIRECTED BY THE ENGINEER, PLANT TEMPORARY SEEDING. REPLACE SALVAGED TOPSOIL AND DEVICES WHEN AN ACCEPTABLE VEGETATIVE COVER (AT LEAST 70%) HAS BEEN ATTAINED. AS SITE CONDITIONS WARRANT, THE CONTRACTOR MAY CHOOSE TO MODIFY THE TYPE OR ARRANGEMENT OF SPECIFIED PRACTICES TO IMPROVE THEIR EFFECTIVENESS AS APPROVED BY THE ENGINEER. THE CONTRACTOR WILL MAINTAIN A LOG OF MAJOR SOIL DISTURBANCE ACTIVITIES, AND ALSO THE DATES OF INSTALLATION OF EROSION CONTROL MEASURES.

SOIL TYPE: KIRKLAND SILT LOAM/KIRKLAND RENFROW COMPLEX

TOTAL AREA OF THE CONSTRUCTION SITE: 1.95 ACRES (85,119 SF)

ESTIMATED AREA TO BE DISTURBED: 1.95 ACRES (85,119 SF)

OFFSITE AREA TO BE DISTURBED: _____
 (FOR CONTRACTOR USE)

TOTAL IMPERVIOUS AREA PRE-CONSTRUCTION: 0.16 ACRES (7,100 SF)

TOTAL IMPERVIOUS AREA POST-CONSTRUCTION: 0.17 ACRES (7,500 SF)

POST-CONSTRUCTION RUNOFF COEFFICIENT OF THE SITE: 0.45

LATITUDE & LONGITUDE OF CENTER OF PROJECT: N36°43'28" W97°20'45"

PROJECT WILL DISCHARGE TO:

NAME OF RECEIVING WATERS: STINK CREEK

SENSITIVE WATERS OR WATERSHEDS: YES NO

303(D) IMPAIRED WATERS: YES NO

IF YES, LIST IMPAIRMENT: _____

LOCATED IN A TMDL: YES NO

LAKE THUNDERBIRD TMDL: YES NO

MS4 ENTITY YES NO

NOTE: IF YES, LOCATION: _____

THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION CONTROL SUMMARIES, PAY ITEMS, & NOTES.

SOIL STABILIZATION PRACTICES:

- _____ TEMPORARY SEEDING
- PERMANENT SODDING, SPRIGGING OR SEEDING
- VEGETATIVE MULCHING
- _____ SOIL RETENTION BLANKET
- PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.

STRUCTURAL PRACTICES:

- _____ STABILIZED CONSTRUCTION EXIT
- TEMPORARY SILT FENCE
- _____ TEMPORARY SILT DIKES
- _____ TEMPORARY FIBER LOG
- _____ DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- _____ DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- _____ ROCK FILTER DAMS
- _____ TEMPORARY SLOPE DRAIN
- _____ PAVED DITCH W/ DITCH LINER PROTECTION
- _____ TEMPORARY DIVERSION CHANNELS
- _____ TEMPORARY SEDIMENT BASINS
- _____ TEMPORARY SEDIMENT TRAPS
- _____ TEMPORARY SEDIMENT FILTERS
- TEMPORARY SEDIMENT REMOVAL
- _____ RIP RAP
- _____ INLET SEDIMENT FILTER
- _____ TEMPORARY BRUSH SEDIMENT BARRIERS
- _____ SANDBAG BERMS
- _____ TEMPORARY STREAM CROSSINGS

OFFSITE VEHICLE TRACKING:

- _____ HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- _____ EXCESS DIRT ON ROAD REMOVED DAILY

NOTES:

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

GENERAL NOTES:

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2009 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:

- 103.05 BONDING REQUIREMENTS
- 104.10 FINAL CLEANING UP
- 104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13 ENVIRONMENTAL PROTECTION
- 106.08 STORAGE AND HANDLING OF MATERIAL
- 107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20 STORM WATER MANAGEMENT
- 220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221 TEMPORARY SEDIMENT CONTROL

IN ADDITION:

"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE STATE OF OKLAHOMA." ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2017.

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION <h2 style="margin: 0;">STORMWATER MANAGEMENT PLAN</h2>
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			
COUNTY	KAY	HIGHWAY HARTFORD AVE STATE JOB NO. 24432(15)	SHEET NO. R003

V:\16-1070E_BR Raising Over I-35, Kay, 1840, HNTB\CTV3\PLANS\1070-SWMP SHEETS.dwg Wednesday, October 24, 2018 1:20:27 PM

STORM WATER MANAGEMENT PLAN

DESCRIPTION	REVISIONS	DATE

SITE DESCRIPTION

EROSION AND SEDIMENT CONTROLS

PROJECT LIMITS: APPROX. 1/8 MILE EAST & WEST OF I-35 ALONG COLEMAN ROAD. COLEMAN ROAD IS LOCATED 3 MILES SOUTH OF THE SH-11 & I-35 JUNCTION ALONG THE I-35 CORRIDOR.

PROJECT DESCRIPTION: RAISE BRIDGE PROFILE AND ADJUST ROADWAY PROFILE TO MATCH. PROJECT INCLUDES REPLACING GUARDRAIL AND RESHAPING SLOPES TO MATCH RAISE PROFILE GRADE OF THE ROAD.

SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES: _____
 PRIOR TO INITIATING SOIL DISTURBING ACTIVITIES, THE CONTRACTOR WILL INSTALL ALL PERIMETER TEMPORARY SEDIMENT CONTROLS SPECIFIED. STRIP, STOCKPILE AND STABILIZE TOPSOIL. CLEAR AND GRUB ONLY IN NECESSARY AREAS, PRESERVING AS MUCH NATIVE VEGETATION AS POSSIBLE. INSTALL, MAINTAIN AND/OR MOVE TEMPORARY SEDIMENT ITEMS WITH CONSTRUCTION OPERATIONS AS PRACTICAL. IF DIRECTED BY THE ENGINEER, PLANT TEMPORARY SEEDING. REPLACE SALVAGED TOPSOIL AND DEVICES WHEN AN ACCEPTABLE VEGETATIVE COVER (AT LEAST 70%) HAS BEEN ATTAINED. AS SITE CONDITIONS WARRANT, THE CONTRACTOR MAY CHOOSE TO MODIFY THE TYPE OR ARRANGEMENT OF SPECIFIED PRACTICES TO IMPROVE THEIR EFFECTIVENESS AS APPROVED BY THE ENGINEER. THE CONTRACTOR WILL MAINTAIN A LOG OF MAJOR SOIL DISTURBANCE ACTIVITIES, AND ALSO THE DATES OF INSTALLATION OF EROSION CONTROL MEASURES.

SOIL TYPE: TABLET SILT LOAM

TOTAL AREA OF THE CONSTRUCTION SITE: 2.13 ACRES (92,783 SF)

ESTIMATED AREA TO BE DISTURBED: 2.13 ACRES (92,783 SF)

OFFSITE AREA TO BE DISTURBED: _____
 (FOR CONTRACTOR USE)

TOTAL IMPERVIOUS AREA PRE-CONSTRUCTION: 0.16 ACRES (7,100 SF)

TOTAL IMPERVIOUS AREA POST-CONSTRUCTION: 0.17 ACRES (7,500 SF)

POST-CONSTRUCTION RUNOFF COEFFICIENT OF THE SITE: 0.45

LATITUDE & LONGITUDE OF CENTER OF PROJECT: N36°46'4" W97°20'45"

PROJECT WILL DISCHARGE TO:

NAME OF RECEIVING WATERS: STINK CREEK

SENSITIVE WATERS OR WATERSHEDS: YES NO

303(D) IMPAIRED WATERS: YES NO

IF YES, LIST IMPAIRMENT: _____

LOCATED IN A TMDL: YES NO

LAKE THUNDERBIRD TMDL: YES NO

MS4 ENTITY YES NO

NOTE: IF YES, LOCATION: _____
 THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION CONTROL SUMMARIES, PAY ITEMS, & NOTES.

SOIL STABILIZATION PRACTICES:

- _____ TEMPORARY SEEDING
- PERMANENT SODDING, SPRIGGING OR SEEDING
- VEGETATIVE MULCHING
- _____ SOIL RETENTION BLANKET
- PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.

STRUCTURAL PRACTICES:

- _____ STABILIZED CONSTRUCTION EXIT
- TEMPORARY SILT FENCE
- _____ TEMPORARY SILT DIKES
- _____ TEMPORARY FIBER LOG
- _____ DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- _____ DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- _____ ROCK FILTER DAMS
- _____ TEMPORARY SLOPE DRAIN
- _____ PAVED DITCH W/ DITCH LINER PROTECTION
- _____ TEMPORARY DIVERSION CHANNELS
- _____ TEMPORARY SEDIMENT BASINS
- _____ TEMPORARY SEDIMENT TRAPS
- _____ TEMPORARY SEDIMENT FILTERS
- TEMPORARY SEDIMENT REMOVAL
- _____ RIP RAP
- _____ INLET SEDIMENT FILTER
- _____ TEMPORARY BRUSH SEDIMENT BARRIERS
- _____ SANDBAG BERMS
- _____ TEMPORARY STREAM CROSSINGS

OFFSITE VEHICLE TRACKING:

- _____ HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- _____ EXCESS DIRT ON ROAD REMOVED DAILY

NOTES:

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

GENERAL NOTES:

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2009 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:

- 103.05 BONDING REQUIREMENTS
- 104.10 FINAL CLEANING UP
- 104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13 ENVIRONMENTAL PROTECTION
- 106.08 STORAGE AND HANDLING OF MATERIAL
- 107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20 STORM WATER MANAGEMENT
- 220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221 TEMPORARY SEDIMENT CONTROL

IN ADDITION:

"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE STATE OF OKLAHOMA." ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2017.

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION <h2 style="margin: 0;">STORMWATER MANAGEMENT PLAN</h2>
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			
COUNTY	KAY	HIGHWAY	COLEMAN AVE STATE JOB NO. 24432(15) SHEET NO. R004

Wednesday, October 24, 2018 1:20:32 PM
 V:\16-1070E_BR Raising Over I-35, Kay, 1840, HNTB\CTV3\PLANS\1070-SWMP SHEETS.dwg

STORM WATER MANAGEMENT PLAN

DESCRIPTION	REVISIONS	DATE

SITE DESCRIPTION

EROSION AND SEDIMENT CONTROLS

PROJECT LIMITS: APPROX. 1/8 MILE EAST & WEST OF I-35 ALONG CHRYSLER AVE. CHRYSLER AVE IS LOCATED 2 MILES SOUTH OF THE SH-11 & I-35 JUNCTION ALONG THE I-35 CORRIDOR.

PROJECT DESCRIPTION: RAISE BRIDGE PROFILE AND ADJUST ROADWAY PROFILE TO MATCH. PROJECT INCLUDES REPLACING GUARDRAIL AND RESHAPING SLOPES TO MATCH RAISE PROFILE GRADE OF THE ROAD.

SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES: _____
 PRIOR TO INITIATING SOIL DISTURBING ACTIVITIES, THE CONTRACTOR WILL INSTALL ALL PERIMETER TEMPORARY SEDIMENT CONTROLS SPECIFIED. STRIP, STOCKPILE AND STABILIZE TOPSOIL. CLEAR AND GRUB ONLY IN NECESSARY AREAS, PRESERVING AS MUCH NATIVE VEGETATION AS POSSIBLE. INSTALL, MAINTAIN AND/OR MOVE TEMPORARY SEDIMENT ITEMS WITH CONSTRUCTION OPERATIONS AS PRACTICAL. IF DIRECTED BY THE ENGINEER, PLANT TEMPORARY SEEDING. REPLACE SALVAGED TOPSOIL AND DEVICES WHEN AN ACCEPTABLE VEGETATIVE COVER (AT LEAST 70%) HAS BEEN ATTAINED. AS SITE CONDITIONS WARRANT, THE CONTRACTOR MAY CHOOSE TO MODIFY THE TYPE OR ARRANGEMENT OF SPECIFIED PRACTICES TO IMPROVE THEIR EFFECTIVENESS AS APPROVED BY THE ENGINEER. THE CONTRACTOR WILL MAINTAIN A LOG OF MAJOR SOIL DISTURBANCE ACTIVITIES, AND ALSO THE DATES OF INSTALLATION OF EROSION CONTROL MEASURES.

SOIL TYPE: TABLER SILT LOAM/KIRKLAND SILT LOAM

TOTAL AREA OF THE CONSTRUCTION SITE: 2.12 ACRES (92,347 SF)

ESTIMATED AREA TO BE DISTURBED: 2.12 ACRES (92,347 SF)

OFFSITE AREA TO BE DISTURBED: _____
 (FOR CONTRACTOR USE)

TOTAL IMPERVIOUS AREA PRE-CONSTRUCTION: 0.16 ACRES (7,100 SF)

TOTAL IMPERVIOUS AREA POST-CONSTRUCTION: 0.17 ACRES (7,500 SF)

POST-CONSTRUCTION RUNOFF COEFFICIENT OF THE SITE: 0.45

LATITUDE & LONGITUDE OF CENTER OF PROJECT: N36°46'56" W97°20'46"

PROJECT WILL DISCHARGE TO:

NAME OF RECEIVING WATERS: STINK CREEK

SENSITIVE WATERS OR WATERSHEDS: YES NO

303(D) IMPAIRED WATERS: YES NO

IF YES, LIST IMPAIRMENT: _____

LOCATED IN A TMDL: YES NO

LAKE THUNDERBIRD TMDL: YES NO

MS4 ENTITY YES NO

NOTE: IF YES, LOCATION: _____

THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION CONTROL SUMMARIES, PAY ITEMS, & NOTES.

SOIL STABILIZATION PRACTICES:

- _____ TEMPORARY SEEDING
- PERMANENT SODDING, SPRIGGING OR SEEDING
- VEGETATIVE MULCHING
- _____ SOIL RETENTION BLANKET
- PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.

STRUCTURAL PRACTICES:

- _____ STABILIZED CONSTRUCTION EXIT
- TEMPORARY SILT FENCE
- TEMPORARY SILT DIKES
- _____ TEMPORARY FIBER LOG
- _____ DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- _____ DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- _____ ROCK FILTER DAMS
- _____ TEMPORARY SLOPE DRAIN
- _____ PAVED DITCH W/ DITCH LINER PROTECTION
- _____ TEMPORARY DIVERSION CHANNELS
- _____ TEMPORARY SEDIMENT BASINS
- _____ TEMPORARY SEDIMENT TRAPS
- _____ TEMPORARY SEDIMENT FILTERS
- TEMPORARY SEDIMENT REMOVAL
- _____ RIP RAP
- _____ INLET SEDIMENT FILTER
- _____ TEMPORARY BRUSH SEDIMENT BARRIERS
- _____ SANDBAG BERMS
- _____ TEMPORARY STREAM CROSSINGS

OFFSITE VEHICLE TRACKING:

- _____ HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- _____ EXCESS DIRT ON ROAD REMOVED DAILY

NOTES:

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

GENERAL NOTES:

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2009 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:

- 103.05 BONDING REQUIREMENTS
- 104.10 FINAL CLEANING UP
- 104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13 ENVIRONMENTAL PROTECTION
- 106.08 STORAGE AND HANDLING OF MATERIAL
- 107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20 STORM WATER MANAGEMENT
- 220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221 TEMPORARY SEDIMENT CONTROL

IN ADDITION:

"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE STATE OF OKLAHOMA." ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2017.

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION <h2 style="margin: 0;">STORMWATER MANAGEMENT PLAN</h2>
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			
COUNTY	KAY		HIGHWAY CHRYSLER AVE STATE JOB NO. 24432(15) SHEET NO. R005

Wednesday, October 24, 2018 1:20:37 PM V:\16-1070E_BR Raising Over I-35, Kay, 1840, HNTB\CV3\PLANS\1070-SWMP SHEETS.dwg

STORM WATER MANAGEMENT PLAN

DESCRIPTION	REVISIONS	DATE

SITE DESCRIPTION

EROSION AND SEDIMENT CONTROLS

PROJECT LIMITS: APPROX. 3/16 MILE WEST & 1/8 EAST OF I-35 ALONG FERGUSON AVE. FERGUSON AVE IS LOCATED 1 MILE SOUTH OF THE SH-11 & I-35 JUNCTION ALONG THE I-35 CORRIDOR.

PROJECT DESCRIPTION: RAISE BRIDGE PROFILE AND ADJUST ROADWAY PROFILE TO MATCH. PROJECT INCLUDES REPLACING GUARDRAIL AND RESHAPING SLOPES TO MATCH RAISE PROFILE GRADE OF THE ROAD.

SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES: _____
 PRIOR TO INITIATING SOIL DISTURBING ACTIVITIES, THE CONTRACTOR WILL INSTALL ALL PERIMETER TEMPORARY SEDIMENT CONTROLS SPECIFIED. STRIP, STOCKPILE AND STABILIZE TOPSOIL. CLEAR AND GRUB ONLY IN NECESSARY AREAS, PRESERVING AS MUCH NATIVE VEGETATION AS POSSIBLE. INSTALL, MAINTAIN AND/OR MOVE TEMPORARY SEDIMENT ITEMS WITH CONSTRUCTION OPERATIONS AS PRACTICAL. IF DIRECTED BY THE ENGINEER, PLANT TEMPORARY SEEDING. REPLACE SALVAGED TOPSOIL AND DEVICES WHEN AN ACCEPTABLE VEGETATIVE COVER (AT LEAST 70%) HAS BEEN ATTAINED. AS SITE CONDITIONS WARRANT, THE CONTRACTOR MAY CHOOSE TO MODIFY THE TYPE OR ARRANGEMENT OF SPECIFIED PRACTICES TO IMPROVE THEIR EFFECTIVENESS AS APPROVED BY THE ENGINEER. THE CONTRACTOR WILL MAINTAIN A LOG OF MAJOR SOIL DISTURBANCE ACTIVITIES, AND ALSO THE DATES OF INSTALLATION OF EROSION CONTROL MEASURES.

SOIL TYPE: KIRKLAND RENFROW COMPLEX/GRAINOLA ASHPORT

TOTAL AREA OF THE CONSTRUCTION SITE: 2.19 ACRES (95,396 SF)

ESTIMATED AREA TO BE DISTURBED: 2.19 ACRES (95,396 SF)

OFFSITE AREA TO BE DISTURBED: _____
 (FOR CONTRACTOR USE)

TOTAL IMPERVIOUS AREA PRE-CONSTRUCTION: 0.16 ACRES (7,100 SF)

TOTAL IMPERVIOUS AREA POST-CONSTRUCTION: 0.17 ACRES (7,500 SF)

POST-CONSTRUCTION RUNOFF COEFFICIENT OF THE SITE: 0.45

LATITUDE & LONGITUDE OF CENTER OF PROJECT: N36°47'48" W97°20'41"

PROJECT WILL DISCHARGE TO:

NAME OF RECEIVING WATERS: STINK CREEK

SENSITIVE WATERS OR WATERSHEDS: YES NO

303(D) IMPAIRED WATERS: YES NO

IF YES, LIST IMPAIRMENT: _____

LOCATED IN A TMDL: YES NO

LAKE THUNDERBIRD TMDL: YES NO

MS4 ENTITY YES NO

NOTE: IF YES, LOCATION: _____
 THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION CONTROL SUMMARIES, PAY ITEMS, & NOTES.

SOIL STABILIZATION PRACTICES:

- _____ TEMPORARY SEEDING
- PERMANENT SODDING, SPRIGGING OR SEEDING
- VEGETATIVE MULCHING
- _____ SOIL RETENTION BLANKET
- PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.

STRUCTURAL PRACTICES:

- _____ STABILIZED CONSTRUCTION EXIT
- TEMPORARY SILT FENCE
- TEMPORARY SILT DIKES
- _____ TEMPORARY FIBER LOG
- _____ DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- _____ DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- _____ ROCK FILTER DAMS
- _____ TEMPORARY SLOPE DRAIN
- _____ PAVED DITCH W/ DITCH LINER PROTECTION
- _____ TEMPORARY DIVERSION CHANNELS
- _____ TEMPORARY SEDIMENT BASINS
- _____ TEMPORARY SEDIMENT TRAPS
- _____ TEMPORARY SEDIMENT FILTERS
- TEMPORARY SEDIMENT REMOVAL
- _____ RIP RAP
- _____ INLET SEDIMENT FILTER
- _____ TEMPORARY BRUSH SEDIMENT BARRIERS
- _____ SANDBAG BERMS
- _____ TEMPORARY STREAM CROSSINGS

OFFSITE VEHICLE TRACKING:

- _____ HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- _____ EXCESS DIRT ON ROAD REMOVED DAILY

NOTES:

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

GENERAL NOTES:

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2009 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:

- 103.05 BONDING REQUIREMENTS
- 104.10 FINAL CLEANING UP
- 104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13 ENVIRONMENTAL PROTECTION
- 106.08 STORAGE AND HANDLING OF MATERIAL
- 107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20 STORM WATER MANAGEMENT
- 220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221 TEMPORARY SEDIMENT CONTROL

IN ADDITION:

"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE STATE OF OKLAHOMA." ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2017.

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			
COUNTY	KAY	HIGHWAY	FERGUSON AVE STATE JOB NO. 24432(15) SHEET NO. R006

STORMWATER MANAGEMENT PLAN

Wednesday, October 24, 2018 1:20:42 PM V:\16-1070E_BR Raising Over I-35, Kay, 1840, HNTB\CTV3\PLANS\1070-SWMP SHEETS.dwg

STORM WATER MANAGEMENT PLAN

DESCRIPTION	REVISIONS	DATE

SITE DESCRIPTION

EROSION AND SEDIMENT CONTROLS

PROJECT LIMITS: APPROX. 1/8 MILE EAST & WEST OF I-35 ALONG ADOBE ROAD.
ADOBE ROAD IS LOCATED 1 MILE NORTH OF THE SH-11 & I-35 JUNCTION ALONG
THE I-35 CORRIDOR.

PROJECT DESCRIPTION: RAISE BRIDGE PROFILE AND ADJUST ROADWAY PROFILE TO
MATCH. PROJECT INCLUDES REPLACING GUARDRAIL AND RESHAPING SLOPES TO
MATCH RAISE PROFILE GRADE OF THE ROAD.

SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES: _____
PRIOR TO INITIATING SOIL DISTURBING ACTIVITIES, THE CONTRACTOR WILL INSTALL
ALL PERIMETER TEMPORARY SEDIMENT CONTROLS SPECIFIED. STRIP, STOCKPILE AND
STABILIZE TOPSOIL. CLEAR AND GRUB ONLY IN NECESSARY AREAS, PRESERVING AS
MUCH NATIVE VEGETATION AS POSSIBLE. INSTALL, MAINTAIN AND/OR MOVE
TEMPORARY SEDIMENT ITEMS WITH CONSTRUCTION OPERATIONS AS PRACTICAL. IF
DIRECTED BY THE ENGINEER, PLANT TEMPORARY SEEDING. REPLACE SALVAGED
TOPSOIL AND DEVICES WHEN AN ACCEPTABLE VEGETATIVE COVER (AT LEAST 70%)
HAS BEEN ATTAINED. AS SITE CONDITIONS WARRANT, THE CONTRACTOR MAY
CHOOSE TO MODIFY THE TYPE OR ARRANGEMENT OF SPECIFIED PRACTICES TO
IMPROVE THEIR EFFECTIVENESS AS APPROVED BY THE ENGINEER. THE CONTRACTOR
WILL MAINTAIN A LOG OF MAJOR SOIL DISTURBANCE ACTIVITIES, AND ALSO THE
DATES OF INSTALLATION OF EROSION CONTROL MEASURES.

SOIL TYPE: KIRKLAND SILT LOAM

TOTAL AREA OF THE
 CONSTRUCTION SITE: 1.78 ACRES (77,441 SF)

ESTIMATED AREA TO BE DISTURBED: 1.78 ACRES (77,441 SF)

OFFSITE AREA TO BE DISTURBED:
 (FOR CONTRACTOR USE) _____

TOTAL IMPERVIOUS AREA
 PRE-CONSTRUCTION: 0.16 ACRES (7,100 SF)

TOTAL IMPERVIOUS AREA
 POST-CONSTRUCTION: 0.17 ACRES (7,500 SF)

POST-CONSTRUCTION RUNOFF
 COEFFICIENT OF THE SITE: 0.45

LATITUDE & LONGITUDE
 OF CENTER OF PROJECT: N36°49'33" W97°20'35"

PROJECT WILL DISCHARGE TO:

NAME OF RECEIVING WATERS: STINK CREEK

SENSITIVE WATERS OR WATERSHEDS: YES NO

303(D) IMPAIRED WATERS: YES NO

IF YES, LIST IMPAIRMENT: _____

LOCATED IN A TMDL: YES NO

LAKE THUNDERBIRD TMDL: YES NO

MS4 ENTITY YES NO

NOTE: IF YES, LOCATION: _____

THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP
 THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS
 FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION
 CONTROL SUMMARIES, PAY ITEMS, & NOTES.

SOIL STABILIZATION PRACTICES:

- _____ TEMPORARY SEEDING
- PERMANENT SODDING, SPRIGGING OR SEEDING
- VEGETATIVE MULCHING
- _____ SOIL RETENTION BLANKET
- PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON
 ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED
 FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS,
 OR AS DIRECTED BY THE ENGINEER.

STRUCTURAL PRACTICES:

- _____ STABILIZED CONSTRUCTION EXIT
- TEMPORARY SILT FENCE
- _____ TEMPORARY SILT DIKES
- _____ TEMPORARY FIBER LOG
- _____ DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- _____ DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- _____ ROCK FILTER DAMS
- _____ TEMPORARY SLOPE DRAIN
- _____ PAVED DITCH W/ DITCH LINER PROTECTION
- _____ TEMPORARY DIVERSION CHANNELS
- _____ TEMPORARY SEDIMENT BASINS
- _____ TEMPORARY SEDIMENT TRAPS
- _____ TEMPORARY SEDIMENT FILTERS
- TEMPORARY SEDIMENT REMOVAL
- _____ RIP RAP
- _____ INLET SEDIMENT FILTER
- _____ TEMPORARY BRUSH SEDIMENT BARRIERS
- _____ SANDBAG BERMS
- _____ TEMPORARY STREAM CROSSINGS

OFFSITE VEHICLE TRACKING:

- _____ HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- _____ EXCESS DIRT ON ROAD REMOVED DAILY

NOTES:

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE
 FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM
 THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED.
 INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY
 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS
 RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE
 AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND
 EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT
 NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE
 CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS
 FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING,
 SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE
 REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE
 CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND
 FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP
 MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS,
 CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

GENERAL NOTES:

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE
 OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS
 INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE
 ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT
 CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL
 QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING
 THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH
 THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL
 SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO
 IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF
 FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND
 THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE
 PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE
 INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST
 PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2009 ODOT STANDARD SPECIFICATIONS SHOULD
 BE NOTED:

- 103.05 BONDING REQUIREMENTS
- 104.10 FINAL CLEANING UP
- 104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13 ENVIRONMENTAL PROTECTION
- 106.08 STORAGE AND HANDLING OF MATERIAL
- 107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20 STORM WATER MANAGEMENT
- 220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221 TEMPORARY SEDIMENT CONTROL

IN ADDITION:

"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE
 STATE OF OKLAHOMA." ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2017.

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION				
DRAWN	ALM	09/18					
CHECKED	BDC	09/18					
APPROVED	JRW	09/18					
SQUAD							
COUNTY	KAY	HIGHWAY	ADOBE RD	STATE JOB NO.	24432(15)	SHEET NO.	R007

STORMWATER MANAGEMENT PLAN

Wednesday, October 24, 2018 1:20:47 PM
 V:\16-1070E_BR Raising Over I-35, Kay, 1840, HNTB\CTV3\PLANS\1070-SWMP SHEETS.dwg

STORM WATER MANAGEMENT PLAN

DESCRIPTION	REVISIONS	DATE

SITE DESCRIPTION

EROSION AND SEDIMENT CONTROLS

PROJECT LIMITS: APPROX. 1/16 MILE NORTH & SOUTH OF HOME ROAD ALONG I-35. HOME ROAD IS LOCATED 1 MILE NORTH OF THE SH-177 & I-35 JUNCTION ALONG THE I-35 CORRIDOR.

PROJECT DESCRIPTION: REMOVE EXISTING BRIDGE AND APPURTENANCES. ADJUST DITCH GRADING ALONG I-35. INCLUDES REMOVAL OF EXISTING REINFORCED CONCRETE BOX ON I-35.

SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES: _____
 PRIOR TO INITIATING SOIL DISTURBING ACTIVITIES, THE CONTRACTOR WILL INSTALL ALL PERIMETER TEMPORARY SEDIMENT CONTROLS SPECIFIED. STRIP, STOCKPILE AND STABILIZE TOPSOIL. CLEAR AND GRUB ONLY IN NECESSARY AREAS, PRESERVING AS MUCH NATIVE VEGETATION AS POSSIBLE. INSTALL, MAINTAIN AND/OR MOVE TEMPORARY SEDIMENT ITEMS WITH CONSTRUCTION OPERATIONS AS PRACTICAL. IF DIRECTED BY THE ENGINEER, PLANT TEMPORARY SEEDING. REPLACE SALVAGED TOPSOIL AND DEVICES WHEN AN ACCEPTABLE VEGETATIVE COVER (AT LEAST 70%) HAS BEEN ATTAINED. AS SITE CONDITIONS WARRANT, THE CONTRACTOR MAY CHOOSE TO MODIFY THE TYPE OR ARRANGEMENT OF SPECIFIED PRACTICES TO IMPROVE THEIR EFFECTIVENESS AS APPROVED BY THE ENGINEER. THE CONTRACTOR WILL MAINTAIN A LOG OF MAJOR SOIL DISTURBANCE ACTIVITIES, AND ALSO THE DATES OF INSTALLATION OF EROSION CONTROL MEASURES.

SOIL TYPE: KIRKLAND SILT LOAM

TOTAL AREA OF THE CONSTRUCTION SITE: 1.68 ACRES (73,181 SF)

ESTIMATED AREA TO BE DISTURBED: 1.68 ACRES (73,181 SF)

OFFSITE AREA TO BE DISTURBED: _____
 (FOR CONTRACTOR USE)

TOTAL IMPERVIOUS AREA PRE-CONSTRUCTION: 0.13 ACRES (5,620 SF)

TOTAL IMPERVIOUS AREA POST-CONSTRUCTION: 0.00 ACRES (0 SF)

POST-CONSTRUCTION RUNOFF COEFFICIENT OF THE SITE: 0.40

LATITUDE & LONGITUDE OF CENTER OF PROJECT: N36°57'21" W97°20'44"

PROJECT WILL DISCHARGE TO:

NAME OF RECEIVING WATERS: DRY CREEK

SENSITIVE WATERS OR WATERSHEDS: YES NO

303(D) IMPAIRED WATERS: YES NO

IF YES, LIST IMPAIRMENT: _____

LOCATED IN A TMDL: YES NO

LAKE THUNDERBIRD TMDL: YES NO

MS4 ENTITY YES NO

NOTE: IF YES, LOCATION: _____
 THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION CONTROL SUMMARIES, PAY ITEMS, & NOTES.

SOIL STABILIZATION PRACTICES:

- _____ TEMPORARY SEEDING
- PERMANENT SODDING, SPRIGGING OR SEEDING
- VEGETATIVE MULCHING
- _____ SOIL RETENTION BLANKET
- PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.

STRUCTURAL PRACTICES:

- _____ STABILIZED CONSTRUCTION EXIT
- _____ TEMPORARY SILT FENCE
- TEMPORARY SILT DIKES
- TEMPORARY FIBER LOG
- _____ DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- _____ DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- _____ ROCK FILTER DAMS
- _____ TEMPORARY SLOPE DRAIN
- _____ PAVED DITCH W/ DITCH LINER PROTECTION
- _____ TEMPORARY DIVERSION CHANNELS
- _____ TEMPORARY SEDIMENT BASINS
- _____ TEMPORARY SEDIMENT TRAPS
- _____ TEMPORARY SEDIMENT FILTERS
- TEMPORARY SEDIMENT REMOVAL
- _____ RIP RAP
- _____ INLET SEDIMENT FILTER
- _____ TEMPORARY BRUSH SEDIMENT BARRIERS
- _____ SANDBAG BERMS
- _____ TEMPORARY STREAM CROSSINGS

OFFSITE VEHICLE TRACKING:

- _____ HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- _____ EXCESS DIRT ON ROAD REMOVED DAILY

NOTES:

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

GENERAL NOTES:

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2009 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:

- 103.05 BONDING REQUIREMENTS
- 104.10 FINAL CLEANING UP
- 104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13 ENVIRONMENTAL PROTECTION
- 106.08 STORAGE AND HANDLING OF MATERIAL
- 107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20 STORM WATER MANAGEMENT
- 220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221 TEMPORARY SEDIMENT CONTROL

IN ADDITION:

"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE STATE OF OKLAHOMA." ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2017.

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION <h2 style="margin: 0;">STORMWATER MANAGEMENT PLAN</h2>				
DRAWN	ALM	09/18					
CHECKED	BDC	09/18					
APPROVED	JRW	09/18					
SQUAD							
COUNTY	KAY	HIGHWAY	HOME RD	STATE JOB NO.	24432(15)	SHEET NO.	R008

Wednesday, October 24, 2018 1:20:52 PM V:\16-1070E_BR Raising Over I-35, Kay, 1840, HNTB\CTV3\PLANS\1070-SWMP SHEETS.dwg

STORM WATER MANAGEMENT PLAN

DESCRIPTION	REVISIONS	DATE

SITE DESCRIPTION

PROJECT LIMITS: APPROX. 1/8 MILE EAST & WEST OF I-35 ALONG INDIAN ROAD. INDIAN IS LOCATED 2 MILES NORTH OF THE SH-177 & I-35 JUNCTION ALONG THE I-35 CORRIDOR. CONSTRUCT ASPHALT WIDENING FOR CROSSOVER APPROX 1/4 MILE S. OF INDIAN ROAD.

PROJECT DESCRIPTION: RAISE BRIDGE PROFILE AND ADJUST ROADWAY PROFILE TO MATCH. PROJECT INCLUDES REPLACING GUARDRAIL AND RESHAPING SLOPES TO MATCH RAISE PROFILE GRADE OF THE ROAD.

SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES: PRIOR TO INITIATING SOIL DISTURBING ACTIVITIES, THE CONTRACTOR WILL INSTALL ALL PERIMETER TEMPORARY SEDIMENT CONTROLS SPECIFIED. STRIP, STOCKPILE AND STABILIZE TOPSOIL. CLEAR AND GRUB ONLY IN NECESSARY AREAS, PRESERVING AS MUCH NATIVE VEGETATION AS POSSIBLE. INSTALL, MAINTAIN AND/OR MOVE TEMPORARY SEDIMENT ITEMS WITH CONSTRUCTION OPERATIONS AS PRACTICAL. IF DIRECTED BY THE ENGINEER, PLANT TEMPORARY SEEDING. REPLACE SALVAGED TOPSOIL AND DEVICES WHEN AN ACCEPTABLE VEGETATIVE COVER (AT LEAST 70%) HAS BEEN ATTAINED. AS SITE CONDITIONS WARRANT, THE CONTRACTOR MAY CHOOSE TO MODIFY THE TYPE OR ARRANGEMENT OF SPECIFIED PRACTICES TO IMPROVE THEIR EFFECTIVENESS AS APPROVED BY THE ENGINEER. THE CONTRACTOR WILL MAINTAIN A LOG OF MAJOR SOIL DISTURBANCE ACTIVITIES, AND ALSO THE DATES OF INSTALLATION OF EROSION CONTROL MEASURES.

SOIL TYPE: KIRKLAND SILT LOAM

TOTAL AREA OF THE CONSTRUCTION SITE: 2.09 ACRES (91,019 SF) INDIAN +0.08 ACRES(3,300 SF) CROSSOVER= 2.17 ACRES

ESTIMATED AREA TO BE DISTURBED: 2.17 ACRES (94,319 SF)

OFFSITE AREA TO BE DISTURBED: (FOR CONTRACTOR USE)

TOTAL IMPERVIOUS AREA PRE-CONSTRUCTION: 0.16 ACRES (7,100 SF)

TOTAL IMPERVIOUS AREA POST-CONSTRUCTION: 0.25 ACRES (10,800 SF)

POST-CONSTRUCTION RUNOFF COEFFICIENT OF THE SITE: 0.45

LATITUDE & LONGITUDE OF CENTER OF PROJECT: N36°58'13" W97°20'44"

PROJECT WILL DISCHARGE TO:

NAME OF RECEIVING WATERS: SHOO FLY CREEK/DRY CREEK

SENSITIVE WATERS OR WATERSHEDS: YES NO

303(D) IMPAIRED WATERS: YES NO

IF YES, LIST IMPAIRMENT:

LOCATED IN A TMDL: YES NO

LAKE THUNDERBIRD TMDL: YES NO

MS4 ENTITY: YES NO

NOTE: IF YES, LOCATION: THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION CONTROL SUMMARIES, PAY ITEMS, & NOTES.

EROSION AND SEDIMENT CONTROLS

SOIL STABILIZATION PRACTICES:

- TEMPORARY SEEDING
- PERMANENT SODDING, SPRIGGING OR SEEDING
- VEGETATIVE MULCHING
- SOIL RETENTION BLANKET
- PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.

STRUCTURAL PRACTICES:

- STABILIZED CONSTRUCTION EXIT
- TEMPORARY SILT FENCE
- TEMPORARY SILT DIKES
- TEMPORARY FIBER LOG
- DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- ROCK FILTER DAMS
- TEMPORARY SLOPE DRAIN
- PAVED DITCH W/ DITCH LINER PROTECTION
- TEMPORARY DIVERSION CHANNELS
- TEMPORARY SEDIMENT BASINS
- TEMPORARY SEDIMENT TRAPS
- TEMPORARY SEDIMENT FILTERS
- TEMPORARY SEDIMENT REMOVAL
- RIP RAP
- INLET SEDIMENT FILTER
- TEMPORARY BRUSH SEDIMENT BARRIERS
- SANDBAG BERMS
- TEMPORARY STREAM CROSSINGS

OFFSITE VEHICLE TRACKING:

- HAUL ROADS DAMPENED FOR DUST CONTROL
- LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN
- EXCESS DIRT ON ROAD REMOVED DAILY

NOTES:

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

GENERAL NOTES:

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2009 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:

- 103.05 BONDING REQUIREMENTS
- 104.10 FINAL CLEANING UP
- 104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13 ENVIRONMENTAL PROTECTION
- 106.08 STORAGE AND HANDLING OF MATERIAL
- 107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20 STORM WATER MANAGEMENT
- 220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221 TEMPORARY SEDIMENT CONTROL


IN ADDITION:

*ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE STATE OF OKLAHOMA. ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2017.


DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION				
DRAWN	ALM	09/18					
CHECKED	BDC	09/18					
APPROVED	JRW	09/18					
SQUAD							
COUNTY	KAY	HIGHWAY	INDIAN RD	STATE JOB NO.	24432(15)	SHEET NO.	R009

STORMWATER MANAGEMENT PLAN

Wednesday, October 24, 2018 1:22:14 PM
 W:\16-1070E_BR_Raising_Over I-35_Koy_1840_HNTB\CIV3D\PLANS\1070-Erosion_Control.dwg



SUMMARY OF DISTURBED AREA (NORTH AVE)			
DRAINAGE AREA NUMBER	STRUCTURE DRAIN LOCATION	AREA ACRES	EROSION CONTROL MEASURES
D.A.1	OFFSITE I-35 CROSS DRAIN	0.57	SILT FENCE
D.A.2	OFFSITE	0.54	SILT FENCE
D.A.3	OFFSITE I-35 DITCH	0.14	SILT FENCE
D.A.4	OFFSITE POND	0.84	SILT FENCE
D.A.5	OFFSITE	0.77	SILT FENCE
TOTALS =		2.86	



SUMMARY OF DISTURBED AREA (HIGHLAND AVE)			
DRAINAGE AREA NUMBER	STRUCTURE DRAIN LOCATION	AREA ACRES	EROSION CONTROL MEASURES
D.A.1	EXISTING 24" RCP SOUTH	0.53	SILT FENCE
D.A.2	OFFSITE I-35 DITCH	0.55	SILT FENCE
D.A.3	EXISTING 30" RCP SOUTH	0.45	SILT FENCE
D.A.4	OFFSITE I-35 DITCH	0.65	SILT FENCE
TOTALS =		2.18	

LEGEND

- TEMPORARY SILT DIKE INSTALLATION
- TEMPORARY SILT FENCE INSTALLATION
- DISTURBED AREA


GRAPHIC SCALE (HORIZ.)
 1 inch = 50' ft.
 50' 0 50' 100'

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION GUY ENGINEERING SERVICES, INC.
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			


EROSION CONTROL

COUNTY KAY HWY/ROAD NORTH & HIGHLAND STATE JOB NO. 24432(15) SHEET NO. R010

Wednesday, October 24, 2018 1:23:11 PM
 W:\16-1070E_BR_Raising_Over_I-35_Kay_1840_HNTB\CIV3D\PLANS\1070-Erosion_Control.dwg



SUMMARY OF DISTURBED AREA (HARTFORD AVE)			
DRAINAGE AREA NUMBER	STRUCTURE DRAIN LOCATION	AREA ACRES	EROSION CONTROL MEASURES
D.A.1	INLET 30" RCP I-35	0.54	SILT FENCE
D.A.2	OFFSITE I-35 DITCH	0.52	SILT FENCE
D.A.3	OFFSITE	0.35	SILT FENCE
D.A.4	EXISTING RCB	0.55	SILT FENCE
TOTALS =		1.95	




SUMMARY OF DISTURBED AREA (COLEMAN ROAD)			
DRAINAGE AREA NUMBER	STRUCTURE DRAIN LOCATION	AREA ACRES	EROSION CONTROL MEASURES
D.A.1	OFFSITE I-35 DITCH NORTH	0.57	SILT FENCE
D.A.2	OFFSITE I-35 DITCH NORTH	0.51	SILT FENCE
D.A.3	OFFSITE I-35 DITCH NORTH	0.13	SILT FENCE
D.A.4	OFFSITE I-35 DITCH NORTH	0.13	SILT FENCE
D.A.5	OFFSITE OVERLAND	0.40	SILT FENCE
D.A.6	OFFSITE OVERLAND	0.39	SILT FENCE
TOTALS =		2.13	

LEGEND

TEMPORARY SILT DIKE INSTALLATION
 TEMPORARY SILT FENCE INSTALLATION

GRAPHIC SCALE (HORIZ.)
 1 inch = 50' ft.

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION GUY ENGINEERING SERVICES, INC.
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			
EROSION CONTROL			
COUNTY <u>KAY</u> HWY/RD <u>HARTFORD & COLEMAN</u> STATE JOB NO. <u>24432(15)</u> SHEET NO. <u>R011</u>			




SUMMARY OF DISTURBED AREA (CHRYSLER AVE)

DRAINAGE AREA NUMBER	STRUCTURE DRAIN LOCATION	AREA ACRES	EROSION CONTROL MEASURES
D.A. 1	INLET RCB I-35	0.49	SILT FENCE/SILT DIKE
D.A. 2	OFFSITE I-35 DITCH	0.58	SILT FENCE/SILT DIKE
D.A. 3	OFFSITE CHRYSLER DITCH	0.53	SILT FENCE
D.A. 4	OFFSITE I-35 DITCH	0.10	SILT FENCE
D.A. 5	OFFSITE OVERLAND	0.31	SILT FENCE
D.A. 6	OFFSITE CHRYSLER DITCH	0.11	SILT FENCE/SILT DIKE
TOTALS =		2.12	


LEGEND

- TEMPORARY SILT DIKE INSTALLATION
- TEMPORARY SILT FENCE INSTALLATION




DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION GUY ENGINEERING SERVICES, INC.
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			
EROSION CONTROL			
COUNTY	KAY	HWY/RD	CHRYSLER AVE STATE JOB NO. 24432(15) SHEET NO. R012

Wednesday, October 24, 2018 1:24:45 PM
 W:\16-1070E_BR_Raising_Over I-35_Kay_1840_HNTB\CIV3D\PLANS\1070-Erosion_Control.dwg




SUMMARY OF DISTURBED AREA (FERGUSON AVE WEST SIDE)			
DRAINAGE AREA NUMBER	STRUCTURE DRAIN LOCATION	AREA ACRES	EROSION CONTROL MEASURES
D.A.1	INLET EXISTING RCB	0.46	SILT FENCE
D.A.2	OFFSITE DRAINAGE CHANNEL	0.37	SILT FENCE
D.A.3	INLET I-35	0.13	SILT FENCE
D.A.4	OFFSITE I-25 DITCH	0.21	SILT FENCE
TOTALS =		1.17	



SUMMARY OF DISTURBED AREA (FERGUSON AVE EAST SIDE)			
DRAINAGE AREA NUMBER	STRUCTURE DRAIN LOCATION	AREA ACRES	EROSION CONTROL MEASURES
D.A.1	INLET EXISTING RCB I-35	0.49	SILT FENCE
D.A.2	OFFSITE I-35 DITCH	0.18	SILT FENCE
D.A.3	OFFSITE DRAINAGE CHANNEL	0.35	SILT FENCE
TOTALS =		1.02	


LEGEND
 TEMPORARY SILTS DIKE INSTALLATION
 TEMPORARY SILTS FENCE INSTALLATION




DESIGN	BDC	09/18
DRAWN	ALM	09/18
CHECKED	BDC	09/18
APPROVED	JRW	09/18
SQUAD		

OKLAHOMA DEPARTMENT OF TRANSPORTATION
 GUY ENGINEERING SERVICES, INC.
EROSION CONTROL
 COUNTY KAY HWY/RD FERGUSON AVE STATE JOB NO. 24432(15) SHEET NO. R013

Wednesday, October 24, 2018 1:25:41 PM
 W:\16-1070E_BR_Raising_Over_I-35_Kay_1840_HNTB\CIV3D\PLANS\1070-Erosion_Control.dwg




SUMMARY OF DISTURBED AREA (ADOBE ROAD)			
DRAINAGE AREA NUMBER	STRUCTURE DRAIN LOCATION	AREA ACRES	EROSION CONTROL MEASURES
D.A.1	OFFSITE I-35 DITCH	0.38	SILT FENCE
D.A.2	I-35 CROSS DRAIN	0.41	SILT FENCE
D.A.3	OFFSITE I-35 DITCH	0.12	SILT FENCE
D.A.4	INLET EXISTING CROSS DRAIN	0.38	SILT FENCE
D.A.5	OFFSITE DOWNSTREAM CHANNEL	0.49	SILT DIKE/FIBER LOG
TOTALS =		1.78	



SUMMARY OF DISTURBED AREA (HOME ROAD)			
DRAINAGE AREA NUMBER	STRUCTURE DRAIN LOCATION	AREA ACRES	EROSION CONTROL MEASURES
D.A.1	I-35 DITCH SOUTH	1.03	SILT FENCE
D.A.2	I-35 MEDIAN DITCH SOUTH	0.05	SILT FENCE
D.A.3	I-35 DITCH SOUTH	0.39	SILT FENCE
D.A.4	I-35 INLET CROSS DRAIN	0.21	SILT DIKE/FIBER LOG
TOTALS =		1.68	


- LEGEND**
- TEMPORARY SILT DIKE INSTALLATION
 - TEMPORARY SILT FENCE INSTALLATION
 - FIBER LOG



DESIGN	BDC	09/18
DRAWN	ALM	09/18
CHECKED	BDC	09/18
APPROVED	JRW	09/18
SQUAD		

OKLAHOMA DEPARTMENT OF TRANSPORTATION
 GUY ENGINEERING SERVICES, INC.

EROSION CONTROL




SUMMARY OF DISTURBED AREA (INDIAN ROAD)

DRAINAGE AREA NUMBER	STRUCTURE DRAIN LOCATION	AREA ACRES	EROSION CONTROL MEASURES
D.A. 1	CROSS DRAIN I-35	0.43	SILT FENCE
D.A. 2	CROSS DRAIN I-35	0.55	SILT FENCE
D.A. 3	OFFSITE DITCH INDIAN ROAD	0.57	SILT FENCE
D.A. 4	OFFSITE DITCH INDIAN ROAD	0.55	SILT DIKE/FIBER LOG
TOTALS =		2.09	



LEGEND

- TEMPORARY SILT DIKE INSTALLATION
- TEMPORARY SILT FENCE INSTALLATION
- DISTURBED AREA



DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION GUY ENGINEERING SERVICES, INC.				
DRAWN	ALM	09/18					
CHECKED	BDC	09/18					
APPROVED	JRW	09/18					
SQUAD							
EROSION CONTROL							
COUNTY	KAY	HIGHWAY/ROAD	INDIAN RD	STATE JOB NO.	24432(15)	SHEET NO.	R015



DESCRIPTION	REVISIONS	DATE



Wednesday, October 24, 2018 1:26:56 PM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\NORTH\1070-NORTH PLAN & PROFILE.dwg

NOTE:
ALL UTILITY LOCATIONS
ARE APPROXIMATE.

DESCRIPTION	REVISIONS	DATE





BM 38
Sta. 26+90.03, 826.96' Lt.
R.R. Spike in Brace Post
148' Rt. Sta. 940+06
N=623906.85
E=2160402.62
EL=1022.25

BM 39
Sta. 25+92.15, 945.52' Rt.
"T" in Center of E. HDWL.
57' Rt. Sta. 922+34
N=622133.45
E=2160323.22
EL=1013.40


NOTE:
ALL UTILITY LOCATIONS
ARE APPROXIMATE.

DESCRIPTION	REVISIONS	DATE



NOTE:
ALL UTILITY LOCATIONS
ARE APPROXIMATE.



DESCRIPTION	REVISIONS	DATE



LEGEND

- BENCHMARK
- PROPOSED ASPH. SURFACING

**CAUTION
FIBER OPTIC
CROSSING**



Wednesday, October 24, 2018 1:27:58 PM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\COLEMAN\1070-COLEMAN P&P.dwg

71+00 72+00 73+00 74+00 75+00 76+00 77+00 78+00 79+00 80+00 81+00 82+00 83+00 84+00

DESCRIPTION	REVISIONS	DATE

NOTE:
ALL UTILITY LOCATIONS
ARE APPROXIMATE.

SECTION 30
T 27 N, R 1 W

SECTION 30
T 27 N, R 1 W

CRL CURVE #4
PI STA 84+08.68
 $\Delta=0^{\circ}45'48''$
 $D=0^{\circ}34'23''$
 $T=66.62'$
 $L=133.24'$
 $R=10000.00'$
 $EXT=0.22'$
 $X=2160643.0666$
 $Y=649450.2484$
 $V=45$ MPH
 $S=NC$

CRL CURVE #1
PI STA 72+96.62
 $\Delta=0^{\circ}56'36''$
 $D=0^{\circ}34'23''$
 $T=82.33'$
 $L=164.65'$
 $R=10000.00'$
 $EXT=0.34'$
 $X=2159531.0808$
 $Y=649446.9193$
 $V=45$ MPH
 $S=NC$

SECTION 31
T 27 N, R 1 W

CRL CURVE #2
PI STA 76+09.95
 $\Delta=0^{\circ}37'02''$
 $D=0^{\circ}34'23''$
 $T=53.86'$
 $L=107.72'$
 $R=10000.00'$
 $EXT=0.15'$
 $X=2159844.3678$
 $Y=649452.4191$
 $V=45$ MPH
 $S=NC$

CRL CURVE #3
PI STA 80+15.47
 $\Delta=1^{\circ}06'20''$
 $D=0^{\circ}34'23''$
 $T=96.48'$
 $L=192.94'$
 $R=10000.00'$
 $EXT=0.47'$
 $X=2160249.8751$
 $Y=649455.1688$
 $V=45$ MPH
 $S=NC$


LEGEND

- BENCHMARK
- PROPOSED TBSC TYPE E SURFACING


**CAUTION
FIBER OPTIC
CROSSING**

CRL CHRYLER AVE STA. 78+02.53
= C I35 STA. 1195+55.21

SECTION 31
T 27 N, R 1 W




Wednesday, October 24, 2018 1:28:19 PM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\CHRYSLER\1070-CHRYSLER P&P.dwg



STA. 72+25.00 BEGIN CHRYSLER AVE J.P. NO. 24432(15)

STA. 84+50.00 END CHRYSLER AVE J.P. NO. 24432(15)

DESCRIPTION	REVISIONS	DATE



LEGEND



- BENCHMARK
- PROPOSED TBSC TYPE E SURFACING

NOTE:
ALL UTILITY LOCATIONS
ARE APPROXIMATE.

CRL CURVE #1
 PI STA 75+89.63
 $\Delta=5^{\circ}05'56''$
 $D=1^{\circ}38'13''$
 $T=155.84'$
 $L=311.47'$
 $R=3500.00'$
 $EXT=3.47'$
 $X=2159753.6561$
 $Y=654714.3899$
 $V=40$ MPH
 $S=NC$

CRL CURVE #2
 PI STA 80+14.98
 $\Delta=13^{\circ}01'15''$
 $D=5^{\circ}43'46''$
 $T=114.12'$
 $L=227.25'$
 $R=1000.00'$
 $EXT=6.49'$
 $X=2160177.5648$
 $Y=654751.7560$
 $V=20$ MPH
 $S=NC$

SECTION 19
T 27 N, R 1 W



Wednesday, October 24, 2018 1:28:38 PM
 V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\FERGUSON\1070-FERGUSON P&P.dwg

DESCRIPTION	REVISIONS	DATE

CRL CURVE #3
 PI STA 84+39.32
 $\Delta=14^{\circ}06'04''$
 $D=6^{\circ}01'52''$
 $T=117.50'$
 $L=233.80'$
 $R=950.00'$
 $EXT=7.24'$
 $X=2160598.7643$
 $Y=654692.6853$
 $V=20$ MPH
 $S=NC$


CRL CURVE #4
 PI STA 86+84.77
 $\Delta=6^{\circ}10'45''$
 $D=6^{\circ}01'52''$
 $T=51.27'$
 $L=102.45'$
 $R=950.00'$
 $EXT=1.38'$
 $X=2160844.0049$
 $Y=654718.9709$
 $V=20$ MPH
 $S=NC$

SECTION 19
 T 27 N, R 1 W

SECTION 30
 T 27 N, R 1 W



**CAUTION
 POWER
 CROSSING**

MEET AND MATCH
 EXISTING WIDTH,
 DITCHES AND
 GRADE



NOTE:
 ALL UTILITY LOCATIONS
 ARE APPROXIMATE.

- LEGEND**
- BENCHMARK
 - PROPOSED ASPH. SURFACING



STA. 89+10.00 END FERGUSON J.P. NO. 24432(15)

SECTION 7
T 27 N, R 1 W


CRL CURVE #1
PI STA 84+72.10
 $\Delta=0^{\circ}26'54''$
 $D=0^{\circ}34'23''$
 $T=39.12'$
 $L=78.24'$
 $R=10000.00'$
EXT=0.08'
X=2160536.7701
Y=665312.4913
V= 45 MPH
S= NC

SECTION 7
T 27 N, R 1 W

CRL CURVE #2
PI STA 90+08.31
 $\Delta=0^{\circ}40'03''$
 $D=0^{\circ}34'23''$
 $T=58.24'$
 $L=116.49'$
 $R=10000.00'$
EXT=0.17'
X=2161072.9735
Y=665310.1218
V= 45 MPH
S= NC

DESCRIPTION	REVISIONS	DATE

CRL CURVE #3
PI STA 92+19.75
 $\Delta=0^{\circ}24'35''$
 $D=0^{\circ}34'23''$
 $T=35.76'$
 $L=71.53'$
 $R=10000.00'$
EXT=0.06'
X=2161284.3913
Y=665306.7246
V= 45 MPH
S= NC





LEGEND

- BENCHMARK
- PROPOSED TBSC TYPE E SURFACING
- NOTE: ALL UTILITY LOCATIONS ARE APPROXIMATE.

SECTION 18
T 27 N, R 1 W


STA. 1353+97 @ 3' X 2' X 141'
RDY RCB "X"ING @ 68' LT & 71' RT
FLELEV. 1060.8' LT & 1060.3' RT

**CAUTION
FIBER OPTIC
CROSSING**



Wednesday, October 24, 2018 1:29:07 PM
V:\16-1070E BR Raising Over I-35_Kay_1840_HNTB\CIV3D\PLANS\ADOBE\ADOBE_P&P.dwg

Wednesday, October 24, 2018 1:29:27 PM
 V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HOME\1070 - HOME PLAN AND PROFILE.dwg







DESCRIPTION	REVISIONS	DATE

LEGEND
 BENCHMARK




NOTE:
 ALL UTILITY LOCATIONS
 ARE APPROXIMATE.

**CAUTION
 FIBER OPTIC
 CROSSING**





DESCRIPTION	REVISIONS	DATE



- GENERAL TRAFFIC CONTROL NOTES:**
1. MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (FEET) SHALL BE TWICE THE POSTED SPEED LIMIT (M.P.H.) WITH THE FOLLOWING EXCEPTIONS: SPACING SHALL NOT EXCEED 50 FEET FOR CONES OR TUBE CHANNELIZERS. SPACING SHALL NOT EXCEED 75 FEET FOR CHANNELIZER CONES. SPACING SHALL NOT EXCEED 100 FEET FOR TYPE II BARRICADES, VERTICAL PANELS OR DRUMS.
 2. FOR TAPERS, A MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (IN FEET) SHALL BE EQUAL TO THE POSTED SPEED LIMIT (MPH). DOWNSTREAM TAPERS SHALL CONTAIN A MINIMUM OF FOUR (4) CHANNELIZING DEVICES.
 3. PORTABLE LONGITUDINAL BARRIERS SHALL BE POSITIONED TO ALLOW 2' SHY DISTANCE FROM OUTSIDE OF TRAVEL WAY.

LEGEND

- ▲ SIGN
- DRUM
- PORTABLE MEDIAN BARRIER
- ▣ CONST ZONE IMPACT ATTENUATOR
- ▴ TYPE III BARRICADE

NOTE:
THIS SHEET REPRESENTS TRAFFIC CONTROL AND PORTABLE LONGITUDINAL BARRIER PLACEMENT FOR NORTH BOUND TRAFFIC. PLACEMENT OF TRAFFIC CONTROLS AND BARRIERS WOULD ALSO BE PLACED IN THE SOUTH BOUND DIRECTION IN THE SAME MANNER AS SHOWN FOR THE NORTH BOUND DIRECTION.




DESIGN	BDC	09/18
DRAWN	ALM	09/18
CHECKED	BDC	09/18
APPROVED	JRW	09/18
SQUAD		

OKLAHOMA DEPARTMENT OF TRANSPORTATION
GUY ENGINEERING SERVICES, INC.
ADVANCE WARNING SIGNS
(TYP SHOULDER WORK)
STATE JOB NO. 24432(15) SHEET NO. T001

DRAWING NOT TO SCALE

Thursday, October 25, 2018 8:38:06 AM V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\1070-ADVANCE WARNING SIGN.dwg

DESCRIPTION	REVISIONS	DATE



GENERAL TRAFFIC CONTROL NOTES:

1. MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (FEET) SHALL BE TWICE THE POSTED SPEED LIMIT (M.P.H.) WITH THE FOLLOWING EXCEPTIONS: SPACING SHALL NOT EXCEED 50 FEET FOR CONES OR TUBE CHANNELIZERS. SPACING SHALL NOT EXCEED 75 FEET FOR CHANNELIZER CONES, SPACING SHALL NOT EXCEED 100 FEET FOR TYPE II BARRICADES, VERTICAL PANELS OR DRUMS.
2. FOR TAPERS, A MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (IN FEET) SHALL BE EQUAL TO THE POSTED SPEED LIMIT (MPH). DOWNSTREAM TAPERS SHALL CONTAIN A MINIMUM OF FOUR (4) CHANNELIZING DEVICES.
3. PORTABLE LONGITUDINAL BARRIERS SHALL BE POSITIONED TO ALLOW 2' SHY DISTANCE FROM INSIDE LANE.

LEGEND

- ▲ SIGN
- ARROW DISPLAY
- DRUM
- PORTABLE MEDIAN BARRIER
- ▣ CONST ZONE IMPACT ATTENUATOR

NOTE: THIS SHEET REPRESENTS TRAFFIC CONTROL AND PORTABLE LONGITUDINAL BARRIER PLACEMENT FOR NORTH BOUND TRAFFIC. PLACEMENT OF TRAFFIC CONTROLS AND BARRIERS WOULD ALSO BE PLACED IN THE SOUTH BOUND DIRECTION IN THE SAME MANNER AS SHOWN FOR THE NORTH BOUND DIRECTION.

DESIGN	BDC	09/18
DRAWN	ALM	09/18
CHECKED	BDC	09/18
APPROVED	JRW	09/18
SQUAD		


OKLAHOMA DEPARTMENT OF TRANSPORTATION
GUY ENGINEERING SERVICES, INC.
ADVANCE WARNING SIGNS
(TYP LANE CLOSURE)
 STATE JOB NO. 24432(15) SHEET NO. T002

DRAWING NOT TO SCALE

Thursday, October 25, 2018 8:38:46 AM V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\1070-ADVANCE WARNING SIGN.dwg

Thursday, October 25, 2018 8:39:00 AM
 V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\1070-ADVANCE WARNING SIGN.dwg

DESCRIPTION	REVISIONS	DATE



* PERMANENT SIGNS WILL BE PLACED FOR HOME ROAD.
 "ROAD CLOSED" SIGNS WILL BE PLACE APPROXIMATELY 150'
 LT & RT OF I-35 C.L. AT HOME ROAD. TYPE A FLASHERS
 WILL NOT BE ON PERMANENT SIGNS.

LEGEND

- SIGN
- CONSTRUCTION COMPLETE
- WORK AREA
- DRUM
- PORTABLE MEDIAN BARRIER
- CONST ZONE IMPACT ATTENUATOR
- TYPE III BARRICADE

DESIGN	BDC	09/18
DRAWN	ALM	09/18
CHECKED	BDC	09/18
APPROVED	JRW	09/18
SQUAD		



OKLAHOMA DEPARTMENT OF TRANSPORTATION
 GUY ENGINEERING SERVICES, INC.

**WARNING SIGNS
 (TYP SECTION LINE)**

STATE JOB NO. 24432(15) SHEET NO. T003

DRAWING NOT TO SCALE

DESCRIPTION	REVISIONS	DATE



GENERAL TRAFFIC CONTROL NOTES:

1. MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (FEET) SHALL BE TWICE THE POSTED SPEED LIMIT (M.P.H.) WITH THE FOLLOWING EXCEPTIONS: SPACING SHALL NOT EXCEED 50 FEET FOR CONES OR TUBE CHANNELIZERS. SPACING SHALL NOT EXCEED 75 FEET FOR CHANNELIZER CONES, SPACING SHALL NOT EXCEED 100 FEET FOR TYPE II BARRICADES, VERTICAL PANELS OR DRUMS.
2. FOR TAPERS, A MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (IN FEET) SHALL BE EQUAL TO THE POSTED SPEED LIMIT (MPH). DOWNSTREAM TAPERS SHALL CONTAIN A MINIMUM OF FOUR (4) CHANNELIZING DEVICES.

LEGEND

- ▤ TYPE III BARRICADE W/TYPE A LIGHTS & R11-2 "ROAD CLOSED"
- SIGN
- DRUM OR OTHER CHANNELIZER
- DIRECTION OF TRAFFIC
- ⇨ ARROW DISPLAY

NOTE: SHEETS T004-T006 ARE FOR SHIFTING ALL TRAFFIC TO THE NORTHBOUND LANES.

* ADVANCE WARNING TRAFFIC CONTROL SHOWN FOR NORTH BOUND TRAFFIC. SOUTH BOUND ADVANCE WARNING FOR TRAFFIC CONTROL IS NOT SHOWN. HOWEVER, THE SAME SIGNS, TAPERS AND LAYOUT FOR SOUTH BOUND LANES WOULD APPLY.

ADVANCE WARNING CROSSOVER NORTH BOUND LEFT LANE CLOSURE

Thursday, October 25, 2018 8:25:43 AM V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\1070-CROSSOVER TRAFFIC CONTROL.dwg



DESIGN	BDC	09/18
DRAWN	ALM	09/18
CHECKED	BDC	09/18
APPROVED	JRW	09/18
SQUAD		

OKLAHOMA DEPARTMENT OF TRANSPORTATION
GUY ENGINEERING SERVICES, INC.
TRAFFIC CONTROL CROSSOVER
DETAIL 1

STATE JOB NO. 24432(15) SHEET NO. T004

DRAWING NOT TO SCALE

Thursday, October 25, 2018 8:25:00 AM
 V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\1070-CROSSOVER TRAFFIC CONTROL.dwg



KEY MAP


DESCRIPTION	REVISIONS	DATE

GENERAL TRAFFIC CONTROL NOTES:

1. MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (FEET) SHALL BE TWICE THE POSTED SPEED LIMIT (M.P.H.) WITH THE FOLLOWING EXCEPTIONS: SPACING SHALL NOT EXCEED 50 FEET FOR CONES OR TUBE CHANNELIZERS. SPACING SHALL NOT EXCEED 75 FEET FOR CHANNELIZER CONES, SPACING SHALL NOT EXCEED 100 FEET FOR TYPE II BARRICADES, VERTICAL PANELS OR DRUMS.
2. FOR TAPERS, A MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (IN FEET) SHALL BE EQUAL TO THE POSTED SPEED LIMIT (MPH). DOWNSTREAM TAPERS SHALL CONTAIN A MINIMUM OF FOUR (4) CHANNELIZING DEVICES.

LEGEND

- ∩∩∩ TYPE III BARRICADE W/TYPE A LIGHTS & R11-2 "ROAD CLOSED"
- SIGN
- DRUM OR OTHER CHANNELIZER
- ARROW DISPLAY
- DIRECTION OF TRAFFIC
- ▨ EXISTING PAVED MEDIAN TO BE USED AS CROSSOVER



TRAFFIC CONTROL CROSSOVER "A" FROM NORTH BOUND LANES BACK TO SOUTHBOUND LANES

DESIGN	BDC	09/18
DRAWN	ALM	09/18
CHECKED	BDC	09/18
APPROVED	JRW	09/18
SQUAD		

OKLAHOMA DEPARTMENT OF TRANSPORTATION
 GUY ENGINEERING SERVICES, INC.

**TRAFFIC CONTROL
 CROSSOVER DETAIL 2**


STATE JOB NO. 24432(15) SHEET NO. T005

DRAWING NOT TO SCALE

DESCRIPTION	REVISIONS	DATE

LEGEND

- ∩∩∩ TYPE III BARRICADE W/TYPE A LIGHTS & R11-2 "ROAD CLOSED"
- ⊣ SIGN
- DRUM OR OTHER CHANNELIZER
- DIRECTION OF TRAFFIC
- ▨ EXISTING PAVED MEDIAN TO BE USED AS CROSSOVER



CRL CURVE DATA TABLE (CROSSOVER NORTH OF SH-177 SHIFT SOUTHBOUND TRAFFIC BACK TO SOUTHBOUND LANES)


ALIGNMENT PT.	STATION	BEARING	DISTANCE	NORTHING	EASTING
P.C.	779+44.37	N05°50'36"E	110.15	708,265.40	2,159,676.52
P.I.	780+54.52			708,427.78	2,159,695.64
P.T.	781+64.24	N14°37'21"E	11.41	708,590.29	2,159,677.74
P.C.	781+75.65			708,598.32	2,159,676.85
P.I.	783+29.58	N14°37'21"E	153.93	708,708.15	2,159,664.75
P.T.	784+82.33			708,818.53	2,159,669.61

GENERAL TRAFFIC CONTROL NOTES:

1. MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (FEET) SHALL BE TWICE THE POSTED SPEED LIMIT (M.P.H.) WITH THE FOLLOWING EXCEPTIONS: SPACING SHALL NOT EXCEED 50 FEET FOR CONES OR TUBE CHANNELIZERS. SPACING SHALL NOT EXCEED 75 FEET FOR CHANNELIZER CONES, SPACING SHALL NOT EXCEED 100 FEET FOR TYPE II BARRICADES, VERTICAL PANELS OR DRUMS.
2. FOR TAPERS, A MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (IN FEET) SHALL BE EQUAL TO THE POSTED SPEED LIMIT (MPH). DOWNSTREAM TAPERS SHALL CONTAIN A MINIMUM OF FOUR (4) CHANNELIZING DEVICES.

CRL CURVE DATA TABLE (CROSSOVER NORTH OF SH-177 SHIFT SOUTHBOUND TRAFFIC BACK TO SOUTHBOUND LANES)

CURVE NO.	P.I. STATION	Δ	D	R	T	L	E	P.C.		P.I.		C.C.		P.T.		DESIGN V MPH	FULL SUPER
								NORTHING	EASTING	NORTHING	EASTING	NORTHING	EASTING	NORTHING	EASTING		
C1	780+54.52	8°46'45"	3°59'34"	1435.00	110.15	219.87	4.22	708,478.64	2,159,644.43	708,588.22	2,159,655.64	708,587.47	2,159,659.80	708,694.80	2,159,683.45	50	N.C.
C2	783+29.58	12°14'42"	3°59'34"	1435.00	153.93	306.68	8.23	708,705.84	2,159,686.33	708,854.78	2,159,725.19	708,856.00	2,159,717.05	709,008.58	2,159,731.57	50	N.C.



KEY MAP


TRAFFIC CONTROL CROSSOVER "A" ENLARGED DETAIL

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION GUY ENGINEERING SERVICES, INC. TRAFFIC CONTROL CROSSOVER DETAIL 3 STATE JOB NO. 24432(15) SHEET NO. T006
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			

DRAWING NOT TO SCALE

Thursday, October 25, 2018 8:26:27 AM V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\1070-CROSSOVER TRAFFIC CONTROL.dwg

DESCRIPTION	REVISIONS	DATE




- GENERAL TRAFFIC CONTROL NOTES:**
1. MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (FEET) SHALL BE TWICE THE POSTED SPEED LIMIT (M.P.H.) WITH THE FOLLOWING EXCEPTIONS: SPACING SHALL NOT EXCEED 50 FEET FOR CONES OR TUBE CHANNELIZERS. SPACING SHALL NOT EXCEED 75 FEET FOR CHANNELIZER CONES, SPACING SHALL NOT EXCEED 100 FEET FOR TYPE II BARRICADES, VERTICAL PANELS OR DRUMS.
 2. FOR TAPERS, A MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (IN FEET) SHALL BE EQUAL TO THE POSTED SPEED LIMIT (MPH). DOWNSTREAM TAPERS SHALL CONTAIN A MINIMUM OF FOUR (4) CHANNELIZING DEVICES.

- LEGEND**
- ▽ TYPE III BARRICADE W/TYPE A LIGHTS & R11-2 "ROAD CLOSED"
 - SIGN
 - DRUM OR OTHER CHANNELIZER
 - ARROW DISPLAY
 - DIRECTION OF TRAFFIC

NOTE: SHEETS T007-T009 ARE FOR SHIFTING ALL TRAFFIC TO THE SOUTHBOUND LANES.

* ADVANCE WARNING TRAFFIC CONTROL SHOWN FOR NORTH BOUND TRAFFIC. SOUTH BOUND ADVANCE WARNING FOR TRAFFIC CONTROL IS NOT SHOWN. HOWEVER, THE SAME SIGNS, TAPERS AND LAYOUT FOR SOUTH BOUND LANES WOULD APPLY.




ADVANCE WARNING CROSSOVER NORTH BOUND RIGHT LANE CLOSURE

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION GUY ENGINEERING SERVICES, INC. TRAFFIC CONTROL CROSSOVER DETAIL 4 STATE JOB NO. 24432(15) SHEET NO. T007
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			

DRAWING NOT TO SCALE

Thursday, October 25, 2018 8:26:50 AM V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\1070-CROSSOVER TRAFFIC CONTROL.dwg

Thursday, October 25, 2018 8:33:20 AM
 V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\1070-CROSSOVER TRAFFIC CONTROL.dwg




MATCHLINE B

LEGEND

- ∩∩ TYPE III BARRICADE W/TYPE A LIGHTS & R11-2 "ROAD CLOSED"
- SIGN
- DRUM OR OTHER CHANNELIZER
- ⇄ ARROW DISPLAY
- DIRECTION OF TRAFFIC
- ▨ EXISTING PAVED MEDIAN TO BE USED AS CROSSOVER

- GENERAL TRAFFIC CONTROL NOTES:**
1. MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (FEET) SHALL BE TWICE THE POSTED SPEED LIMIT (M.P.H.) WITH THE FOLLOWING EXCEPTIONS: SPACING SHALL NOT EXCEED 50 FEET FOR CONES OR TUBE CHANNELIZERS. SPACING SHALL NOT EXCEED 75 FEET FOR CHANNELIZER CONES, SPACING SHALL NOT EXCEED 100 FEET FOR TYPE II BARRICADES, VERTICAL PANELS OR DRUMS.
 2. FOR TAPERS, A MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (IN FEET) SHALL BE EQUAL TO THE POSTED SPEED LIMIT (MPH). DOWNSTREAM TAPERS SHALL CONTAIN A MINIMUM OF FOUR (4) CHANNELIZING DEVICES.

DESCRIPTION	REVISIONS	DATE



KEY MAP

SEE ENLARGED DETAIL CROSSOVER "A" SHEET T009

I-35 SOUTH BI-DIRECTIONAL TRAFFIC
 I-35 NORTH CLOSED

TRAFFIC CONTROL CROSSOVER "A" FROM NORTH BOUND TO SOUTH BOUND LANES

DRAWING NOT TO SCALE

DESIGN	BDC	09/18
DRAWN	ALM	09/18
CHECKED	BDC	09/18
APPROVED	JRW	09/18
SQUAD		

OKLAHOMA DEPARTMENT OF TRANSPORTATION
 GUY ENGINEERING SERVICES, INC.
TRAFFIC CONTROL CROSSOVER DETAIL 5
 STATE JOB NO. 24432(15) SHEET NO. T008


DESCRIPTION	REVISIONS	DATE

LEGEND

- ▽▽ TYPE III BARRICADE W/TYPE A LIGHTS & R11-2 "ROAD CLOSED"
- SIGN
- DRUM OR OTHER CHANNELIZER
- ▨ WORK AREA
- DIRECTION OF TRAFFIC
- ▨ EXISTING PAVED MEDIAN TO BE USED AS CROSSOVER

GENERAL TRAFFIC CONTROL NOTES:

1. MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (FEET) SHALL BE TWICE THE POSTED SPEED LIMIT (M.P.H.) WITH THE FOLLOWING EXCEPTIONS: SPACING SHALL NOT EXCEED 50 FEET FOR CONES OR TUBE CHANNELIZERS. SPACING SHALL NOT EXCEED 75 FEET FOR CHANNELIZER CONES, SPACING SHALL NOT EXCEED 100 FEET FOR TYPE II BARRICADES, VERTICAL PANELS OR DRUMS.
2. FOR TAPERS, A MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (IN FEET) SHALL BE EQUAL TO THE POSTED SPEED LIMIT (MPH). DOWNSTREAM TAPERS SHALL CONTAIN A MINIMUM OF FOUR (4) CHANNELIZING DEVICES.




CRL CURVE DATA TABLE (CROSSOVER NORTH OF SH-177 SHIFT ALL TRAFFIC TO SOUTHBOUND LANES)


CURVE NO.	P.I. STATION	Δ	D	R	T	L	E	P.C.		P.I.		C.C.		P.T.		DESIGN V MPH	FULL SUPER
								NORTHING	EASTING	NORTHING	EASTING	NORTHING	EASTING	NORTHING	EASTING		
C3	778+98.57	13°00'00"	3°59'34"	1435.00	163.50	325.59	9.28	708,265.40	2,159,676.52	708,427.78	2,159,695.64	708,427.81	2,159,686.35	708,590.29	2,159,677.74	50	N.C.
C4	781+79.23	08°48'21"	3°59'34"	1435.00	110.49	220.55	4.25	708,598.32	2,159,676.85	708,708.15	2,159,664.75	708,708.29	2,159,669.00	708,818.53	2,159,669.61	50	N.C.

CRL ALIGNMENT TABLE (CROSSOVER NORTH OF SH-177 SOUTH TO NORTHBOUND)

ALIGNMENT PT.	STATION	BEARING	DISTANCE	NORTHING	EASTING
P.C.	777+35.07			708,265.40	2,159,676.52
P.I.	778+98.57	N06°42'49"E	163.50	708,427.78	2,159,695.64
P.T.	780+60.66	N06°17'11"W		708,590.29	2,159,677.74
P.C.	780+68.74	N06°17'11"W	8.08	708,598.32	2,159,676.85
P.I.	781+79.23	N06°17'11"W	110.49	708,708.15	2,159,664.75
P.T.	782+89.29	N02°31'10"E		708,818.53	2,159,669.61



KEY MAP



TRAFFIC CONTROL CROSSOVER "A" ENLARGED DETAIL

DESIGN	BDC	09/18
DRAWN	ALM	09/18
CHECKED	BDC	09/18
APPROVED	JRW	09/18
SQUAD		

OKLAHOMA DEPARTMENT OF TRANSPORTATION
GUY ENGINEERING SERVICES, INC.

TRAFFIC CONTROL CROSSOVER DETAIL 6


STATE JOB NO. 24432(15) SHEET NO. T009

DRAWING NOT TO SCALE

LEGEND

- ▽▽ TYPE III BARRICADE W/TYPE A LIGHTS & R11-2 "ROAD CLOSED"
- SIGN
- DRUM OR OTHER CHANNELIZER
- DIRECTION OF TRAFFIC
- ▨ EXISTING PAVED MEDIAN TO BE USED AS CROSSOVER

DESCRIPTION	REVISIONS	DATE



CRL CURVE DATA TABLE (CROSSOVER SOUTH OF INDIAN ROAD SHIFT ALL TRAFFIC TO NORTHBOUND SIDE)


ALIGNMENT PT.	STATION	BEARING	DISTANCE	NORTHING	EASTING
P.C.	857+95.93	N00°20'23"W	124.95	716,328.57	2,159,715.30
P.I.	859+20.88			716,451.52	2,159,714.57
P.T.	860+45.20	N10°17'33"W	56.93	716,574.46	2,159,692.24
P.C.	861+02.13	N10°17'33"W		716,630.47	2,159,682.07
P.I.	862+30.78	N00°14'35"W	128.65	716,757.05	2,159,659.09
P.T.	863+53.82			716,883.22	2,159,658.55

GENERAL TRAFFIC CONTROL NOTES:

1. MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (FEET) SHALL BE TWICE THE POSTED SPEED LIMIT (M.P.H.) WITH THE FOLLOWING EXCEPTIONS: SPACING SHALL NOT EXCEED 50 FEET FOR CONES OR TUBE CHANNELIZERS. SPACING SHALL NOT EXCEED 75 FEET FOR CHANNELIZER CONES, SPACING SHALL NOT EXCEED 100 FEET FOR TYPE II BARRICADES, VERTICAL PANELS OR DRUMS.
2. FOR TAPERS, A MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (IN FEET) SHALL BE EQUAL TO THE POSTED SPEED LIMIT (MPH). DOWNSTREAM TAPERS SHALL CONTAIN A MINIMUM OF FOUR (4) CHANNELIZING DEVICES.

CRL CURVE DATA TABLE (CROSSOVER SOUTH OF INDIAN ROAD SHIFT ALL TRAFFIC TO NORTHBOUND SIDE)

CURVE NO.	P.I. STATION	Δ	D	R	T	L	E	P.C.		P.I.		C.C.		P.T.		DESIGN V MPH	FULL SUPER
								NORTHING	EASTING	NORTHING	EASTING	NORTHING	EASTING	NORTHING	EASTING		
C5	856+20.88	9°57'10"	3°59'34"	1435.00	124.95	249.27	5.43	716,328.57	2,159,715.30	716,451.52	2,159,714.57	716,451.01	2,159,709.16	716,574.46	2,159,692.24	50	N.C.
C6	859+30.78	10°2'58"	3°59'34"	1435.00	128.65	251.69	5.54	716,630.47	2,159,682.07	716,757.05	2,159,659.09	716,757.56	2,159,664.60	716,883.22	2,159,658.55	50	N.C.



KEY MAP

TRAFFIC CONTROL CROSSOVER "B" ENLARGED DETAIL

DESIGN	BDC	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION GUY ENGINEERING SERVICES, INC. TRAFFIC CONTROL CROSSOVER DETAIL 7 STATE JOB NO. 24432(15) SHEET NO. TOIO
DRAWN	ALM	09/18	
CHECKED	BDC	09/18	
APPROVED	JRW	09/18	
SQUAD			


DRAWING NOT TO SCALE

Thursday, October 25, 2018 8:35:17 AM V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\1070-CROSSOVER TRAFFIC CONTROL.dwg

Thursday, October 25, 2018 8:35:49 AM
 V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\1070-CROSSOVER TRAFFIC CONTROL.dwg

DESCRIPTION	REVISIONS	DATE

- LEGEND**
- ▽ TYPE III BARRICADE W/TYPE A LIGHTS & R11-2 "ROAD CLOSED"
 - SIGN
 - DRUM OR OTHER CHANNELIZER
 - DIRECTION OF TRAFFIC
 - ▨ EXISTING PAVED MEDIAN TO BE USED AS CROSSOVER



CRL CURVE DATA TABLE (CROSSOVER SOUTH OF INDIAN ROAD SHIFT NORTHBOUND TRAFFIC BACK TO NORTHBOUND LANES)


ALIGNMENT PT.	STATION	BEARING	DISTANCE	NORTHING	EASTING
P.C.	858+24.67	N00°18'49"W	125.82	716,355.03	2,159,661.15
P.I.	859+50.49			716,480.84	2,159,660.46
P.T.	860+75.66	N9°42'27"E	59.40	716,604.85	2,159,681.68
P.C.	861+35.06	N9°42'27"E	125.17	716,663.40	2,159,691.69
P.I.	862+60.23			716,786.78	2,159,712.80
P.T.	863+84.77	N00°15'45"W		716,911.95	2,159,712.23

GENERAL TRAFFIC CONTROL NOTES:

- MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (FEET) SHALL BE TWICE THE POSTED SPEED LIMIT (M.P.H.) WITH THE FOLLOWING EXCEPTIONS: SPACING SHALL NOT EXCEED 50 FEET FOR CONES OR TUBE CHANNELIZERS. SPACING SHALL NOT EXCEED 75 FEET FOR CHANNELIZER CONES. SPACING SHALL NOT EXCEED 100 FEET FOR TYPE II BARRICADES, VERTICAL PANELS OR DRUMS.
- FOR TAPERS, A MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES (IN FEET) SHALL BE EQUAL TO THE POSTED SPEED LIMIT (MPH). DOWNSTREAM TAPERS SHALL CONTAIN A MINIMUM OF FOUR (4) CHANNELIZING DEVICES.

CRL CURVE DATA TABLE (CROSSOVER SOUTH OF INDIAN ROAD SHIFT NORTHBOUND TRAFFIC BACK TO NORTHBOUND LANES)

CURVE NO.	P.I. STATION	Δ	D	R	T	L	E	P.C.		P.I.		C.C.		P.T.		DESIGN V MPH	FULL SUPER
								NORTHING	EASTING	NORTHING	EASTING	NORTHING	EASTING	NORTHING	EASTING		
C7	859+50.49	10°01'17"	3°59'34"	1435.00	125.82	250.99	5.51	716,355.03	2,159,661.15	716,480.84	2,159,660.46	716,480.39	2,159,665.95	716,604.85	2,159,681.68	50	N.C.
C8	862+60.23	9°58'13"	3°59'34"	1435.00	125.17	249.71	5.45	716,663.40	2,159,691.69	716,786.78	2,159,712.80	716,787.23	2,159,707.37	716,911.95	2,159,712.23	50	N.C.



KEY MAP

TRAFFIC CONTROL CROSSOVER "B" ENLARGED DETAIL

DRAWING NOT TO SCALE

DESIGN	BDC	09/18
DRAWN	ALM	09/18
CHECKED	BDC	09/18
APPROVED	JRW	09/18
SQUAD		


OKLAHOMA DEPARTMENT OF TRANSPORTATION
 GUY ENGINEERING SERVICES, INC.
TRAFFIC CONTROL CROSSOVER DETAIL 8
 STATE JOB NO. 24432(15) SHEET NO. T011

DESCRIPTION	REVISIONS	DATE

I-35 SOUTH

I-35 NORTH


MATCHLINE A



LEGEND

- ▲ SIGN
- DRUM
- PORTABLE MEDIAN BARRIER
- ▨ CONST ZONE IMPACT ATTENUATOR
- △△ TYPE III BARRICADE

BORDER
R=1.5"
TH=0.75"
IN=0.75"



- COLOR:
LEGEND, SYMBOL AND BORDER
BLACK (NON-REFLECTORIZED)
BACKGROUND:
- ▲ FLUORESCENT ORANGE (REFLECTORIZED)
 - * FLUORESCENT YELLOW (REFLECTORIZED)
 - WHITE (REFLECTORIZED)
 - RED (NON-REFLECTORIZED)

Wednesday, October 24, 2018 1:33:15 PM W:\16-1070E BR Raising Over I-35, Key, 1840, HNTB\CIV3D\PLANS\1070-ADV WRNING SIGN-ROLL ROADBLCK.dwg

DESIGN	MZV	09/18
DRAWN	BDC	09/18
CHECKED	JRW	09/18
APPROVED	JRW	09/18
SQUAD		

OKLAHOMA DEPARTMENT OF TRANSPORTATION
GUY ENGINEERING SERVICES, INC.

**ROLLING ROADBLOCK
DETAIL 1**


STATE JOB NO. 24432(15) SHEET NO. T012

DRAWING NOT TO SCALE

KAY I-35 BRIDGES US-60 TO OK-KS STATE LINE

Wednesday, October 24, 2018 2:37:07 PM
 W:\16-1070E BR Raising Over I-35, Key, 1840, HNTB\CIV3D\PLANS\1070-TRAFF CNTRL ROLLING ROADBLOCK.dwg

DESCRIPTION	REVISIONS	DATE




ROLLING ROADBLOCK SCHEMATIC (NB I-35)

Not To Scale

- NOTES:
- THE ROLLING ROADBLOCK OPERATION CONSISTS OF PROVIDING TRAFFIC PACING OPERATIONS TO MOTORISTS WITHIN THE PROJECT AREA, AS SHOWN. IT INCLUDES LOCATING, PROVIDING ROADSIDE ASSISTANCE AND CLEARING TRAFFIC RELATED INCIDENTS. THE USE OF LAW ENFORCEMENT OFFICERS SHALL BE INTEGRATED INTO THE ROLLING ROADBLOCK OPERATIONS. ODOT DIVISION 4 SHALL BE RESPONSIBLE FOR PROCUREMENT OF OKLAHOMA AND KANSAS HIGHWAY PATROL PERSONNEL AND VEHICLES.
 - THE CONTRACTOR SHALL PROVIDE A TRAFFIC CONTROL PLAN FOR REVIEW AND OBTAIN APPROVAL PRIOR TO IMPLEMENTING THE FIRST ROLLING ROADBLOCK. THE PLAN SHALL INCLUDE A PACING PLAN. THE PACING PLAN SHALL INCLUDE A SUMMARY THE CONTRACTOR'S EQUIPMENT, PERSONNEL, INCLUDING LAW ENFORCEMENT PERSONNEL, AND A DETAILED DESCRIPTION OF THE OPERATION. A CONTINGENCY PLAN SHALL BE INCLUDED TO ACCOUNT FOR BREAKDOWN OF THE CONTRACTOR'S CRITICAL EQUIPMENT AND TO ADDRESS EMERGENCIES THAT REQUIRE EXITING THE QUEUE. IF THERE ARE CERTAIN WORK ACTIVITIES THAT NEED TO BE COMPLETED PRIOR TO START OF WORK, THE ACTIVITIES SHOULD BE CLEARLY DETAILED IN A CHECKLIST THAT IS USED TO ENSURE THAT ALL PREPARATIONS HAVE BEEN MADE PRIOR TO INITIATING THE ROLLING ROADBLOCK.
 - THE ROADBLOCK OPERATION FOR A GIVEN LOCATION SHALL BE CONDUCTED BETWEEN THE HOURS OF 8:00 PM AND 6:00 AM. MONDAY EVENING THROUGH FRIDAY MORNING. IF NECESSARY, ROLLING ROADBLOCKS MAY BE REQUIRED ON WEEKENDS; LANE RENTAL FEES MAY BE INCURRED FOR DAYLIGHT OPERATIONS. ROLLING ROADBLOCKS WILL BE INITIATED SIMULTANEOUSLY IN BOTH DIRECTIONS FOR RAISING OF THE BRIDGE. THE BRIDGE WILL BE RAISED IN STAGES, NECESSITATING MULTIPLE ROLLING ROADBLOCKS (IN EACH DIRECTION).
 - A PLANNING MEETING WITH ALL ROLLING ROADBLOCK PARTICIPANTS SHALL BE HELD TWO TO THREE WEEKS IN ADVANCE OF THE FIRST EVENT TO DEFINE RESPONSIBILITIES AND TO ENSURE THAT THOSE ACTIVITIES REQUIRED FOR ACCOMPLISHING THE TASK WILL BE IN PLACE FOR THE ROADBLOCK. PERSONNEL SHALL INCLUDE AS A MINIMUM, A) THE LEAD COORDINATOR, WHO IS STATIONED AT THE WORK AREA AND COMMUNICATES WITH THE PACE CARS, B.) AN INDIVIDUAL OR INDIVIDUALS TO COMMUNICATE WITH THE LEAD COORDINATOR CONCERNING WORK STATUS, C.) SELECTED CONSTRUCTION PERSONNEL, AND D.) LAW ENFORCEMENT OFFICERS. FOUR OFFICERS ARE REQUIRED FOR EACH ROLLING ROADBLOCK (FOR EACH DIRECTION). THE PURPOSE OF THE MEETING IS TO IDENTIFY THE LEAD COORDINATOR, SET POINTS OF CONTACTS, TO SET LINES COMMUNICATION, AND TO REVIEW ROLES AND RESPONSIBILITIES. ADDITIONAL MEETINGS WILL BE HELD IF THERE ARE PERSONNEL CHANGES, OR AS NECESSARY. PLANNING MEETINGS WILL BE HELD AT ODOT DIVISION 4 IN PERRY.
 - A FINAL MEETING INVOLVING PARTICIPANTS SHALL BE HELD AT THE BRIDGE SITE TO REVIEW PROCEDURES AND TO ENSURE THAT ALL PRELIMINARY REQUIREMENTS FOR THE ROLLING ROADBLOCK HAVE BEEN IMPLEMENTED.
 - THE CONTRACTOR SHALL SIGN OFF ON THE PRE ROLLING ROADBLOCK CHECKLIST TO CONFIRM THAT EVERYTHING HAS BEEN COMPLETED FOR EACH LIFT. ON-RAMPS AND ENTRANCES BETWEEN THE BEGINNING POINT OF THE PACING AREA AND THE WORK AREA SHALL BE BLOCKED USING FLAGGERS AND TRAFFIC CONTROL DEVICES UNTIL THE PACE SETTING VEHICLES HAVE PASSED. THE CONTRACTOR SHALL PROVIDE TWO-WAY RADIOS THAT SHALL BE UTILIZED TO PROVIDE COMMUNICATION TO PACE VEHICLES, CONTRACTOR'S WORKERS, FLAGGERS STATIONED AT ON-RAMPS, AND THE ENGINEER.
 - A MINIMUM OF THREE WEEKS PRIOR TO THE START OF ROLLING ROADBLOCK OPERATIONS FOR A GIVEN LOCATION, THE CONTRACTOR SHALL PROVIDE THE DATE AND TIMES THAT ROLLING ROADBLOCK OPERATIONS ARE TO BEGIN TO THE ENGINEER, ODOT DISTRICT 4 TRAFFIC ENGINEER, ODOT PUBLIC INFORMATION OFFICE AND THE OKLAHOMA HIGHWAY PATROL TO ENABLE NOTIFICATION TO THE PUBLIC.
 - PORTABLE CHANGEABLE MESSAGE SIGNS SHALL BE DISPLAYED ONE WEEK PRIOR TO THE START OF A ROLLING ROADBLOCK. MESSAGES SHALL BE CHANGED TO INDICATE WHEN THE ROLLING ROADBLOCK OPERATIONS ARE IN EFFECT. PORTABLE CHANGEABLE MESSAGE SIGNS SHALL BE IN ACCORDANCE WITH SECTION 882, CHANGEABLE MESSAGE SIGN.
 - THE MAXIMUM PACING SPEED IS 10MPH.
 - MESSAGE SIGN TEXT SHALL BE PROVIDED BY THE ENGINEER.
 - ALL DETAILS SHOWN ON SHEET T001 APPLY, AS LONG AS SHOULDERS ARE CLOSED AT THE BRIDGE AND THE ROLLING ROADBLOCK IS NOT IN OPERATION. T001 SIGNS ARE COVERED WHEN THE ROLLING ROADBLOCK IS IN OPERATION. T012 SIGNS ARE COVERED WHEN THE ROLLING ROADBLOCK IS NOT IN EFFECT.
 - AS SHOWN, THE ROLLING ROADBLOCK IS BASED ON 30 MINUTES PER PHASE OF BRIDGE RAISING. MULTIPLE PHASES MAY BE REQUIRED.

Site	Location	Type	Ramp(s) Upstream	Approx. Dist. From Site (mi)	Type III Barricades (SD)	Wing Barricades (ramps) (SD)	Flagger (SD)	Port. Change. Message Signs (Crossroad) (SD)
1-NB	North	Raising	E0250	1.8	1	1	1	
			Local Road	5.4	1	1	1	
1-SB	North	Raising	US 60	0.8	1	1	1	14
			Hubbard Road	4.8	1	1	1	
2-NB	Highland	Raising	US 60	0.9	1	1	1	14
			E0250	3.0	1	1	1	
2-SB	Highland	Raising	Hubbard Road	2.8	1	1	1	
3-NB	Hartford	Raising	US 60	1.9	1	1	1	14
			E0250	4.0	1	1	1	
3-SB	Hartford	Raising	Hubbard Road	1.8	1	1	1	
4-NB	Coleman	Raising	Hubbard Road	1.0	1	1	1	
			US 60	5.0	1	1	1	14
4-SB	Coleman	Raising	SH 11	2.8	1	1	1	14
5-NB	Chrysler	Raising	Hubbard Road	1.9	1	1	1	
			US 60	5.8	1	1	1	14
5-SB	Chrysler	Raising	SH 11	1.7	1	1	1	14
6-NB	Ferguson	Raising	Hubbard Road	3.0	1	1	1	
6-SB	Ferguson	Raising	SH 11	0.8	1	1	1	14
7-NB	Adobe	Raising	SH 11	1.0	1	1	1	14
			Hubbard Road	4.9	1	1	1	
7-SB	Adobe	Raising	(None)					
8-NB	Home	Demo	US 177	1.0	1	1	1	14
			County Road	1.9	1	1	1	
8-SB	Home	Demo	Weigh Station	1.7	1	1	1	
9-NB	Indian	Raising	US 177	1.9	1	1	1	14
			County Road	2.8	1	1	1	
9-SB	Indian	Raising	Weigh Station	0.6	1	1	1	
Totals:					26	26	26	154

SUMMARY: TRAFFIC CONTROL DEVICES






ROLLING ROADBLOCK OPERATIONS (EXAMPLE)

NOTE: OPERATIONS PLAN TO BE DETERMINED BY HIGHWAY PATROL.

DRAWING NOT TO SCALE




DESIGN	MZV	09/18	OKLAHOMA DEPARTMENT OF TRANSPORTATION GUY ENGINEERING SERVICES, INC. ROLLING ROADBLOCK DETAIL 2 STATE JOB NO. 24432(15) SHEET NO. T013 KAY I-35 BRIDGES US-60 TO OK-KS STATE LINE
DRAWN	DGD	09/18	
CHECKED	JRW	09/18	
APPROVED	JRW	09/18	
SQUAD			

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:33:50 PM
 V:\16-1070E-BR Raising Over I-35, Kcy, 1840, HNTB\CIV3D\PLANS\NORTH\1070-NORTH SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:34:02 PM
 V:\16-1070E-BR Raising Over L-35, Kay, 1840, HNTB\CIV3D\PLANS\NORTH\1070-NORTH SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:34:11 PM
V:\16-1070E-BR Raising Over I-35, Kcy, 1840, HNTB\CIV3D\PLANS\NORTH\1070-NORTH SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:34:22 PM
 V:\16-1070E-BR Raising Over L-35, Kcy, 1840, HNTB\CIV3D\PLANS\NORTH\1070-NORTH SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Friday, October 26, 2018 9:13:44 AM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTBE CIV3D\PLANS\1070-NORTH SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Friday, October 26, 2018 9:14:28 AM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTBE\CIV\3D\PLANS\NORTH\1070-NORTH SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:34:51 PM
 V:\16-1070E-BR Raising Over L-35.Kay.1840.HNTB\CIV3D\PLANS\NORTH\1070-NORTH SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE





Thursday, October 25, 2018 12:56:38 PM
 V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTBE\CIV3D\PLANS\1070-NORTH SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE




Thursday, October 25, 2018 12:57:31 PM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTBE\CIV3D\PLANS\1070-NORTH SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






**CAUTION
FIBER OPTIC
CROSSING**



Wednesday, October 24, 2018 1:35:21 PM
V:\16-1070E-BR Raising Over I-35.Kay.1840.HNTB\CIV3D\PLANS\NORTH\1070-NORTH SECTIONS.dwg




DESCRIPTION	REVISIONS	DATE



BEGIN HIGHLAND AVE




Wednesday, October 24, 2018 1:35:43 PM
 V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HIGHLAND\1070-HIGHLAND SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:35:50 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HIGHLAND\1070-HIGHLAND SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:36:00 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HIGHLAND\1070-HIGHLAND SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:36:10 PM
V:\E-16-1070E-BR Raising Over I-35, Kcy, 1840, HNTB\CIV3D\E-PLANS\E-HIGHLAND\1070-HIGHLAND SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Friday, October 26, 2018 9:34:33 AM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTBE CIV\3D\PLANS\16-HIGHLAND\1070-HIGHLAND SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Thursday, October 25, 2018 1:00:08 PM
V:\16-1070E BR Raising Over I-35, Kgy, 1840, HNTBE CIV3D\PLANS\HIGH-LAND\1070-HIGHLAND SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:36:40 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\F\PLANS\F\HIGHLAND\1070-HIGHLAND SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE




Thursday, October 25, 2018 1:00:51 PM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTBE CIV3D\PLANS\16-HIGHLAND\1070-HIGHLAND SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE




Thursday, October 25, 2018 10:08 PM
V:\16-1070E BR Raising Over I-35, Kgy, 1840, HNTBE CIV3D\PLANS\16-HIGHLAND\1070-HIGHLAND SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






END HIGHLAND AVE
 32+00.00



STA. 26+95.57 TO STA. 27+15.57 RT
 TRANSITION FROM 1:2 TO 1:3
 31+50.00




Wednesday, October 24, 2018 1:37:10 PM
 V:\16-1070E-BR Raising Over I-35, Kcy, 1840, HNTB\CIV3D\PLANS\HIGHLAND\1070-HIGHLAND SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:37:34 PM
 V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV\3D\PLANS\HARTFORD\1070-HARTFORD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:37:46 PM
 V:\16-1070E-BR Raising Over L-35, Kay, 1840, HNTB\CIV3D\PLANS\HARTFORD\1070-HARTFORD\SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:37:56 PM
 V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HARTFORD\1070-HARTFORD\SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:38:05 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HARTFORD\1070-HARTFORD\SECTION\1070-HARTFORD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Monday, October 29, 2018 8:01:51 AM
V:\16-1070E BR Raising Over I-35, Kcy, 1840, HNTBE CIV3D\PLANS\HARTFORD\1070-HARTFORD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:38:25 PM
 V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HARTFORD\1070-HARTFORD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:38:35 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HARTFORD\1070-HARTFORD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:38:45 PM
 V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HARTFORD\1070-HARTFORD\SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE




Wednesday, October 24, 2018 1:38:55 PM
V:\E-16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\E\PLANS\HARTFORD\1070-HARTFORD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:39:05 PM
 V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HARTFORD\1070-HARTFORD\1070-HARTFORD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:39:15 PM
 V:\16-1070E-BR Raising Over L-35, Kay, 1840, HNTB\CIV3D\PLANS\HARTFORD\1070-HARTFORD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:39:40 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\COLEMAN\1070-COLEMAN SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:39:51 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\COLEMAN\1070-COLEMAN SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:40:01 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\F\PLANS\COLEMAN\1070-COLEMAN SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:40:11 PM
V:\16-1070E-BR Raising Over L-35, Kay, 1840, HNTB\CIV3D\PLANS\COLEMAN\1070-COLEMAN SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE





Friday, October 26, 2018 9:41:01 AM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV\3D\PLANS\COLEMAN\1070-COLEMAN SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE




Wednesday, October 24, 2018 1:40:31 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\COLEMAN\1070-COLEMAN SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






STA. 79+64.63 TO STA. 79+84.63
TRANSITION FROM 1:2 TO 1:3



**CAUTION
FIBER OPTIC
CROSSING**




Wednesday, October 24, 2018 1:40:41 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\F\PLANS\COLEMAN\1070-COLEMAN SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:40:51 PM
 V:\E-16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV\3D\PLANS\COLEMAN\1070-COLEMAN SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:41:01 PM
V:\16-1070E-BR Raising Over I-35, Ky, 1840, HNTB\CIV3D\PLANS\COLEMAN\1070-COLEMAN SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:41:11 PM
 V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\COLEMAN\1070-COLEMAN SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Thursday, October 25, 2018 1:30:35 PM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\CHRYSLER\1070-CHRYSLER SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE




Thursday, October 25, 2018 1:31:14 PM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTBE\CIV\3D\PLANS\F\CHRYSLER\1070-CHRYSLER SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE




Thursday, October 25, 2018 1:57:21 PM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTBE\CIV3D\PLANS\CHRYSLER\1070-CHRYSLER SECTIONS.dwg


DESCRIPTION	REVISIONS	DATE



76+85.89






76+50.00



76+45.60




Wednesday, October 24, 2018 1:42:06 PM
V:\E-16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\E-PLANSET\CHRYSLER\1070-CHRYSLER SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Friday, October 26, 2018 9:43:22 AM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV\3D\PLANS\F\1070-CHRYSLER SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Friday, October 26, 2018 9:45:25 AM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV\3D\PLANS\CHRYSLER\1070-CHRYSLER SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:42:36 PM
 V:\E-16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\CHRYSLER\1070-CHRYSLER SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:42:46 PM
 V:\E-16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\E-PLAN\SE\CHRYSLER\1070-CHRYSLER SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE




Wednesday, October 24, 2018 1:42:56 PM
 V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\CHRYSLER\1070-CHRYSLER SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:43:06 PM
 V:\E-16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\E-PLANSET\CHRYSLER\1070-CHRYSLER SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:43:16 PM
 V:\E-16-1070E-BR Raising Over L-35, Kay, 1840, HNTB\CIV3D\PLANS\CHRYSLER\1070-CHRYSLER SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE





Wednesday, October 24, 2018 2:26:35 PM
 V:\16-1070E-BR Raising Over L-35, Ky, 1840, HNTB\CIV3D\PLANS\FERGUSON\1070-FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE




Thursday, October 25, 2018 1:36:44 PM
 V:\16-1070E BR Raising Over I-35, Kgy, 1840, HNTB\CIV\3D\PLANS\FERGUSON\1070-FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






**CAUTION
POWER
CROSSING**






Wednesday, October 24, 2018 1:44:01 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\FERGUSON\1070-FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:44:11 PM
V:\16-1070E-BR Raising Over L-35, Kay, 1840, HNTB\CIV3D\PLANS\FERGUSON\1070-FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:44:21 PM
 V:\16-1070E-BR Raising Over I-35, Kcy, 1840, HNTB\CIV3D\PLANS\FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:44:31 PM
 V:\E-16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\FE PLANS\FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:44:41 PM
 V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:44:51 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Friday, October 26, 2018 9:49:45 AM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTBE\CIV\3D\PLANS\FERGUSON\1070-FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE



Wednesday, October 24, 2018 1:45:11 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\FERGUSON SECTIONS.dwg




DESCRIPTION	REVISIONS	DATE



**CAUTION
FIBER OPTIC
CROSSING**




Wednesday, October 24, 2018 1:45:21 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV\3D\PLANS\FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:45:31 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:45:41 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV\3D\PLANS\FERGUSON\1070-FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:45:51 PM
V:\E-16-1070E-BR Raising Over L-35, Kay, 1840, HNTB\CIV\3D\PLANS\FERGUSON\1070-FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:46:01 PM
V:\16-1070E-BR Raising Over L-35, Kay, 1840, HNTB\CIV3D\PLANS\FERGUSON\1070-FERGUSON SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:46:22 PM
 V:\16-1070E-BR Raising Over I-35, Kcy, 1840, HNTB\CIV3D\PLANS\16-1070-ADOBE SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:46:31 PM
V:\16-1070E-BR Raising Over I-35, Kcy, 1840, HNTB\CIV\3D\PLANS\1070-ADOBE SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:46:41 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\FIPLANS\FIADOBE\1070-ADOBE SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Friday, October 26, 2018 9:51:59 AM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV\3D\PLANS\ADOBE\1070-ADOBE SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Friday, October 26, 2018 9:53:51 AM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV\3D\PLANS\1\ADOBE SECTION.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:47:11 PM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTB\CIV3\3D\PLANS\FI_ADOBE\1070-ADOBE SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:47:21 PM
 V:\16-1070E-BR Raising Over I-35, Kcy, 1840, HNTB\CIV3D\FI\ANS\FI_1070-ADOBE SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE



Wednesday, October 24, 2018 1:47:31 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\F\PLANS\F\ADOBE\1070-ADOBE SECTIONS.dwg


DESCRIPTION	REVISIONS	DATE





Wednesday, October 24, 2018 1:47:41 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\FI_ADOBE\1070-ADOBE SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE

Wednesday, October 24, 2018 1:47:51 PM
 V:\E-16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\FI\ANS\FI_ADOBE\1070-ADOBE SECTIONS.dwg






DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:48:14 PM
V:\16-1070E BR Raising Over I-35.Kay.1840.HNTB\CIV3D\PLANS\HOME\1070 - HOME SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:48:26 PM
V:\16-1070E-BR Raising Over I-35, Ky, 1840, HNTB\CIV3D\PLANS\HOME\1070 - HOME SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:48:36 PM
 V:\16-1070E-BR Raising Over I-35.kcy, 1840, HNTB\CIV3D\PLANS\HOME\1070 - HOME SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:48:46 PM
 V:\16-1070E-BR Raising Over I-35.kay_1840_HNTB\CIV3D\PLANS\HOME\1070 - HOME SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:48:56 PM
 V:\16-1070E-BR Raising Over I-35_Kay_1840_HNTB\CIV3D\PLANS\HOME\1070 - HOME SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:49:07 PM
 V:\16-1070E-BR Raising Over I-35_Kay_1840_HNTB\CIV3D\PLANS\HOME\1070 - HOME SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:49:16 PM
 V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HOME\1070 - HOME SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:49:27 PM
 V:\16-1070E-BR Raising Over I-35.Kay.1840.HNTBF\CIV3D\PLANS\HOME\1070 - HOME SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE





Wednesday, October 24, 2018 1:49:37 PM
 V:\16-1070E-BR Raising Over I-35_Kay_1840_HNTB\CIV3D\PLANS\HOME\1070 - HOME SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE




Wednesday, October 24, 2018 1:49:47 PM
 V:\E-16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HOME\1070 - HOME SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE




Wednesday, October 24, 2018 1:49:57 PM
 V:\E-16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\HOME\1070 - HOME SECTIONS.dwg


DESCRIPTION	REVISIONS	DATE



74+50.00



74+00.00






BEGIN INDIAN ROAD

73+50.00




Friday, October 26, 2018 10:07:37 AM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTBE CIV3D\PLANS\INDIAN\1070-INDIAN ROAD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:50:25 PM
V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\PLANS\INDIAN\1070-INDIAN ROAD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:50:35 PM
 V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV\3D\PLANS\INDIAN\1070-INDIAN ROAD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Friday, October 26, 2018 9:55:43 AM
V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTBE CIV3D\PLANS\INDIAN\1070-INDIAN ROAD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Friday, October 26, 2018 9:57:21 AM
 V:\16-1070E BR Raising Over I-35, Kay, 1840, HNTBE CIV3D\PLANS\INDIAN RD\1070-INDIAN ROAD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE






Wednesday, October 24, 2018 1:51:05 PM
 V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\F\PLANSE\INDIANE\1070-INDIAN ROAD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE



Wednesday, October 24, 2018 1:51:15 PM
 V:\16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\FI PLAN\SE\INDIAN\1070-INDIAN ROAD SECTIONS.dwg

DESCRIPTION	REVISIONS	DATE



Wednesday, October 24, 2018 1:51:25 PM
V:\E-16-1070E-BR Raising Over I-35, Kay, 1840, HNTB\CIV3D\E-PLANS\INDIAN\1070-INDIAN ROAD SECTIONS.dwg